




US Army Corps
of Engineers
Office of the Chief
of Engineers


EP 1110-1-8
Volume 2
June 1981

Construction Equipment Ownership and Operating Expense Schedule

Region II



Regions for the Construction Equipment Ownership and Operating Expense Schedule



DAEN-CWE-BA
DAEN-MPE-S

DEPARTMENT OF THE ARMY
US Army Corps of Engineers
Washington, DC 20314

EP 1110-1-8
Volume 2

Pamphlet
No. 1110-1-8

15 June 1981


Engineering and Design
CONSTRUCTION EQUIPMENT OWNERSHIP
AND OPERATING EXPENSE SCHEDULE

1. Purpose. This pamphlet establishes predetermined equipment ownership and operating expense rates for use in preparation of estimates and in pricing negotiated procurements requiring independent Government estimates.
2. Applicability. This pamphlet applies to all field operating activities having either military or civil works responsibilities for construction contracts in Region II which includes the following states:

Delaware	Maryland
District of Columbia	Michigan(lower peninsula)
Illinois(East of U.S. Hwy. 51)	Ohio
Indiana	Virginia
Kentucky(East of U.S. Hwy. 51)	West Virginia

3. General. The rates and percentages shown in this pamphlet are based on equipment in sound workable condition owned or controlled and furnished by a contractor or subcontractor. These rates and percentages do not include allowances for operating labor, mobilization or demobilization costs, overhead, or profit, and do not represent rental charges for those in the business of renting equipment. The rates included in this pamphlet are based on construction equipment purchased new on 1 July 1979. The percentages for marine equipment provide an allowance for ownership expenses only. This pamphlet will be updated annually or more frequently if necessary.

FOR THE COMMANDER:



FORREST W. GAY, III
Colonel, Corps of Engineers
Chief of Staff

DAEN-CWE-BA
DAEN-MPE-S

DEPARTMENT OF THE ARMY
US Army Corps of Engineers
Washington, DC 20314

EP 1110-1-8
(Vol. 2)

Engineer Pamphlet
No. 1110-1-8

15 June 1981

Engineering and Design
CONSTRUCTION EQUIPMENT OWNERSHIP
AND OPERATING EXPENSE SCHEDULE

Table of Contents

	<u>Paragraph</u>	<u>Page</u>
CHAPTER 1. INTRODUCTION		
Purpose-----	1-1	1-1
Applicability-----	1-2	1-1
References-----	1-3	1-1
General-----	1-4	1-1
Use-----	1-5	1-1
CHAPTER 2. METHODOLOGY		
General-----	2-1	2-1
Construction Equipment-----	2-2	2-1
Marine Equipment-----	2-3	2-11
CHAPTER 3. RATE SCHEDULE		
Introduction-----	3-1	3-1
Hourly Equipment Ownership and Operating Expense-----	3-2	3-1
Table 3-1. Hourly Equipment Ownership and Operating Expense		3-5
Table 3-2. Equipment Age Adjustment Factors for Ownership Costs-----		3-87
Table 3-3. Equipment Age Adjustment Factors for Standby Costs-----		3-91
Table 3-4. Shift Adjustment Factors for Ownership Costs-----		3-95

EP 1110-1-8
(Vol. 2)
15 Jun 81

	<u>Paragraph</u>	<u>Page</u>
APPENDIX A. REFERENCES	A-1	
APPENDIX B. AREA FACTORS	B-1	
APPENDIX C. GUIDE FOR SELECTING OPERATING CONDITIONS	C-1	
APPENDIX D. EQUIPMENT HOURLY EXPENSE CALCULATION FACTORS	D-1	
APPENDIX E. SALVAGE AND REPAIR INDEXES FOR CONSTRUCTION EQUIPMENT	E-1	
APPENDIX F. TIRE LIFE AND TIRE WEAR FACTORS	F-1	
APPENDIX G. EQUIPMENT EXTRAS	G-1	

CHAPTER 1

INTRODUCTION

1-1. Purpose. This pamphlet establishes predetermined equipment ownership and operating expense rates for use in preparation of estimates and in pricing negotiated procurements requiring independent Government estimates.

1-2. Applicability. This pamphlet applies to all field operating activities having either military or civil works responsibilities for construction contracts for work in Region II, which includes the following states:

Delaware	Maryland
District of Columbia	Michigan (lower peninsula)
Illinois (East of U.S. Hwy. 51)	Ohio
Indiana	Virginia
Kentucky (East of U.S. Hwy. 51)	West Virginia

1-3. References. See APPENDIX A.

1-4. General. The rates and percentages shown in this pamphlet are based on equipment in sound workable condition owned or controlled and furnished by a contractor or subcontractor. These rates and percentages do not include allowances for operating labor, mobilization or demobilization costs, overhead, or profit, and do not represent rental charges for those in the business of renting equipment. The rates included in this pamphlet are based on construction equipment purchased new on 1 July 1979. The percentages for marine equipment provide an allowance for ownership expenses only. This pamphlet will be updated annually or more frequently if necessary.

1-5. Use. This pamphlet shall be used as the basis for estimating equipment costs for all construction contracts (including dredging) and modifications requiring an independent Government estimate. This pamphlet shall also be used in pricing of contract modifications over \$25,000 when:

a. Cost or pricing data is not required.

b. Cost or pricing data is required and actual cost data to support either ownership or operating costs for each piece of equipment or equipment groups of similar serial and series is not available.

EP 1110-1-8

(Vol. 2)

15 Jun 81

c. Cost or pricing data is required and available but all or part of the data is determined not to be in accordance with the cost principles of the Defense Acquisition Regulations (DAR).

CHAPTER 2

METHODOLOGY

2-1. General. This pamphlet provides hourly use rates for construction equipment and annual ownership percentages for marine plant and equipment. The methodology used to compute the hourly use rates for construction equipment is provided in paragraph 2-2. The methodology used to compute the annual ownership percentages for marine equipment is provided in paragraph 2-3.

2-2. Construction Equipment.

a. General. The total hourly rates include all costs of owning and operating equipment except operating labor and overhead expenses. The ownership portion of the rate consists of allowances for depreciation and cost of facilities capital. Operating costs include allowances for: fuel; filters, oil and grease; servicing the equipment; repair and maintenance; and tire wear and tire repair. Area factors used to compute the hourly equipment ownership and operating expenses are provided in APPENDIX B.

b. Operating Conditions.

(1) Equipment rates have been computed for both "Average" and "Severe" working conditions. "Difficult" conditions are the arithmetic mean of "Average" and "Severe" rates. Where only the "Average" rate is shown, the one rate will apply for all conditions.

(2) Average, difficult, or severe conditions in accordance with contract specifications are determined by the Contracting Officer on the basis of supporting evidence and in general accordance with the "Guide for Selecting Operating Conditions" in APPENDIX C. Difficult conditions are those lying midway between average and severe. Evaluation of operating conditions for equipment not listed in APPENDIX C will be consistent with the examples shown in the "guide."

c. Ownership Costs. The ownership portion of the rate consists of allowances for depreciation and cost of facilities capital and is computed from a predetermined "equipment cost." "Equipment cost" is based on the total catalog price for the equipment, including extras normally purchased, and required safety features. A 7.5 percent discount is taken for all equipment except highway trucks which are discounted

17.5 percent. Freight and sales tax are added to the discounted price to arrive at the predetermined "equipment cost."

(1) Depreciation.

(a) Depreciation was computed using the straight-line method and the hourly rate was determined by dividing the "Depreciation Value" ("equipment cost," less tire cost and estimated salvage) by the expected normal life of the equipment in hours.

(b) Salvage value for the used equipment was determined from the "Handbook of New and Used Construction Equipment Values" (Green Guide) and advertisements of used equipment for sale displayed in current engineering and construction magazines. The salvage value percentages used for each type of equipment are listed in APPENDIX D (column "SLV") as a percent of the "equipment cost" and are equal for both "Average Condition" and "Severe Condition." The percentages are adjusted by the economic adjustment factor (EAF) to bring the salvage value up to current price levels. The factor is obtained from APPENDIX E and is equal to the economic index for the current year divided by the economic index for the year the equipment was purchased new. The ownership costs shown in TABLE 3-1 represent the hourly costs for equipment purchased new approximately two years ago.

(c) Tire cost was considered to be an operating expense and was subtracted from the "equipment cost" before computing depreciation. The tire cost is that cost at the time the equipment was purchased new.

(d) The expected normal life of the equipment was established from manufacturers' or equipment associations' recommendations. The expected normal life in hours is given in APPENDIX D. (Column "LFE" in thousand Hrs.)

(e) Annual average operating hours have been established for equipment operation within the region covered by this pamphlet. Average hours of use per year were determined by reducing the maximum available hours (40 hours per week, 52 weeks per year) to allow for lost time due to weather, employee's holidays, equipment maintenance and repairs, mobilization and demobilization and miscellaneous down time. The hours of use per year shown in APPENDIX B is equivalent to one year's life for single shift operation.

(2) Cost of Facilities Capital ("CFC").

(a) The cost of facilities capital (CFC) as defined in DAR 15-205.50 and CAS 414 is included in the use rates. This

cost was computed by multiplying the cost of money rate (14.625%) determined by the Secretary of the Treasury pursuant to P.L. 92-41 (85 Stat. 97) by the average value of equipment and prorating the result over the annual operating hours. This cost of money rate was discounted to 11.6% to avoid duplication when applying markups for overhead and profit.

$$CFC/hr = \frac{[(N-1)(1+S)+2]}{2N} \frac{\text{(Equipment Cost)}}{\text{(Work Hrs per Year)}} \text{ (11.6\%)}$$

Where: N = No. of years in depreciation period
S = Salvage Value Factor

(b) The salvage value is determined by multiplying the salvage value percentage in APPENDIX D times the economic adjustment factor as explained in paragraph 2-2.c.(1)(b).

(3) Licenses, Taxes, Storage and Insurance. License fees, taxes, storage and insurance costs are considered indirect costs and are not included in the use rates. If the Contractor normally allocates these costs directly to a particular item of work, an allowance for these costs may be made.

d. Operating Cost.

(1) General. The total operating cost is the sum of the costs for fuel, filters, oil and grease, servicing the equipment, repairs and maintenance, tire wear and tire repair.

(2) Fuel Consumption Cost.

(a) The fuel consumption in gallons per BHP-hour is listed in TABLE 3-1 for both "Average" and "Severe" conditions. The fuel consumption rate for "Severe Conditions" is 30 percent greater than the "Average Conditions" rate. Fuel consumption is computed by using the following formula:

$$\text{Fuel consumption(gal/hr)} = \frac{\text{BHP} \times \text{HP Factor} \times \text{Lbs Fuel per BHP-HR}}{\text{Wt of Fuel per Gallon}}$$

where:

(1) BHP as used herein is the net brake HP of the engine at the flywheel under the following conditions: (1) at sea level; and (2) at full-load governed speed with engine fully equipped with generator, fan, air cleaner, and other regular equipment.

(2) Gasoline consumption = 0.62 lbs per BHP-hr

(3) Diesel consumption = 0.42 lbs per BHP-hr

(4) Gasoline wt = 6.1 lbs per gallon

(5) Diesel wt = 7.1 lbs per gallon

(b) Electricity consumption = HP factor x 1 KW per electric HP hour. This assumes that electric motor uses 1 KW/HP considering all inefficiencies.

(c) It is necessary to modify the rated horsepower as engines and motors in actual production do not work at their full rated horsepower at all times. The horsepower factor used in the fuel and electricity consumption formulas represents the average percent of full rated horsepower being utilized by the engine. The "HP Factors" are given in APPENDIX D.

(d) The cost per gallon for gasoline and diesel fuel and the cost per kilowatt hour for electricity used to compute the hourly fuel and electricity costs are shown in APPENDIX B. The hourly fuel costs for all gasoline powered equipment and diesel powered highway trucks and truck crane carriers includes an allowance for federal and state road taxes.

(e) The estimated hourly fuel costs included in TABLE 3-1 are also noted separately for both average and severe conditions. Hourly fuel costs will be adjusted in the event the averaged (weighted) fuel prices (f.o.b. jobsite) vary by more than 10 percent above or below the price assumed in the basic computation. For example, if the price per gallon should increase by 15 percent, then 15 percent of the hourly fuel cost will be added to the total hourly rate. The Contractor will be required to furnish copies of all fuel supply contracts and invoices to the Government. Request for upward adjustment in the rates will be considered only where fuel is to be supplied by recognized distributors.

(3) Filters, Oil and Grease Costs (FOG). "FOG" costs are computed as either a percentage of the hourly fuel costs (see APPENDIX D) or, if the equipment has no engine, a reasonable hourly cost is included. Labor and equipment costs for fueling, greasing, and servicing are included in the rate. The "FOG" allowance for cranes, draglines, backhoes, and shovels (except self-propelled hydraulic cranes) has been reduced to allow for servicing normally performed by the oiler assigned to the piece of equipment.

(4) Maintenance and Repair Costs.

(a) The cost of maintenance and repairs includes all expenses incurred for parts, labor, fringe benefits, shop overhead, supporting facilities, outside specialty services, and maintenance equipment. The basic hourly costs are computed as follows:

$$\text{Repairs/Hr} = \frac{(\text{New Equipment Cost} - \text{Tire Cost}) (\text{Repairs \%})}{\text{Life in Hrs}}$$

The maintenance and repair cost percentages are given in APPENDIX D (Column "RPR"). The tire cost is the cost of the tires when the equipment was purchased new.

(b) The basic hourly rate for maintenance and repairs is adjusted by two multiplying factors so that actual costs and site conditions are considered.

(1) Economic Adjustment Factor. The economic adjustment factor (EAF) is used to adjust the basic hourly rate to current price levels. The indexes in APPENDIX E are used to develop this factor which is equal to the economic index for current year divided by the economic index for the year the piece of equipment was purchased new.

(2) Labor Adjustment Factor. The labor adjustment factor (LAF) is used to adjust the repairs percentage (RPR) to account for variations in labor costs. The factor for the area covered by this pamphlet is given in APPENDIX B.

(5) Hourly Tire Cost.

(a) Tires included on rubber-tired equipment are the bias ply tires suggested as standard equipment by the equipment manufacturers.

(b) The hourly tire cost equals the current cost of new tires plus the cost of one recapping divided by the expected life of the new tires plus the life of the recapped tires. It has been determined that a recap costs approximately 50 percent of the new tire cost and that the life of a new tire plus recapping will equal approximately 1.8 times the "useful life" of a new tire.

(c) The useful tire life was determined from the method and tables in the manual prepared by Terex Division of General Motors "Production and Cost Estimating of Material Movement with Earthmoving Equipment," with the exception that the maximum tire life has been assumed to be as indicated in APPENDIX F. A

sample computation of the tire wear factors for off-highway haul units is given in APPENDIX F.

(d) The tire wear factor for front tires for belt loaders shown in APPENDIX D is used to provide an hourly allowance for belt wear of the conveyor belt.

(6) Tire Repair Costs. Tire repairs are computed as 15 percent of the hourly tire wear cost.

e. Standby. The standby rate is computed from the average condition rates by allowing the full "CFC" hourly cost plus one-fourth of the hourly depreciation. No more than 8 hours of standby will be paid during a 24-hour day, nor more than 40 hours per week. Standby time will not be allowed unless the equipment has been in idle status in excess of 16 hours during a 24-hour day. Likewise, standby will not be allowed during periods when the equipment would have otherwise been in idle status. Actual operating time during a week will be credited against the 40 hours maximum standby allowance.

f. Working Hours. The hourly use rates shown in TABLE 3-1 are computed on the basis of a 40-hour work week. When the Contractor works more than 40 hours per week the cost for "CFC" will be excluded from the hourly rate for those hours in excess of 40 hours per week. The hourly use rates for work weeks greater than 40 hours can be computed as shown in the sample computations or may be calculated by the use of TABLE 3-3.

g. Sample Computation. A sample computation has been provided in Figure 2-1 to illustrate how the hourly use rates in TABLE 3-1 were computed using the methodology stated in this pamphlet. When an hourly rate for a specific piece of equipment must be computed by the methods in Figure 2-1, the procedure given shall be followed.

FOR ILLUSTRATION PURPOSES ONLY

Local reproduction authorized - blank masters available from local FMO

CONSTRUCTION EQUIPMENT HOURLY OWNERSHIP AND OPERATING RATE WORK SHEET
(EP 1110-1-8)

1. REQUIRED DATA

a. Unit Number 2740

(1) Equipment Description Lorain Truck Crane 50-Ton
(2) Model and Series MC-550A W/160' Boom
(3) Year Purchased 1979 (4) Year Purchased New 1979
(5) Equipment Horsepower 115 (6) Carrier Horsepower 246
(7) Fuel Type Diesel/Diesel (8) Shipping Weight 111,100 Lbs.
(9) Tire Size: Front-1400x20-18PR Drive-1400x20-18PR Trailing- N/A

b. Key Number from APPENDIX D 225

(1) Condition Average
(2) Salvage Value % 20% (3) Life 18,000 Hrs.
(4) Equipment Fuel Factor .038 (5) Carrier Fuel Factor .006
(6) FOG Factor: Gas N/A Diesel .26 Electric N/A
(7) Tire Wear Factor: Front .95 Drive .90 Trailing N/A
(8) Repairs Cost Factor .60

2. EQUIPMENT COST

a. List Price When New (including extras) = \$ 267,037.00

(1) Discount: (List Price) x *7.5% *(17.5% for Highway Trucks)

$$= (\$ 267,037.00) \times *.075 = (-) \$ 20,027.75$$

(2) Freight: (Shipping Weight) x (Prep. and Del. Rate)
From 1-a-(8) From APPENDIX B

$$= (1111 \text{ Cwt.}) \times (\$ 1.40) = (+) \$ 1,556.40$$

b. Subtotal: Summation of Part a. (Use actual cost when available) = \$ 248,564.62

(1) State Sales Tax: (Subtotal) x (Tax Rate)
From 2-b

$$= (\$ 248,564.62) \times (.04) = (+) \$ 9,942.58$$

c. Equipment Cost: Summation of Part b. (Use actual cost when available) = \$ 258,507.20

CONSTRUCTION EQUIPMENT HOURLY OWNERSHIP AND OPERATING RATE WORK SHEET (Continued)

3. LIFE (N)

$$\text{(Life From 1-b-(3))} + \text{(Hours Use/Year From APPENDIX B)} \\ = (\underline{18,000} \text{ Hrs}) + (\underline{1500} \text{ Hrs/Yr}) \quad \underline{12.0} \text{ Yrs.}$$

4. ECONOMIC ADJUSTMENT FACTOR (EAF)

$$\text{(Economic Index for Present) + (Economic Index for Year Purchased New From APP. E)} \\ \text{Year From APPENDIX E} \quad \text{Purchased New From APP. E} \\ = (\underline{3.044}) + (\underline{2512}) \quad = \underline{1.212} \text{ (EAF)}$$

5. SALVAGE VALUE FACTOR (S)

$$\text{(Salvage Factor) x (EAF)} \\ \text{From 1-b-(2)} \quad \text{From 4} \\ = (\underline{.20}) \times (\underline{1.212}) \quad = \underline{.242} \text{ (S)}$$

6. OWNERSHIP COSTS

a. Depreciation:

$$\text{Equipment} \quad \text{Life} \\ \text{[(Cost From) x [1.0 - (S From)]} \quad \text{[From 2-c]} \\ \text{2-c} \quad \text{5} \quad \text{When New} \quad \text{1-b-(3)} \\ = [(\underline{\$258,507}) \times [1.0 - (\underline{.242})]] - (\underline{\$5,698}) \div (\underline{18,000} \text{ Hr}) = \$ \underline{10.57} / \text{Hr.}$$

b. Cost of Facilities Capital (CFC):

$$\text{Life} \quad \text{Life} \\ (1) [[(From) - 1.0] \times [(S From) + 1.0] + 2.0] \div [(From) \times 2.0] \\ 3 \quad 5 \quad 3 \\ = [(\underline{12.0} \text{ Yrs}) - 1.0] \times [(\underline{.242}) + 1.0] + 2.0] \div [(\underline{12.0} \text{ Yrs}) \times 2.0] = \underline{.6526}$$

$$\text{Equipment} \quad \text{Average} \quad \text{CFC Factor} \quad \text{Hrs Use/} \\ (2) \text{[(Cost From) x (Value Factor) x (From Para.)} \quad \text{From 6-b-(1)} \quad \text{2-2.c.(2)} \quad \text{Yr From } \\ \text{2-c} \quad \text{From 6-b-(1)} \quad \text{APP. B} \\ = (\underline{\$258,507}) \times (\underline{.6526}) \times (\underline{.116}) \div (\underline{1,500} \text{ Hrs/Yr}) \quad = \$ \underline{13.05} / \text{Hr.}$$

c. Total Hourly Ownership: (Sum 6-a + 6-b-(2)) = \$ 23.62 / Hr.

CONSTRUCTION EQUIPMENT HOURLY OWNERSHIP AND OPERATING RATE WORK SHEET (Continued)

7. OPERATING COSTS

a. Fuel Costs:

(1) Equipment: (Equip Fuel Factor) x (H.P. From) x (Fuel Cost)
From 1-b-(4) 1-a-(5) Per Gal.

$$=(.038) \times (116 \text{ HP}) \times (\$ 1.05/\text{Gal}) = \$ 4.59/\text{Hr.}$$

(2) Carrier: (Carrier Fuel Factor) x (H.P. From) x (Fuel Cost)
From 1-b-(5) 1-a-(6) Per Gal.

$$=(.006) \times (246 \text{ HP}) \times (\$ 1.15/\text{Gal}) = \$ 1.70/\text{Hr.}$$

(3) Total Fuel Costs: (Sum 7-a-(1), 7-a-(2)) = \$ 6.29/Hr.

b. FOG Costs:

(1) Equipment: (FOG Factor) x (Hourly Fuel Cost)
From 1-b-(6) From 7-a-(1)

$$=(.26) \times (\$ 4.59/\text{Hr}) = \$ 1.19/\text{Hrs.}$$

(2) Carrier: (FOG Factor) x (Hourly Fuel Cost)
From 1-b-(6) From 7-a-(2)

$$=(.26) \times (\$ 1.70/\text{Hr}) = \$.44/\text{Hr.}$$

(3) Total FOG Costs: (Sum 7-b-(1), 7-b-(2)) = \$ 1.63/Hr.

c. Repairs Cost:

(1) Repair Factor:

(Repairs Cost Factor) x (EAF) x (LAF From)
From 1-b-(8) From 4 APP. B

$$=(.60) \times (.212) \times (.99) = .720$$

(2) Hourly Repairs:

Equipment Life
[(Cost From) - (Tire Cost)] x (Repair Factor) + (From)
2-c When New From 7-c-(1) 1-b-(3)

$$=[(\$ 258,507) - (\$ 5,698)] \times (.720) + (\$ 18,000/\text{Hr}) = \$ 10.11/\text{Hr.}$$

CONSTRUCTION EQUIPMENT HOURLY OWNERSHIP AND OPERATING RATE WORK SHEET (Continued)

d. Tire Wear Costs:

$$(1) \text{ Front Tires: } 1.5 \times \frac{\text{Front Cost}}{(\text{Tires})} + [1.8 \times \frac{\text{F-Tire}}{(\text{Ftr Frm})} \times \frac{\text{Max Tire}}{(\text{Life Frm})}] \\ = 1.5 \times (\underline{\$ 2,423}) + [1.8 \times (\underline{.95}) \times (\underline{5,000 \text{ Hr}})] = \$ \underline{1.43} / \text{Hr.}$$

$$(2) \text{ Drive Tires: } 1.5 \times \frac{\text{Drive Cost}}{(\text{Tires})} + [1.8 \times \frac{\text{D-Tire}}{(\text{Ftr Frm})} \times \frac{\text{Max Tire}}{(\text{Life Frm})}] \\ = 1.5 \times (\underline{\$ 4,845}) + [1.8 \times (\underline{.90}) \times (\underline{5,000 \text{ Hr}})] = \$ \underline{.90} / \text{Hr.}$$

$$(3) \text{ Trailing Tires: } 1.5 \times \frac{\text{Trlg Cost}}{(\text{Tires})} + [1.8 \times \frac{\text{T-Tire}}{(\text{Ftr Frm})} \times \frac{\text{Max Tire}}{(\text{Life Frm})}] \\ = 1.5 \times (\underline{\$ \quad \quad \quad}) + [1.8 \times (\underline{\quad \quad \quad}) \times (\underline{\quad \quad \quad \text{ Hr}})] = \$ \underline{N/A} / \text{Hr.}$$

$$(4) \text{ Total Tire Wear Cost: } (\text{Sum 7-d-(1) thru (3)}) = \$ \underline{1.33} / \text{Hr.}$$

$$\text{e. Tire Repair Cost: } (\text{Tire Wear Frm 7-d-(4)}) \times 0.15$$

$$= (\underline{\$ 1.33}) \times 0.15 = \$ \underline{.20} / \text{Hr.}$$

$$\text{f. Total Operating Costs: } (\text{Sum 7-a thru 7-e}) = \$ \underline{19.56} / \text{Hr.}$$

8. TOTAL HOURLY RATES

$$\text{a. Single Shift Hourly Rate: } (40 \text{ Hours per Week})$$

(Ownership Costs Frm 6-c) + (Operating Costs Frm 7-f)

$$= (\underline{\$ 23.62 / \text{Hr}}) + (\underline{\$ 19.56 / \text{Hr}}) = \$ \underline{43.18} / \text{Hr.}$$

b. Hourly Rate for Other Work Shifts:

(Depreciation) + [(CFC Frm From 6-a 6-b-(2)) × 40 ÷ (Work Hrs Per Week) + (Operating Costs) Frm 7-f]

$$= (\underline{\$ 10.57 / \text{Hr}}) + [(\underline{\$ 13.05 / \text{Hr}}) \times 40 \div (\underline{60 \text{ Hr/Wk}})] + (\underline{\$ 19.56 / \text{Hr}}) = \$ \underline{38.83} / \text{Hr.}$$

c. Hourly Standby Rate:

(Depreciation) × 0.25 + (CFC Frm From 6-a 6-b-(2))

$$= (\underline{\$ 10.57 / \text{Hr}}) \times 0.25 + (\underline{\$ 13.05 / \text{Hr}}) = \$ \underline{15.69} / \text{Hr.}$$

2-3. Marine Equipment.

a. General. Hourly use rates for ownership and operating costs have not been developed for marine equipment since this type of equipment is normally custom designed and built. This section, however, presents the methodology for determining the ownership expense expressed as a percent of equipment value, which is defined as the actual acquisition cost plus any capital improvements. The annual percentages are shown in TABLE 2-1 for various types of equipment. When a type of equipment is not listed, the ownership expense percent may be determined by using the percentage listed for a similar type with the same expected life. Hourly ownership and operating expenses for any land-based equipment involved with the operation will be based on the methodology herein for construction equipment.

b. Ownership Cost. Ownership cost is based on the equipment value and equals the cost of depreciation and facilities capital. When cost or pricing data is available, the actual equipment value shall be used. Otherwise, the value of a similar piece of equipment may be used and, if necessary, adjusted so that capacity, size, and horsepower are properly considered.

(1) Depreciation. Depreciation is computed using the straight-line method and the annual rate is determined by dividing the depreciable value by the expected normal life of the equipment in years. When the actual age of a piece of equipment exceeds the normal life, one year shall be added to the actual age and the depreciation shall be recomputed. The depreciable value is the acquisition cost, plus any capital improvements, less estimated salvage. Costs for drydocking and major repairs, which occur periodically, are considered a part of operating costs and will be allocated on an equal annual basis over the years between such occurrences, in accordance with paragraph 15-205.20 of DAR.

(2) Cost of Facilities Capital (CFC). The cost of facilities capital (CFC) is computed as shown in paragraph 2-2.c, except that CFC is determined on an annual basis instead of an hourly basis and it is expressed here as an annual percentage factor.

$$CFC = \frac{[(N-1)(1+S) + 2]}{2N} (11.6\%)$$

where: N = No. of years in depreciation period
S - Salvage Value Factor

(3) The salvage value factor is expressed as a decimal and is shown in TABLE 2-1 for different items of equipment.

(4) Taxes, storage (layup), and insurance are considered indirect (overhead) costs or a part of operating costs (see paragraph 2-2.c.(3)). These are not included in ownership rates since they vary by geographic areas and with individual contractors and should not be duplicated in the estimate or submitted proposal.

(5) The expected life shown in TABLE 2-1 for shore pipeline and floating pipeline is based on average dredging conditions. When more severe conditions are encountered, such as the dredging of very abrasive sand or rock, the expected life should be decreased. Similarly when better than average conditions are encountered, such as dredging mud or silt, the expected life should be increased. In either case, the adjustment should be made only for the time required to dredge the exceptional material. When the dredged material is a combination of various types, a weighted average should be estimated and the expected life adjusted accordingly. The repair of pipelines during the economic life is considered a part of operating costs.

c. Annual Use. Marine equipment is normally operated 24 hours per day, 7 days per week, and costs are usually kept on a monthly basis. This is the preferred basis, but if an hourly or daily basis is used, the monthly cost should be divided by the actual number of hours or days the contractor is working. If actual time cannot be determined the monthly cost should be divided by 720 hours or 30 days. The number of months' use per year is of such a variable nature that it is established for each contract by including this factor in the clauses of the contract.

d. Standby. The standby rate is computed by allowing the full CFC monthly rate plus one-fourth of the monthly depreciation. In addition to the standby ownership rate, on dredges it may be necessary to include a small amount for operating costs to account for the operation of a diesel engine generator for power to operate pumps, navigation lights, etc. Standby will not be allowed during periods when the equipment would have otherwise been in idle status.

TABLE 2-1 ANNUAL OWNERSHIP EXPENSE FACTORS FOR MARINE EQUIPMENT

TYPE OF EQUIPMENT	LIFE (YRS)	SALVAGE VALUE FACTOR	PERCENT ANNUAL OWNERSHIP EXPENSE		
			DEPRE- CIATION	CFC	TOTAL
Hydraulic dredge, including hydraulic dredges used as Boosters:					
10-inch thru 14-inch	20	.05	4.75	6.37	11.12
16-inch thru 20-inch	25	.10	3.60	6.59	10.19
24-inch and over	30	.10	3.00	6.55	9.55
Booster & Barge:					
10-inch thru 14-inch	20	.05	4.75	6.37	11.12
16-inch thru 20-inch	25	.10	3.60	6.59	10.19
24-inch and over	30	.10	3.00	6.55	9.55
Dredge, Hopper	30	.10	3.00	6.55	9.55
Dredge, clamshell/ dragline	20	.05	4.75	6.37	11.12
Dredge, Dipper/Hyd Excav	25	.05	3.80	6.31	10.11
Bucket Dredge	30	.10	3.00	6.55	9.55
Dump Scows	20	.05	4.75	6.37	11.12
Barges:					
Fuel	20	.05	4.75	6.37	11.12
Water	20	.05	4.75	6.37	11.12
Equipment or Work	20	.05	4.75	6.37	11.12
Derrick	20	.10	4.50	6.64	11.14
Anchor	20	.05	4.75	6.37	11.12
Drill Boat or Barge	20	.10	4.50	6.64	11.14
Mooring Barge	20	.05	4.75	6.37	11.12
Tugs	20	.10	4.50	6.64	11.14
Tenders	20	.10	4.50	6.64	11.14
Launches	12	.05	7.92	6.55	14.47
Shore Pipeline (Average)	3	0	33.3	7.73	41.03
Floating Line:					
Pontoons	15	0	6.7	6.19	12.89
Pipeline/Joints (Avg)	10	0	10.0	6.38	16.38

CHAPTER 3

RATE SCHEDULE

3-1. Introduction. Hourly rates for construction equipment for both average and severe conditions are presented in TABLE 3-1. The rates may be adjusted or recomputed when (a) "Difficult Conditions" are specified by the contract, (b) actual acquisition cost is significantly different from the "Equipment Cost" shown, (c) age is different from that used, (d) license, taxes, storage and insurance costs are charged directly to an item of work, (e) fuel costs differ by more than 10% from the cost shown, and (f) work week exceeds 40 hours per week. Whenever one or more of these conditions exist, the rates may be adjusted using the tables in this chapter or computed as shown in the sample computations in Figure 2-1.

3-2. Hourly Equipment Ownership and Operating Expense.

a. Description.

(1) The following example illustrates how the equipment is listed in TABLE 3-1: The unit number 2710 is the identifying number of this piece of equipment in the input and output computer listings. The number 5530 is the model number of the equipment (American Model 5530 Truck Crane). The crane is rated at 75 tons and is equipped with a 170-foot boom. The crane has a 115-horsepower engine, the carrier has a 238-horsepower engine and both engines are diesel. The cost column reflects the pre-determined "equipment cost," used to compute the rates.

(2) The "total hourly rate" column includes all ownership and operating expenses, including fuel costs. The "Adjustable Elements" column shows ownership and fuel costs broken out of the total rate so they can be adjusted as indicated in CHAPTER 2 and 3. Operating costs may be determined by subtracting the ownership cost from the total hourly rate. The CWT column is the shipping weight of the equipment in hundredweight.

b. Truck Selection. Because of the large number of possible combinations of highway truck chassis and truck bodies, they are listed separately. To make an exact truck selection for a given set of hauling conditions would require lengthy calculations; however, for estimating purposes the selection can be made by using the GVW rating of the truck chassis. The combined weight of the truck chassis, the truck body and the payload must not exceed the GVW rating shown for the truck chassis.

c. Dozer Selection. Because of the various number of dozer and ripper combinations available for each crawler tractor the tractors and attachments are listed separately. Only the hourly expense for those attachments that are required to perform the work shall be allowed.

d. Equipment Extras. Equipment extras included on the major pieces of equipment in TABLE 3-1 are listed in APPENDIX G.

e. Equipment Not Listed. When an item of equipment is not listed in TABLE 3-1 the hourly rate may be determined by using the hourly rate listed for a similar piece of equipment or by proportioning a rate listed so that capacity, size, and horsepower are properly considered. When an hourly rate cannot be determined from TABLE 3-1, the rate will be calculated following the methodology outlined in CHAPTER 2.

f. Over-Age Equipment. When an item of equipment has exceeded the economic service life given in APPENDIX D, it is considered over-age and the hourly use rate will not exceed the rate for a piece of equipment that is not over age. An hourly rate for over-age equipment will be computed from TABLE 3-1 and the age adjustment tables or as shown in Figure 2-1 on the basis that the equipment is as old as possible without exceeding the "life" as shown in APPENDIX D.

g. Equipment Purchased Used. A detailed method for computing an hourly use rate for equipment purchased used has not been included in this pamphlet. The condition of the equipment at the time of purchase (extent of capital improvements, mechanical condition of drive train, previous hours of operation, etc.) is difficult or impossible to determine and to evaluate when computing an hourly use rate based on actual acquisition cost. When actual cost data in accordance with paragraph 1-5 is not available, an hourly use rate and standby rate for equipment purchased used will be computed on the basis that the equipment was purchased new by the contractor in the year it was manufactured.

h. Rate Adjustment Tables. The rate adjustment tables (TABLES 3-2, 3-3 and 3-4) should be used to adjust the hourly rates in TABLE 3-1 when the actual age of the equipment and working hours are to be considered. These tables may be used whenever information is available to indicate that the contractor's equipment is not the same age as the equipment listed in this pamphlet or when the hours worked have exceeded 40 hours per week. The rate adjustment tables have been developed from the equations used to calculate ownership and standby costs and it has been determined that they provide

reasonable adjustment factors to allow a short-cut method for computing an hourly use rate when actual conditions are considered. When cost or pricing data is available the rate adjustment tables may be used in lieu of a step-by-step rate computation for each item of equipment, provided that the equipment is equivalent in size, capacity, horsepower, etc. to the item listed in the pamphlet.




TABLE 3-1. HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE

CATEGORY INDEX

	<u>Page</u>
Aggregate Spreaders.....	3-9
Air Compressors - Portable.....	3-9
Air Tools - Jackhammers, Backfill Tampers, Sandblast Equip. and Concrete Vibrators.....	3-10
Asphalt Distributor.....	3-12
Asphalt Finishers.....	3-12
Brooms - Towed & Self-Propelled.....	3-12
Brush Chippers.....	3-13
Buckets	
Clamshell.....	3-13
Concrete.....	3-15
Dragline.....	3-16
Compactors - Manually Operated.....	3-19
Concrete Hauler (See Transit Mixers)	
Concrete Buggies.....	3-19
Concrete Pavers.....	3-19
Concrete Placers and Pumps.....	3-20
Cranes, Shovels, Backhoes & Draglines - Crawler Type.....	3-21
Cranes - Hydraulic	
Self-Propelled.....	3-28
Truck Mounted.....	3-29
Cranes - Truck Mounted.....	3-30
Dozers (See tractor, Crawler)	
Drills	
Blast Hole (Trac Drills).....	3-32
Core-Air-Column Mounted.....	3-32
Core-Skid Mounted.....	3-33
Rotary.....	3-33
Fork Lifts.....	3-34
Generator Electric Plants - Skid Mounted.....	3-35
Graders - Motor.....	3-36
Hoists.....	3-37
Hydraulic Excavators	
Crawler Mounted.....	3-38
Truck Mounted.....	3-41
Land Clearing Equipment.....	3-41

TABLE 3-1. HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE
(Continued)

CATEGORY INDEX (Continued)

	<u>Page</u>
Lighting Sets - Trailer Mounted.....	3-41
Loaders - Belt.....	3-42
Loaders - Front End Track Type.....	3-45
Loaders - Front End Wheel Type.....	3-47
Loader/Backhoe - Industrial Type Tractor.....	3-50
Loader/Backhoe - Crawler Type Tractor.....	3-50
Loader/Backhoe Attachments.....	3-51
Pile Extractors.....	3-51
Pile Hammers	
Diesel.....	3-51
Air or Steam	
Single Acting.....	3-52
Double Acting.....	3-52
Vibratory.....	3-53
Pipelayers.....	3-53
Pumps - Grout.....	3-54
Pumps - Water.....	3-54
Ripper & Hydr. Bank Sloper.....	3-56
Roller	
Rubber Tired, Self-Propelled.....	3-59
Rubber Tired, Towed.....	3-59
Sheeps Foot, Double Drum.....	3-60
Smooth Wheel, Self-Propelled.....	3-61
Vibratory, Towed.....	3-62
Vibratory, Self-Propelled.....	3-62
Sandblast Equipment (See Air Tools)	
Scrapers - Self-Propelled.....	3-63
Scrapers - Tractor Drawn.....	3-65
Tampers (See Compactors, Manually Operated)	
Tractor - Crawlers (Blades, Push Plates & Push Blocks are separate).....	3-66
Tractor - Wheel Type Dozers.....	3-71
Tractor - Farm Type.....	3-71
Trencher-Chain Type.....	3-71
Trencher-Wheel Type.....	3-72
Trucks - Highway (Chassis Only).....	3-72

TABLE 3-1. HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE
(Continued)

CATEGORY INDEX (Continued)

	<u>Page</u>
Truck Accessories (Add to Chassis)	
Dump Bodies (5 - 12 C.Y.).....	3-75
Flatbeds.....	3-76
Hoists.....	3-76
Crane - Hydraulic.....	3-77
Trailers	
Bottom Dump.....	3-75
End Dump.....	3-76
Flatbed.....	3-78
Lowboy (Flatbed).....	3-78
Tilt.....	3-79
Transit Mixers.....	3-79
Water Tank.....	3-79
Trucks - Off-Highway.....	3-80
Trucks - Water, Tractor Drawn.....	3-82
Wagons	
Bottom Dump.....	3-82
Rear Dump.....	3-83
Water Blaster.....	3-83
Water Tanks.....	3-84
Welders.....	3-84




TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT			
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.				
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL			
AGGREGATE SPREADER *****												
TOWED												
1005	WALES HANDY SPREADER SPREADS TO 2' DEPTH AND UP TO 10' WIDE	4,746	1.13		0.34	0.60	0.00			19		
1010	HI-WAY MOD R-1 SPREADS TO 3.5' DEPTH AND UP TO 12' WIDE	6,186	1.44		0.43	0.77	0.00			23		
SELF PROPELLED												
1020	ETHYRE TO 8' DEPTH & 13' WIDE	187 HP G	30,828	22.23		2.18	3.88	12.30		155		
1025	ETHYRE TO 8' DEPTH & 13' WIDE	123 HP D	34,421	12.57		2.44	4.34	3.87		160		
AIR COMPRESSORS PORTABLE ***** (HOSE NOT INCLUDED)												
ROTARY SCREW												
1040	SIZE 85 CFM QUIET 100 PSI	47 HP G	6,733	6.82		0.48	0.84	4.00		17		
1045	SIZE 85 CFM QUIET 100 PSI	38 HP D	9,541	4.13		0.69	1.19	1.52		20		
1050	SIZE 100 CFM QUIET 100 PSI	50 HP G	8,993	7.69		0.65	1.13	4.26		20		
1055	SIZE 100 CFM QUIET 100 PSI	42 HP D	10,788	4.62		0.77	1.34	1.68		23		
1060	SIZE 125 CFM QUIET 100 PSI	56 HP G	10,271	8.67		0.74	1.29	4.77		24		
1065	SIZE 125 CFM QUIET 100 PSI	47 HP D	12,055	5.17		0.86	1.50	1.88		26		
1070	SIZE 150 CFM QUIET 100 PSI	69 HP G	12,754	10.68		0.92	1.59	5.87		26		
1075	SIZE 150 CFM QUIET 100 PSI	70 HP D	14,983	7.01		1.08	1.87	2.79		28		
1080	SIZE 185 CFM QUIET 100 PSI	69 HP G	13,847	10.93		1.00	1.73	5.87		27		
1085	SIZE 185 CFM QUIET 100 PSI	70 HP D	16,327	7.31		1.17	2.03	2.79		29		

EP 1110-1-B
 (Vol. 2)
 15 Jun 81

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.			
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL		
AIR COMPRESSORS PORTABLE (CONT'D) ***** (HOSE NOT INCLUDED)											
1090	SIZE 340 CFM QUIET 100 PSI	103 HP D	31,733	12.54		2.28	3.96	4.11		55	
1095	SIZE 450 CFM QUIET 100 PSI	152 HP D	42,025	17.40		3.01	5.24	6.06		80	
1100	SIZE 600 CFM QUIET 100 PSI	196 HP D	58,857	23.52		4.23	7.35	7.82		111	
1105	SIZE 750 CFM QUIET 100 PSI	228 HP D	68,381	27.34		4.91	8.53	9.10		120	
1110	SIZE 825 CFM QUIET 100 PSI	250 HP D	73,527	29.63		5.28	9.17	9.97		127	
1115	SIZE 900 CFM QUIET 100 PSI	280 HP D	81,250	32.95		5.84	10.14	11.17		148	
1120	SIZE 1000 CFM QUIET 100 PSI	283 HP D	92,533	35.69		6.65	11.55	11.29		165	
1125	SIZE 1200 CFM QUIET 100 PSI	325 HP D	111,901	42.27		8.04	13.96	12.97		192	
1130	SIZE 1600 CFM QUIET 100 PSI	456 HP D	132,750	53.74		9.53	16.56	18.19		223	
AIR TOOLS ***** (HOSE NOT INCLUDED)											
GARDNER DENVER											
1140	TAMPER T23	20CFM A	851	0.46		0.09	0.21	0.00		1	
1145	SPADER SP27E	32CFM A	857	0.46		0.09	0.21	0.00		1	
1150	SINKER DRILL S48	88CFM A	1,774	0.96		0.19	0.44	0.00		1	
1155	SINKER DRILL S58	98CFM A	1,887	1.02		0.20	0.47	0.00		1	
1160	PAVING BREAKER B37	41CFM A	880	0.48		0.09	0.22	0.00		1	
1165	PAVING BREAKER B67C	46CFM A	944	0.51		0.11	0.24	0.00		1	
1170	PAVING BREAKER B87C	50CFM A	1,027	0.56		0.11	0.26	0.00		1	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT					
			CONDITION	STAND-BY	AVERAGE	SEVERE	OWNER-SHIP	FUEL						
					AVERAGE	SEVERE	OWNER-SHIP	FUEL						
AIR TOOLS (CONT'D)														
\$8888888888888888														
(HOSE NOT INCLUDED)														
GARDNER DENVER (CONT'D)														
1175	FEED LEG DRILL FL83-54" TRAVEL RETRACTABLE	103CFM A	3,470	1.87		0.37	0.86	0.00	1					
1180	FEED LEG DRILL FL53-48" TRAVEL RETRACTABLE	88CFM A	2,970	1.60		0.31	0.74	0.00	1					
SANDBLASTERS CLEMCO														
1190	SCW-1028P SANDBLASTER 1/2" HOSE INCLUDES ACCESSORIES AND 50' HOSE	85CFM A	1,212	0.71		0.13	0.30	0.00	2					
1195	SCW-1440P SANDBLASTER 3/4" HOSE INCLUDES ACCESSORIES AND 50' HOSE	85CFM A	2,151	1.23		0.23	0.54	0.00	5					
1200	SCWB-1648P SANDBLASTER 1" HOSE INCLUDES ACCESSORIES AND 50' HOSE	125CFM A	2,220	1.26		0.24	0.55	0.00	6					
1205	SCWB-2452P SANDBLASTER 1-1/4" HOS INCLUDES ACCESSORIES AND 50' HOSE	210CFM A	2,330	1.33		0.25	0.59	0.00	6					
1210	SCH-3079P SANDBLASTER 1-1/4" HOSE INCLUDES ACCESSORIES AND 50' HOSE	210CFM A	2,536	1.44		0.27	0.64	0.00	9					
CONCRETE VIBRATORS (DART)														
1220	CONCRETE VIBRATOR MOD A-600SH 6"	120CFM A	2,162	2.11		0.23	0.54	0.00	1					
1225	CONCRETE VIBRATOR MOD A-450SH 4.5"	98CFM A	1,843	1.80		0.20	0.46	0.00	1					
1230	CONCRETE VIBRATOR MOD A-35012 3.5"	74CFM A	1,647	1.61		0.18	0.41	0.00	1					
1235	CONCRETE VIBRATOR MOD A-30012 3"	50CFM A	1,468	1.44		0.16	0.37	0.00	1					
1240	CONCRETE VIBRATOR MOD A-25010 2.5"	44CFM A	1,193	1.17		0.13	0.30	0.00	1					

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT	
			CONDITION		STAND-BY	AVERAGE COND.	SEVERE COND.				
			AVERAGE	SEVERE							
	ASPHALT DISTRIBUTOR-ROSCO ***** (NO CHASSIS)										
1250	MOD RES 1000 GAL. TRUCK MOUNTED 18,000 TO 24,000 GVW REQUIRED	50 HP G	17,786	9.54		1.29	2.15	4.26		72	
1255	MOD RES 1500 GAL. TRUCK MOUNTED 24,000 TO 32,000 GVW REQUIRED	50 HP G	18,449	9.69		1.34	2.23	4.26		75	
1260	MOD RES 2000 GAL. TRUCK MOUNTED 32,000 GVW REQUIRED	50 HP G	19,758	9.97		1.43	2.38	4.26		87	
1265	MOD RES 3000 GAL. TRUCK MOUNTED 42,000 GVW REQUIRED	50 HP G	22,264	10.59		1.60	2.63	4.26		109	
	ASPHALT FINISHERS-BARBER GREENE *****										
1275	MOD SB111 8'-12' WIDE (PNEUMATIC)	70 HP D	68,769	19.88		4.89	8.78	2.79		155	
1280	MOD SB131 10'-12' WIDE (P'MATIC) W/VIB SCREED,AUTO. FEEDERS AND GR CONTROL	95 HP D	99,840	28.82		7.09	12.70	3.79		245	
1285	MOD SB140 10'-12' WIDE (P'MATIC) OPTIONS SAME AS MOD SB131	130 HP D	114,528	34.45		8.10	14.47	5.19		314	
1290	MOD SA150 10'-12' WIDE (CRAWLER) OPTIONS SAME AS MOD SB131	130 HP D	137,971	38.93		9.84	17.74	5.19		370	
	BROOMS M-B *****										
1300	MOD 53T HYD 7 FT. TOWED MECH/DRIVE W/SPRINKLER		4,850	1.31		0.35	0.62	0.00		24	
1305	MOD 53-M 7 FT. TOWED MOTOR/DRIVEN W/SPRINKLER	25 HP G	6,211	4.12		0.45	0.79	2.13		30	
1310	MOD MT 7 FT. TRACTOR/MOUNTED PTO/DRIVE W/SPRINKLER/		2,219	0.69		0.16	0.29	0.00		10	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT			
			CONDITION	STAND-BY	AVERAGE COND.	SEVERE COND.	OWNER-SHIP	FUEL				
BROOMS H-B (CONT'D)												

1315	MOD HT 7 FT. TRACTOR/MOUNTED HYD/DRIVE W/SPRINKLER	3,725	0.99		0.27	0.48	0.00		14			
BRUSH CHIPPERS - FITCHBERG												

1325	MOD TWC-612 CAP. TO 6" DIA. LOG 151 HP G	4,880	18.14		0.35	0.63	12.86		37			
1330	MOD TWC-915 CAP. TO 9" DIA. LOG 165 HP G	6,005	19.99		0.43	0.77	14.05		40			
BUCKETS-CLAMSHELL												

GENERAL PURPOSE - SQUARE NOSE ESCO MODEL 6												
1340	1.0 C.Y.	7,833	1.82	2.74	0.57	1.00	0.00	1.58	0.00			
1345	1.5 C.Y.	11,514	2.67	4.01	0.82	1.46	0.00	2.31	0.00			
1350	2.0 C.Y.	13,029	3.02	4.55	0.93	1.65	0.00	2.62	0.00			
1355	2.5 C.Y.	16,979	3.94	5.92	1.21	2.15	0.00	3.41	0.00			
1360	3.0 C.Y.	17,986	4.17	6.27	1.29	2.28	0.00	3.61	0.00			
1365	3.5 C.Y.	18,385	4.26	6.41	1.32	2.33	0.00	3.69	0.00			
1370	4.0 C.Y.	20,242	4.70	7.05	1.45	2.57	0.00	4.06	0.00			
1375	4.5 C.Y.	21,879	5.07	7.63	1.56	2.77	0.00	4.39	0.00			
1380	5.0 C.Y.	23,692	5.49	8.26	1.70	3.00	0.00	4.75	0.00			
1385	5.5 C.Y.	25,568	5.93	8.91	1.83	3.24	0.00	5.13	0.00			
1390	6.0 C.Y.	26,465	6.13	9.23	1.90	3.35	0.00	5.31	0.00			
1395	6.5 C.Y.	28,626	6.63	9.98	2.05	3.62	0.00	5.74	0.00			

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT			
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.				
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL			
BUCKETS-CLAMSHELL (CONT'D)												
XXXXXXXXXXXXXXXXXXXXXX												
GENERAL PURPOSE - SQUARE NOSE CONT'D												
ESCO MODEL G												
1400	7.0 C.Y.	29,473	6.83	10.27	2.11	3.73	0.00	5.91	0.00	185		
HEAVY DUTY - SQUARE NOSE												
ESCO MODEL HD												
1410	1.0 C.Y.	9,512	2.21	3.32	0.69	1.21	0.00	1.91	0.00	49		
1415	1.5 C.Y.	13,824	3.21	4.83	1.00	1.76	0.00	2.78	0.00	74		
1420	2.0 C.Y.	14,909	3.45	5.20	1.06	1.88	0.00	2.99	0.00	82		
1425	2.5 C.Y.	18,943	4.39	6.60	1.36	2.40	0.00	3.80	0.00	104		
1430	3.0 C.Y.	20,712	4.80	7.21	1.48	2.62	0.00	4.15	0.00	115		
1435	3.5 C.Y.	22,343	5.18	7.79	1.60	2.83	0.00	4.48	0.00	126		
1440	4.0 C.Y.	24,008	5.57	8.36	1.72	3.04	0.00	4.81	0.00	137		
1445	4.5 C.Y.	25,773	5.97	8.98	1.84	3.26	0.00	5.17	0.00	147		
1450	5.0 C.Y.	28,360	6.57	9.88	2.03	3.59	0.00	5.68	0.00	163		
1455	5.5 C.Y.	29,921	6.94	10.43	2.14	3.79	0.00	6.00	0.00	172		
1460	6.0 C.Y.	31,652	7.33	11.03	2.26	4.00	0.00	6.35	0.00	182		
1465	6.5 C.Y.	32,985	7.64	11.49	2.36	4.17	0.00	6.61	0.00	193		
1470	7.0 C.Y.	34,334	7.96	11.96	2.46	4.35	0.00	6.88	0.00	193		
EXTRA HEAVY DUTY - SQUARE NOSE												
ESCO MODEL X												
1480	1.0 C.Y.	10,868	2.52	3.79	0.78	1.38	0.00	2.18	0.00	58		
1485	1.5 C.Y.	16,148	3.75	5.63	1.16	2.05	0.00	3.24	0.00	85		

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT					
			CONDITION	STAND-BY	AVERAGE COND.		SEVERE COND.							
					AVERAGE	SEVERE	OWNER-SHIP	FUEL						
BUCKETS-CLAMSHELL (CONT'D)														

EXTRA HEAVY DUTY - SQUARE NOSE CONT'D														
ESCO MODEL X														
1490	2.0 C.Y.	19,531	4.52	6.80	1.40	2.47	0.00	3.91	0.00	103				
1495	2.5 C.Y.	21,792	5.05	7.59	1.56	2.76	0.00	4.37	0.00	121				
1500	3.0 C.Y.	23,650	5.49	8.24	1.70	3.00	0.00	4.74	0.00	135				
1505	3.5 C.Y.	24,852	5.75	8.66	1.78	3.14	0.00	4.98	0.00	149				
1510	4.0 C.Y.	26,322	6.10	9.17	1.88	3.33	0.00	5.28	0.00	158				
1515	4.5 C.Y.	27,563	6.39	9.61	1.98	3.49	0.00	5.53	0.00	168				
1520	5.0 C.Y.	29,556	6.85	10.29	2.11	3.74	0.00	5.92	0.00	181				
1525	5.5 C.Y.	31,289	7.25	10.90	2.24	3.96	0.00	6.27	0.00	193				
1530	6.0 C.Y.	32,891	7.63	11.46	2.36	4.17	0.00	6.59	0.00	203				
1535	6.5 C.Y.	35,635	8.27	12.41	2.56	4.52	0.00	7.14	0.00	220				
1540	7.0 C.Y.	36,697	8.50	12.79	2.62	4.64	0.00	7.36	0.00	230				
BUCKETS-CONCRETE-GAR-BRO														

GENERAL PURPOSE - MANUAL														
1550	1.0 C.Y.	1,065	0.25		0.08	0.14	0.00			6				
1555	1.5 C.Y.	1,329	0.31		0.10	0.17	0.00			8				
1560	2.0 C.Y.	1,725	0.40		0.12	0.22	0.00			11				
1565	3.0 C.Y.	2,467	0.57		0.18	0.31	0.00			19				
1570	4.0 C.Y.	3,119	0.73		0.23	0.40	0.00			23				

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.						
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL					
BUCKETS-CONCRETE-GAR-BRO (CONT'D)														
XXXXXXXXXXXXXXXXXXXXXX														
GENERAL PURPOSE - LOW SLUMP - AIR														
1580	1.0 C.Y.	4,571	1.06		0.33	0.58	0.00			19				
1585	1.5 C.Y.	4,790	1.10		0.34	0.60	0.00			21				
1590	2.0 C.Y.	4,995	1.17		0.36	0.64	0.00			23				
1595	3.0 C.Y.	6,798	1.58		0.49	0.86	0.00			42				
1600	4.0 C.Y.	7,061	1.64		0.51	0.90	0.00			52				
1605	6.0 C.Y. DBL. COMPT.	10,235	2.37		0.73	1.29	0.00			72				
1610	8.0 C.Y. DBL. COMPT.	12,199	2.83		0.88	1.55	0.00			80				
LAYDOWN - HEAVY DUTY - CLAM GATE TYPE														
1620	1.0 C.Y.	4,193	0.97		0.30	0.53	0.00			17				
1625	2.0 C.Y.	4,641	1.08		0.34	0.59	0.00			21				
1630	3.0 C.	5,304	1.23		0.38	0.67	0.00			27				
1635	4.0 C.Y.	6,143	1.43		0.44	0.78	0.00			60				
BUCKETS-DRAGLINE														
XXXXXXXXXXXXXXXXXXXXXX														
LIGHT WEIGHT - PERFORATED HENDRIX MODEL LS														
1650	1.0 C.Y.	2,455	0.57	0.86	0.18	0.31	0.00	0.50	0.00	18				
1655	1.5 C.Y.	2,994	0.69	1.04	0.22	0.38	0.00	0.60	0.00	26				
1660	2.0 C.Y.	3,529	0.82	1.23	0.26	0.45	0.00	0.71	0.00	32				
1665	2.5 C.Y.	4,146	0.96	1.44	0.30	0.52	0.00	0.83	0.00	36				

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT			
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.				
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL			
BUCKETS-DRAGLINE (CONT'D)												
XXXXXXXXXXXXXXXXXXXXXX												
LIGHT WEIGHT - PERFORATED (CONT'D)												
HENDRIX MODEL LS												
1670	3.0 C.Y.	5,098	1.18	1.78	0.36	0.64	0.00	1.03	0.00	41		
1675	3.5 C.Y.	5,652	1.31	1.98	0.41	0.72	0.00	1.14	0.00	47		
1680	4.0 C.Y.	6,884	1.60	2.40	0.50	0.88	0.00	1.38	0.00	64		
1685	4.5 C.Y.	7,308	1.70	2.55	0.53	0.93	0.00	1.47	0.00	67		
1690	5.0 C.Y.	8,820	2.05	3.07	0.63	1.12	0.00	1.77	0.00	83		
1695	6.0 C.Y.	9,570	2.22	3.34	0.69	1.21	0.00	1.92	0.00	90		
1700	7.0 C.Y.	10,461	2.43	3.65	0.75	1.33	0.00	2.10	0.00	101		
1705	8.0 C.Y.	11,600	2.69	4.04	0.83	1.47	0.00	2.32	0.00	112		
1710	10.0 C.Y.	14,563	3.37	5.08	1.04	1.84	0.00	2.93	0.00	139		
1715	12.0 C.Y.	17,909	4.15	6.24	1.28	2.27	0.00	3.59	0.00	166		
1720	14.0 C.Y.	20,592	4.78	7.18	1.48	2.61	0.00	4.13	0.00	191		
MEDIUM WEIGHT - HENDRIX MODEL TS												
1730	1.0 C.Y.	2,973	0.69	1.04	0.22	0.38	0.00	0.60	0.00	19		
1735	1.5 C.Y.	3,655	0.84	1.28	0.26	0.46	0.00	0.74	0.00	28		
1740	2.0 C.Y.	4,354	1.01	1.52	0.31	0.55	0.00	0.88	0.00	36		
1745	2.5 C.Y.	5,023	1.17	1.75	0.36	0.64	0.00	1.01	0.00	41		
1750	3.0 C.Y.	6,000	1.39	2.10	0.43	0.76	0.00	1.21	0.00	49		
1755	3.5 C.Y.	6,630	1.54	2.31	0.47	0.84	0.00	1.33	0.00	54		
1760	4.0 C.Y.	7,948	1.84	2.78	0.57	1.00	0.00	1.60	0.00	70		

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.						
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL					
BUCKETS-DRAGLINE (CONT'D)														
XXXXXXXXXXXXXXXXXXXXXX														
MEDIUM WT. - HENDRIX MODEL TS CONT'D														
1765	4.5 C.Y.	8,510	1.97	2.97	0.61	1.07	0.00	1.71	0.00	72				
1770	5.0 C.Y.	10,909	2.53	3.80	0.78	1.38	0.00	2.19	0.00	93				
1775	6.0 C.Y.	11,270	2.62	3.93	0.81	1.43	0.00	2.26	0.00	96				
1780	7.0 C.Y.	12,862	2.97	4.48	0.92	1.62	0.00	2.58	0.00	111				
1785	8.0 C.Y.	14,165	3.28	4.94	1.01	1.79	0.00	2.84	0.00	122				
1790	10.0 C.Y.	18,051	4.19	6.29	1.29	2.29	0.00	3.62	0.00	159				
1795	12.0 C.Y.	23,006	5.33	8.01	1.64	2.91	0.00	4.61	0.00	202				
1800	14.0 C.Y.	25,619	5.94	8.93	1.83	3.24	0.00	5.14	0.00	225				
HEAVY WEIGHT - HENDRIX MODEL MH-S														
1810	2.75 C.Y.	9,646	2.23	3.37	0.69	1.22	0.00	1.94	0.00	69				
1815	3.0 C.Y.	10,038	2.33	3.50	0.72	1.27	0.00	2.01	0.00	72				
1820	3.5 C.Y.	11,239	2.61	3.91	0.81	1.43	0.00	2.25	0.00	81				
1825	4.0 C.Y.	15,023	3.48	5.24	1.08	1.90	0.00	3.02	0.00	110				
1830	4.5 C.Y.	16,797	3.89	5.86	1.20	2.12	0.00	3.37	0.00	123				
1835	5.0 C.Y.	17,345	4.01	6.05	1.24	2.19	0.00	3.48	0.00	127				
1840	6.0 C.Y.	18,572	4.30	6.47	1.33	2.35	0.00	3.72	0.00	136				
1845	7.0 C.Y.	23,297	5.40	8.12	1.67	2.95	0.00	4.67	0.00	173				
1850	8.0 C.Y.	24,171	5.60	8.43	1.73	3.06	0.00	4.85	0.00	180				
1855	10.0 C.Y.	31,766	7.36	11.07	2.27	4.02	0.00	6.37	0.00	242				
1860	12.0 C.Y.	36,014	8.35	12.55	2.58	4.56	0.00	7.22	0.00	275				

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.		
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL	
BUCKETS-DRAGLINE (CONT'D) *****										
1865	HEAVY WT - HENDRIX MODEL MH-S CONT'D 14.0 C.Y.	39,155	9.08	13.63	2.80	4.96	0.00	7.84	0.00	299
COMPACTORS MANUALLY OPERATED *****										
1875	UR-12 I-R RAMMER	3 HP G	1.427	0.97		0.13	0.26	0.35		1
1880	GVR100 WACKER RAMMER	3 HP G	1.357	0.93		0.11	0.24	0.35		1
1885	GVR220Y WACKER RAMMER	5 HP G	2.290	1.59		0.20	0.42	0.59		2
1890	VPG160B WACKER VIBRO PLATE	4 HP G	1.046	0.97		0.09	0.19	0.47		2
1895	VPG600 WACKER VIBRO PLATE	9 HP G	3,203	2.52		0.28	0.59	1.06		6
CONCRETE BUGGIES - REMINGTON *****										
1905	10 CF WALK-BEHIND	8 HP G	1,963	1.40		0.14	0.25	0.73		6
CONCRETE PAVERS *****										
CMI										
1915	MOD SUPER 200 16' WIDE SLIPFORM UNIT, 0-25 FT/MIN, CRAWLER MTD.	165 HP D	105,441	33.10		7.52	13.56	6.58		296
1920	MOD SUBURBAN 24' WIDE SLIPFORM UNIT, 0-60 FT/MIN, CRAWLER MTD.	250 HP D	188,556	56.88		13.45	24.24	9.97		720

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT					
			CONDITION	STAND-BY	AVERAGE COND.		SEVERE COND.							
					AVERAGE	SEVERE	OWNER-SHIP	FUEL						
CONCRETE PAVERS (CONT'D)														

GOMACO														
1930	MOD C-650 24' WIDE FORM PAVER W/4' FINISHING CYLINDERS	50 HP 6	17,553	9.76		1.25	2.23	4.26	91					
1935	MOD HW-165 16'-6" WIDE SLIPFORM UNIT, AUTO VIBRATORS, CRLR MTD	100 HP D	84,577	24.91		6.04	10.88	3.99	240					
CONCRETE PLACERS														

ALIVA SHOTCRETE EQUIPMENT														
1945	MOD 240 PLACE 1 TO 5 CY/HR	275CFM A	8,979	2.18		0.64	1.14	0.00	7					
1950	MOD 250 PLACE 5.5 TO 10 CY/HR	450CFM A	16,462	3.88		1.18	2.10	0.00	13					
1955	MOD 260 PLACE 5 TO 22 CY/HR	675CFM A	23,548	5.49		1.68	3.01	0.00	19					
CONCRETE PUMPS - CHALLENGE-COOK														
1965	MOD 700 1" AGG REQUIRES 15,000 GVW TRUCK	70 CY/HR 128 HP D	41,754	21.61		3.22	6.16	7.53	84					
1970	MOD TITAN4000 TR'L MT'D	100 CY/HR 240 HP D	66,940	37.25		5.17	9.88	14.11	134					
1975	HYDRAULIC BOOM 60' VERT 52'RAD REQUIRES 20,000 GVW TRUCK FOR BOOM ONLY OR 43,000 GVW WITH PUMP		30,381	8.91		2.34	4.48	0.00	59					

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CNT
			CONDITION	STAND-BY	AVERAGE	SEVERE	OWNER-SHIP	FUEL	OWNER-SHIP	
	CRANE-SHOVEL-BACKHOE-DRAGLINE *****									
	CRAWLER TYPE-AMERICAN									
	MOD 4120 DRAGLINE 1 CY 93 HP D 13'-8" CRAWLERS W/28" SHOES									
1985	DRAGLINE OR CLAMSHELL (LESS BUCKET)	126,239	26.79	39.42	8.52	14.50	2.93	22.80	3.81	609
	MOD 597-C 1.25 CY T/C 129 HP D 14'-7" CRAWLERS W/32" SHOES									
1990	DRAGLINE OR CLAMSHELL (LESS BUCKET)	181,765	34.86	50.62	11.56	18.44	4.06	29.29	5.28	814
1995	CRANE 35-T W/70' BOOM	181,196	30.92	45.03	11.53	18.39	3.25	29.20	4.20	803
	MOD 599-C LIFTING CRANE T/C 129 HP D 16'-0" CRAWLERS W/32" SHOES									
2005	CRANE 40-T W/80' BOOM	180,618	30.84	44.90	11.49	18.33	3.25	29.11	4.20	962
	MOD 5299 LIFTING CRANE T/C 129 HP D 17'-6" CRAWLERS W/32" SHOES									
2015	CRANE 50-T W/80' BOOM	207,310	34.83	50.80	13.19	21.04	3.25	33.40	4.20	1088
	MOD 797-C 2 CY T/C 205 HP D 17'-6" CRAWLERS W/33" SHOES									
2025	DRAGLINE OR CLAMSHELL (LESS BUCKET)	242,531	47.75	69.12	15.42	24.61	6.46	39.08	8.39	1278
2030	CRANE 40-T W/80' BOOM	238,915	41.81	60.69	15.20	24.25	5.17	38.49	6.67	1262
	MOD 7250 STEEL ERECTOR T/C 205 HP D 17'-6" CRAWLERS W/33" SHOES									
2040	CRANE 60-T W/80' BOOM	258,284	42.06	60.86	15.76	23.91	5.17	38.47	6.67	1421

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.			
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL		
	CRANE-SHOVEL-BACKHOE-DRAGLINE CONT'D XXXXXXXXXXXXXXXXXXXXXX										
	CRAWLER TYPE-AMERICAN (CONT'D)										
	MOD 7260 LIFTING CRANE T/C 205 HP D 19'-6" CRAWLERS W/38" SHOES										
2050	CRANE 100T W/200' BOOM	332,335	52.37	76.06	20.28	30.77	5.17	49.50	6.67	1886	
	MOD 999-C STEEL ERECTOR T/C 289 HP D 23'-9" CRAWLERS W/44" SHOES										
2060	CRANE 110-T W/200' BOOM	433,969	69.02	100.13	26.48	40.18	7.28	64.63	9.41	2792	
	MOD 9260 4.5 CY T/C 289 HP D 23'-9" CRAWLERS W/38" SHOES										
2070	CRANE 125T W/270' BOOM	459,474	72.56	105.37	28.03	42.53	7.28	68.43	9.41	3025	
2075	DRAGLINE OR CLAMSHELL (LESS BUCKET)	440,250	77.90	112.54	26.85	40.75	9.10	65.57	11.83	2619	
	MOD 9270 LIFT CR TAPERED TIP T/C 289 HP D 23'-9" CRAWLERS W/44" SHOES										
2085	CRANE 150T W/280' BOOM	503,460	78.68	114.39	30.71	46.60	7.28	74.98	9.41	3400	
	MOD 9299 LIFTING CRANE T/C 289 HP D 24'-11" CRAWLERS W/50" SHOES										
2095	CRANE 165T W/290' BOOM	529,839	80.71	116.92	31.64	46.69	7.28	75.80	9.41	3580	
	MOD 9310 LIFTING CRANE T/C 289 HP D 28'-2" CRAWLERS W/50" SHOES										
2105	CRANE 225T W/320' BOOM	620,783	93.09	135.08	37.07	54.71	7.28	88.81	9.41	3990	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.			
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL		
	CRANE-SHOVEL-BACKHOE-DRAGLINE CONT'D XXXXXXXXXXXXXXXXXXXXXXXXXXXXXX										
	CRAWLER TYPE-BUCYRUS ERIE										
	MOD 25-B SER-3 HVY DUTY 1 CY 115 HP D 13'-11" CRAWLERS W/30" SHOES										
2120	DRAGLINE OR CLAMSHELL (LESS BUCKET)	145,357	31.13	45.77	9.81	16.69	3.62	26.26	4.71	671	
2125	CRANE 28-T W/50' BOOM	143,971	24.94	36.25	9.16	14.61	2.90	23.20	3.74	674	
	MOD 30-B SER 4 HVY DUTY 1.5 CY 144 HP D 14'-9" CRAWLERS W/30" SHOES										
2135	BACKHOE	207,237	46.19	66.65	13.68	22.74	5.29	35.84	6.96	787	
2140	DRAGLINE OR CLAMSHELL (LESS BUCKET)	198,538	38.21	55.44	12.63	20.15	4.54	31.99	5.90	833	
2145	CRANE 35-T W/60' BOOM	195,642	33.52	48.79	12.44	19.85	3.63	31.52	4.69	831	
	MOD 38-B SER 2 HVY DUTY 2 CY T/C 178 HP D 17'-5" CRAWLERS W/36" SHOES										
2155	SHOVEL	290,368	63.69	92.04	19.16	31.85	6.54	50.22	8.60	1298	
2160	DRAGLINE OR CLAMSHELL (LESS BUCKET)	273,971	51.95	75.50	17.42	27.80	5.61	44.15	7.29	1226	
	MOD 61-B SER 2 3.25 CY T/C 205 HP D 15'-11" CRAWLERS W/33" SHOES										
2170	SHOVEL	412,229	80.25	115.05	25.81	40.45	7.53	64.51	9.90	1691	
2175	BACKHOE	394,784	77.23	110.66	24.72	38.74	7.53	61.77	9.90	1751	
2180	DRAGLINE OR CLAMSHELL (LESS BUCKET)	374,977	64.82	93.87	22.88	34.71	6.46	55.85	8.39	1523	
2185	CRANE 51-T W/70' BOOM	366,875	57.18	83.14	22.38	33.96	5.17	54.64	6.67	1536	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS			CWT	
			CONDITION		STAND BY	AVERAGE COND.		SEVERE COND.		
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP		
	CRANE-SHOVEL-BACKHOE-DRAGLINE CONT'D *****									
	CRAWLER TYPE-BUCYRUS ERIE (CONT'D)									
	MOD 61-B SER-2 110-T 4 CY T/C 243 HP D 20'-6" CRAWLERS W/42" SHOES									
2195	CRANE 110T W/160' BOOM	468,171	70.95	102.83	27.96	41.26	6.12	66.98	7.91	2182
2200	DRAGLINE OR CLAMSHELL (LESS BUCKET)	441,001	76.30	110.49	26.90	40.82	7.65	65.68	9.95	2010
	MOD 71-B SER 3 4.25 CY T/C 246 HP D 16'-10" CRAWLERS W/36" SHOES									
2210	SHOVEL	468,068	91.70	131.38	29.31	45.93	9.04	73.24	11.88	219
2215	BACKHOE	443,560	87.46	125.23	27.78	43.53	9.04	69.40	11.88	2100
2220	DRAGLINE OR CLAMSHELL (LESS BUCKET)	420,475	73.29	106.03	25.66	38.93	7.75	62.62	10.07	1736
	MOD 88-B SER 4 5.5 CY T/C 365 HP D 17'-10" CRAWLERS W/36" SHOES									
2230	SHOVEL	657,275	124.86	177.82	40.10	60.85	13.41	97.88	17.63	2822
2235	DRAGLINE OR CLAMSHELL (LESS BUCKET)	557,768	96.18	138.33	33.30	49.15	11.50	79.80	14.95	2274
	CRAWLER TYPE-LINK BELT (FMC)									
	MOD LS-98A LIFTING CRANE T/C 118 HP D 15'-1" CRAWLERS W/24" SHOES									
2250	CRANE 40-T W/50' BOOM	149,490	25.85	37.59	9.51	15.17	2.97	24.09	3.84	772
	MOD LS-118 LIFTING CRANE T/C 165 HP D 17'-0" CRAWLERS W/30" SHOES									
2260	CRANE 60-T W/80' BOOM	214,622	36.99	53.80	13.65	21.78	4.16	34.59	5.37	127

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.			
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL		
	CRANE-SHOVEL-BACKHOE-DRAGLINE CONT'D *****										
	CRAWLER TYPE-LINK BELT (CONT'D)										
	MOD LS-338 LIFTING CRANE T/C 208 HP D 20'-0" CRAWLERS W/38" SHOES										
2270	CRANE 100-T W/200' BOOM	343,023	52.86	76.50	20.48	30.22	5.24	49.08	6.77	1912	
	MOD LS-518 LIFTING CRANE T/C 230 HP D 24'-4" CRAWLERS W-44" SHOES										
2280	CRANE 150-T W/250' BOOM	500,136	74.91	108.72	29.86	44.07	5.80	71.55	7.49	2912	
	CRAWLER TYPE-MANITOWOC										
	MOD 3900 VICOM 3.5 CY T/C 334 HP D 20'-4" CRAWLERS W/38" SHOES										
2295	DRAGLINE OR CLAMSHELL (LESS BUCKET)	346,451	65.26	93.72	21.14	32.07	10.52	51.60	13.68	2306	
2300	CRANE 100T W/240' BOOM	355,210	59.39	85.70	21.67	32.88	8.42	52.90	10.87	2354	
	MOD 3900W VICOM SER2 4 CY T/C 334 HP D 24'-0" CRAWLERS W/48" SHOES										
2310	DRAGLINE OR CLAMSHELL (LESS BUCKET)	416,105	75.88	109.31	25.38	38.51	10.52	61.97	13.68	2763	
2315	CRANE 140T W/250' BOOM	423,847	68.95	99.78	25.86	39.24	8.42	63.12	10.87	2815	
	MOD 4100W VICOM SER2 5 CY T/C 345 HP D 26'-6" CRAWLERS W/48" SHOES										
2325	DRAGLINE OR CLAMSHELL (LESS BUCKET)	590,532	102.92	148.89	36.03	54.67	10.87	87.94	14.13	3788	
2330	CRANE 200T W/260' BOOM	600,764	92.02	133.23	35.87	52.94	8.69	85.95	11.23	3929	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.			
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL		
	CRANE-SHOVEL-BACKHOE-DRAGLINE CONT'D XXXXXXXXXXXXXXXXXXXXXXXXXXXXXX										
	CRAWLER TYPE-MANITOWOC (CONT'D)										
	MOD 4600 VICON SERIES 3 7CY T/C 685 HP D 26'-1" CRAWLERS W/60" SHOES										
2340	CRANE 240T W/260' BOOM	863,297	137.87	198.72	51.55	76.07	17.26	123.50	22.30	5095	
2345	DRAGLINE OR CLAMSHELL (LESS BUCKET)	893,062	157.72	226.33	53.32	78.69	21.58	127.76	28.05	5083	
	CRAWLER TYPE-NORTHWEST										
	MOD 28-D 3/4 CY 148 HP D 11'-11" CRAWLERS W/28" SHOES										
2360	DRAGLINE OR CLAMSHELL (LESS BUCKET)	114,492	26.66	38.82	7.73	13.15	4.66	20.68	6.06	484	
2365	CRANE 15-T W/30' BOOM	112,914	22.00	32.00	7.46	12.39	3.73	19.54	4.82	474	
	MOD-41 1 CY 148 HP D 15'-0" CRAWLERS W/30" SHOES										
2375	DRAGLINE OR CLAMSHELL (LESS BUCKET)	149,074	33.05	48.39	10.06	17.12	4.66	26.93	6.06	737	
2380	CRANE 20-T W/40' BOOM	146,790	27.27	39.88	9.69	16.10	3.73	25.39	4.82	720	
	MOD 6 1.5 CY T/C 238 HP D 14'-8" CRAWLERS W/33" SHOES										
2390	DRAGLINE OR CLAMSHELL (LESS BUCKET)	198,207	41.64	59.90	12.60	20.11	7.50	31.94	9.75	1001	
2395	CRANE 30-T W/45' BOOM	199,210	36.85	53.19	12.67	20.21	6.00	32.10	7.75	1001	
	MOD 80-D 2.5 CY T/C 238 HP D 15'-10" CRAWLERS W/30" SHOES										
2405	SHOVEL	301,065	68.35	98.48	19.87	33.03	8.75	52.08	11.50	1550	
2410	DRAGLINE OR CLAMSHELL (LESS BUCKET)	263,998	52.53	75.97	16.79	26.79	7.50	42.54	9.75	1380	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.			
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL		
	CRANE-SHOVEL-BACKHOE-DRAGLINE CONT'D *****										
	CRAWLER TYPE-NORTHWEST (CONT'D)										
	MOD 80-D 2.5 CY T/C 238 HP D 15'-10" CRAWLERS W/30" SHOES										
2415	CRANE 40-T W/50' BOOM	261.036	46.09	66.86	16.60	26.48	6.00	42.06	7.75	1320	
	MOD 95-WT 4.0 CY T/C 263 HP D 19'-0" CRAWLERS W/38" SHOES										
2425	DRAGLINE OR CLAMSHELL (LESS BUCKET)	336.641	61.12	88.09	20.53	31.16	8.28	50.14	10.77	1580	
130	CRANE 60-T W/50' BOOM	333.624	54.26	78.55	20.35	30.88	6.63	49.69	8.56	1565	
	MOD 180-D SERIES 2 5 CY T/C 357 HP D 18'-1" CRAWLERS W/36" SHOES										
2440	SHOVEL	545.956	110.00	157.24	34.19	53.58	13.12	85.44	17.24	2571	
2445	DRAGLINE OR CLAMSHELL (LESS BUCKET)	502.877	89.98	129.85	30.67	46.55	11.25	74.89	14.62	2365	
2450	CRANE 98-T W/170' BOOM	524.202	83.60	121.26	31.98	48.52	9.00	78.07	11.62	2464	
	MOD 190-D SERIES 2 6.5 CY T/C 357 HP D 21'-1" CRAWLERS W/54" SHOES										
2460	SHOVEL	633.104	120.50	171.59	38.62	58.61	13.12	94.29	17.24	2825	
2465	DRAGLINE OR CLAMSHELL (LESS BUCKET)	540.250	93.29	134.15	32.26	47.61	11.25	77.29	14.62	2555	
2470	CRANE 100-T W/170' BOOM	564.480	89.21	129.52	34.43	52.25	9.00	84.07	11.62	2865	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS			CWT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.		
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP		
	CRANE-SHOVEL-BACKHOE-DRAGLINE CONT'D *****									
	CRAWLER TYPE-P & H									
	MOD 535 1.25 CY T/C 158 HP D 15'-8" CRAWLERS W/30" SHOES									
2485	DRAGLINE OR CLAMSHELL (LESS BUCKET)	195,071	38.15	55.27	12.40	19.79	4.98	31.44	6.47	
2490	CRANE 35-T W/50' BOOM	188,833	32.92	47.83	12.01	19.16	3.98	30.43	5.14	
	MOD 550 1.75 CY T/C 158 HP D 18'-0" CRAWLERS W/30" SHOES									
2500	DRAGLINE (LESS BUCKET)	216,474	41.69	60.50	13.76	21.96	4.98	34.89	6.47	
2505	CRANE 50-T W/80' BOOM	210,930	36.22	52.71	13.41	21.40	3.98	33.99	5.14	
	MOD 670WLC 2 CY T/C 198 HP D 18'-6" CRAWLERS W/30" SHOES									
2515	DRAGLINE OR CLAMSHELL (LESS BUCKET)	253,645	49.33	71.51	16.13	25.74	6.24	40.87	8.11	
2520	CRANE 70-T W/150' BOOM	258,953	41.94	60.73	15.80	23.97	4.99	38.57	6.44	
	CRANES-HYDRAULIC-SELF PROPELLED *****									
	GROVE									
2535	MOD RT48 8 TON 123 HP G	75,933	25.32		4.83	7.26	10.47		326	
2540	MOD RT49 10 TON 123 HP G	77,147	25.49		4.90	7.37	10.47		336	
2545	MOD RT515 15 TON 115 HP D	92,453	19.99		5.86	8.78	4.59		415	
2550	MOD RT518 18 TON 115 HP D	93,049	20.44		5.86	8.69	4.59		450	
2555	MOD RT522 22 TON 115 HP D	106,964	22.50		6.76	10.04	4.59		45	
2560	MOD RT625 25 TON 156 HP D	133,385	28.77		8.42	12.49	6.22		545	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT	
			CONDITION	STAND-	AVERAGE COND.	SEVERE COND.				
			AVERAGE	SEVERE	BY OWNER-	FUEL OWNER-	FUEL			
	CRANES-HYD.-SELF PROPELLED CONT'D) *****									
	GROVE (CONT'D)									
2565	MOD RT65S 35 TON 173 HP D	185,699	37.72		11.72	17.42	6.90		673	
	Hyster									
2575	MOD K300B 15 TON 127 HP D	100,630	21.84		6.38	9.56	5.07		438	
2580	MOD K360B 18 TON 127 HP D	103,258	22.23		6.55	9.81	5.07		440	
2585	MOD K400B 20 TON 127 HP D	111,140	23.41		7.06	10.58	5.07		466	
	PETTIBONE									
2595	MOD 25 12.5 TON 120 HP D	90,432	19.98		5.73	8.56	4.79		440	
2600	MOD 36 18 TON 120 HP D	105,598	22.38		6.69	9.98	4.79		460	
2605	MOD 70 35 TON 188 HP D	159,249	34.47		10.05	14.91	7.50		770	
2610	MOD 100SC 50 TON 188 HP D	227,187	44.59		14.38	21.46	7.50		1050	
	CRANES-HYDRAULIC-TRUCK MOUNTED ***** (HP & FUEL LISTED EQUIP/CARRIER)									
	BUCYRUS ERIE									
2620	30-XC 30 TON W/80' BOOM 130/210 HP D/D	184,186	33.30	47.56	11.20	16.89	6.64	27.24	8.38	552
2625	60-XC 60-TON W/136' BOOM 197/238 HP D/D	287,128	50.64	72.67	17.46	26.38	9.50	42.54	12.05	783
	GROVE									
2635	TMS185 18 TON W/106' BOOM 172 HP D	147,869	29.94	42.94	9.37	14.85	6.86	23.65	8.85	442
2640	TMS300 35 TON W/136' BOOM 203 HP D	161,458	32.26	45.88	9.80	14.73	8.10	23.81	10.44	705

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES				ADJUSTABLE ELEMENTS				CWT
			CONDITION		STAND-BY	AVERAGE COND.	SEVERE COND.				
			AVERAGE	SEVERE			OWNER-SHIP	FUEL	OWNER-SHIP	FUEL	
	CRANES-HYDRAULIC-TRUCK MOUNTED CONT'D ***** (HP & FUEL LISTED EQUIP/CARRIER)										
	GROVE (CONT'D)										
2645	TMS475 50 TON W/142' BOOM 203 HP D	196,174	36.84	52.69	11.91	17.95	8.10	28.99	10.44	773	
2650	TW875 80 TON W/146' BOOM 212/302 HP D/D	296,465	53.31	75.83	17.59	25.70	10.54	41.95	13.34	1175	
	LINK BELT (FMC)										
2660	HTC-25 25-T W/95' BOOM 216 HP D	145,723	30.68	43.42	8.85	13.33	8.62	21.53	11.11	462	
2665	HTC-35 35-T W/108' BOOM 216 HP D	170,801	34.08	48.46	10.37	15.62	8.62	25.22	11.11	628	
2670	HTC-50 50-T W/122' BOOM 244 HP D	208,419	40.47	57.68	12.67	19.11	9.74	30.83	12.55	727	
	PETTIBONE										
2680	50TKLSPC 25 TON W/95' BOOM 210 HP D	143,613	31.54	44.82	9.07	14.30	8.38	22.82	10.80	520	
2685	60TKLSPC 30 TON W/101' BOOM 202 HP D	169,397	33.36	47.46	10.27	15.44	8.06	24.96	10.39	673	
2690	100TKLSPC50 TON W/111' BOOM 244 HP D	211,571	41.09	58.54	12.85	19.34	9.74	31.23	12.55	820	
2695	160TKLSPC80 TON W/153' BOOM 365 HP D	311,838	60.46	85.73	18.51	27.04	14.56	44.13	18.78	1395	
	CRANES-TRUCK MOUNTED ***** (HP & FUEL LISTED EQUIP/CARRIER)										
	AMERICAN										
2705	5530 75-T W/170' BOOM 115/238 HP D/D	274,308	44.54	64.05	16.31	23.89	6.23	38.93	7.83	1245	
2710	7530 125T W/200' BOOM 203/350 HP D/D	382,732	64.25	92.06	22.77	33.38	10.51	54.36	13.26	1696	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.						
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL					
CRANES-TRUCK MOUNTED (CONT'D) \$888888888888888888888888888888 (HP & FUEL LISTED EQUIP/CARRIER)														
LINK BELT (FMC)														
2720	HC108C 50-T	W/150' BOOM 117/238 HP D/D	263.278	43.82	63.23	15.98	24.05	6.31	38.86	7.94 1197				
2725	HC218A 100-T	W/220' BOOM 165/318 HP D/D	361.329	58.66	83.75	21.12	30.23	8.78	49.67	11.05 1566				
2730	HC238A 140-T	W/230' BOOM 171/318 HP D/D	433.678	68.33	97.95	25.36	36.32	9.02	59.66	11.36 2068				
LORAIN														
2740	MC550A 50-T	W/160' BOOM 115/246 HP D/D	258.507	43.16	62.23	15.69	23.61	6.29	38.14	7.90 1111				
2745	MC670A 70-T	W/170' BOOM 150/270 HP D/D	309.322	51.13	73.39	18.40	26.97	7.85	43.93	9.89 1243				
2750	MC680 80-T	W/190' BOOM 167/270 HP D/D	315.579	52.80	75.72	18.77	27.52	8.53	44.84	10.77 1373				
2755	MC790 90-T	W/220' BOOM 210/270 HP D/D	379.540	63.51	91.10	22.58	33.10	10.24	53.90	12.98 1594				
2760	MC8150 150T	W/250' BOOM 246/365 HP D/D	520.005	84.36	120.48	30.37	43.42	12.33	71.39	15.59 2625				
P & H														
2770	325TC 25-T	W/110' BOOM 79/190 HP D/D	161.082	29.02	41.92	10.18	16.09	4.46	25.67	5.59 645				
2775	430ATC 35-T	W/150' BOOM 95/210 HP D/D	180.796	31.33	44.94	10.97	16.49	5.24	26.65	6.58 763				
2780	440TC 40-T	W/170' BOOM 95/236 HP D/D	192.399	33.21	47.64	11.67	17.53	5.42	28.34	6.79 964				
2785	650ATC 50-T	W/150' BOOM 135/236 HP D/D	268.600	45.41	65.43	16.31	24.55	7.01	39.65	8.85 1178				
2790	670TC 70-T	W/180' BOOM 135/255 HP D/D	287.336	47.39	68.03	17.08	25.03	7.15	40.79	9.00 1340				
2795	790TC 90-T	W/200' BOOM 160/350 HP D/D	333.066	55.65	79.71	19.80	29.00	8.80	47.26	11.05 1736				
2800	9125TC 140T	W/270' BOOM 210/350 HP D/D	456.443	73.49	105.10	26.69	38.24	10.79	62.80	13.62 2529				
2805	6250TC 250T	W/320' BOOM 363/450 HP D/D	907.571	140.53	202.23	53.11	76.19	17.59	125.04	22.30 4552				

EP 1110-1-8

(Vol. 2)

15 Jun 81

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.		
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL	
	DRILLS-BLAST HOLE-CRAWLER MTD *****									
	GARDNER DENVER									
2815	AT3100B/PR123J 3.5" HOLE 12' FEED 600CFM A	61,779	14.98		4.42	7.89	0.00			91
2820	AT3100B/PR55 4" HOLE 12' FEED 750CFM A	56,599	13.74		4.04	7.22	0.00			93
2825	AT3100B/PR66 4.5" HOLE 12' FEED 900CFM A	64,519	15.64		4.61	8.24	0.00			95
2830	AT3700A/PR123J ANGLE DRILL 600CFM A 3.5" HOLE 12' FEED	73,243	17.77		5.23	9.35	0.00			137
2835	AT3700A/PR66 ANGLE DRILL 900CFM A 4.5" HOLE 12' FEED	75,987	18.43		5.43	9.70	0.00			143
	INGERSOLL-RAND									
2845	CM350/VL140 5.5" HOLE 12' FEED 750CFM A	58,738	14.25		4.20	7.50	0.00			120
2850	ECM350/VL140 5.5" HOLE 12' FEED 750CFM A	65,190	15.80		4.66	8.33	0.00			129
2855	CM350/URD550 5.5" HOLE 12' FEED 900CFM A	64,404	15.61		4.60	8.22	0.00			121
2860	ECM350/URD550 5.5" HOLE 12' FEED 900CFM A	70,859	17.15		5.06	9.04	0.00			130
	JOY									
2870	RAM VCR260 4.5" HOLE 12' FEED 750CFM A	54,236	13.18		3.88	6.93	0.00			126
2875	MUSTANG VCR280 5" HOLE 23' FEED 1200CFM A	75,180	18.23		5.37	9.59	0.00			185
	DRILLS-CORE-AIR-COLUMN MOUNTED *****									
2885	LONGYEAR 24 WOLVERINE AX 700' 450CFM A	10,324	2.71		0.73	1.31	0.00			12
2890	LONGYEAR 65D EX 600' 400CFM A	6,828	1.88		0.49	0.87	0.00			3
2895	65D ROD PULLER 21" STROKE 400CFM A	1,125	0.47		0.08	0.14	0.00			

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT			
			CONDITION	AVERAGE	SEVERE	STAND-BY	OWNER-SHIP	FUEL	OWNER-SHIP				
DRILLS-CORE-SKID MOUNTED													
XXXXXXXXXXXXXX													
ACKER													
2905	HILLBILLY MARK-III NX 1000' MAX	46 HP D	22,679	8.24		1.63	2.90	2.27		40			
2910	MOUNTAINEER NX 2000' MAX	44 HP B	25,036	8.68		1.79	3.20	2.17		45			
SPRAGUE AND HENWOOD													
2920	MOD 37-H NX 400' MAX	18 HP G	10,381	4.67		0.75	1.33	1.88		18			
2925	MOD 40-CL NX 900' MAX	45 HP D	19,168	7.34		1.37	2.45	2.22		27			
LONGYEAR													
2935	MOD 24 STD AX 675' MAX	12 HP G	8,100	3.39		0.58	1.04	1.25		19			
2940	MOD 34 NX 1000' MAX	31 HP G	18,388	8.16		1.32	2.35	3.24		38			
2945	MOD 34 NX 1000' MAX	38 HP D	20,603	7.26		1.48	2.63	1.88		39			
2950	MOD 38 NX 1800' MAX	42 HP D	22,533	7.96		1.61	2.88	2.07		41			
2955	MOD 44 NX 2500' MAX	60 HP D	29,798	10.80		2.13	3.80	2.96		56			
DRILLS-ROTARY													
XXXXXXXXXXXXXX													
CHICAGO PNEUMATIC													
2965	MOD T-650 6-3/4" - W/TRUCK 50,000 G.V.W.	218 HP D	192,551	47.78		12.24	19.34	10.76		440			
JOY-ROBBINS													
2975	RRT 50 TK MOUNTED 6-3/4" TD 9"	304 HP D	318,667	75.64		20.24	31.98	15.00		820			
980	RRT 60 TK MTD 6-3/4" TD 9-7/8"	325 HP D	357,295	83.72		22.71	35.89	16.04		920			

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT
			CONDITION	STAND-BY	AVERAGE COND.	SEVERE COND.			
			AVERAGE	SEVERE	OWNER-SHIP	FUEL	OWNER-SHIP	FUEL	
DRILLS-ROTARY (CONT'D)									

JOY-ROBBINS (CONT'D)									
2985	RRT 70 TK MTD 6-3/4" TO 10-5/8"	350 HP D	410.352	94.56	26.09	41.26	17.27		1020
2990	RR10S DM D9 6 -3/4" TO 9-7/8"	320 HP D	319.104	75.62	20.34	32.30	15.79		1120
2995	RR10HD DM D9 6-3/4" TO 10-5/8"	500 HP D	386.564	98.48	24.64	39.13	24.67		1200
3000	RR11 CRLR MTD 6-3/4" TO 12-1/4"	575 HP E	579.293	100.35	34.70	50.98	22.14		1421
3005	RR12 CRLR MTD 10-5/8" TO 12-1/2"	600 HP E	723.714	118.53	43.35	63.69	23.10		1500
3010	RR16 CRLR MTD 10-5/8" TO 15"	1100 HP E	820.938	158.67	49.17	72.25	42.35		2200
FORK LIFTS									

HYSTER-CHALLENGER									
3020	H30H 3000# @ 24" LC (LOAD CMTR)	63 HP G	18.710	11.17	1.33	2.36	5.36		71
3025	H60H 6000# @ 24" LC	63 HP G	21.146	11.74	1.50	2.65	5.36		103
3030	H110F 11000# @ 24" LC	116 HP G	32.290	20.03	2.29	4.05	9.88		163
3035	H150H 15000# @ 24" LC	127 HP G	45.266	24.34	3.20	5.66	10.81		223
3040	H200HS20000# @ 24" LC	PS 127 HP G	51.763	25.90	3.67	6.50	10.81		256
3045	H250H 25000# @ 24" LC	PS 127 HP G	53.793	26.40	3.80	6.72	10.81		295
3050	H300B 30000# @ 24" LC	PS 127 HP G	59.922	27.88	4.25	7.51	10.81		360
3055	H460B 46000# @ 48" LC	PS 190 HP G	116.081	48.11	8.20	14.48	16.18		590

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES				ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.							
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL						
GENERATOR ELECT PLANTS *****															
CATERPILLAR T = TURBOCHARGED TA = TURBOCHARGED AFTER COOLED															
SKID MOUNTED															
3070	MOD 3304 -T	240/480V	86 KW	129 HP	D	14,121	9.53	12.66	1.02	1.66	5.15	2.59	6.64	37	
3075	MOD 3306 -T	240/480V	130 KW	200 HP	D	16,965	13.68	18.09	1.24	2.01	7.98	3.11	10.29	45	
3080	MOD 3306 -TA	240/480V	150 KW	220 HP	D	19,372	15.19	20.12	1.40	2.28	8.78	3.55	11.32	46	
3085	MOD 3406 -T	240/480V	175 KW	270 HP	D	20,336	17.88	23.61	1.48	2.40	10.77	3.73	13.89	64	
3090	MOD 3406 -TA	240/480V	200 KW	305 HP	D	23,300	20.27	26.76	1.69	2.75	12.17	4.26	15.69	66	
3095	MOD 3408 -T	240/480V	225 KW	335 HP	D	26,445	22.46	29.68	1.92	3.12	13.37	4.85	17.24	72	
3100	MOD 3408 -TA	240/480V	250 KW	375 HP	D	29,738	25.17	33.25	2.16	3.51	14.96	5.45	19.29	75	
3105	MOD D353E-TA	240/480V	335 KW	435 HP	D	47,093	32.01	42.51	3.42	5.56	17.36	8.61	22.38	96	
3110	MOD 3412 -T	240/480V	300 KW	425 HP	D	41,296	30.21	40.06	3.00	4.87	16.96	7.55	21.87	92	
3115	MOD 3412 -TA	240/480V	440 KW	565 HP	D	45,932	38.17	50.45	3.34	5.42	22.54	8.40	29.07	94	
3120	MOD D348 -TA	240/480V	480 KW	683 HP	D	70,599	49.50	65.71	5.13	8.33	27.25	12.92	35.14	135	
3125	MOD D398B-TA	230/460V	566 KW	812 HP	D	94,598	61.22	81.47	6.87	11.16	32.40	17.30	41.76	197	
3130	MOD D399 -TA	230/460V	770 KW	1074 HP	D	121,700	80.19	106.67	8.83	14.34	42.85	22.26	55.26	278	
OWAN															
SKID MOUNTED															
3145		120/240V	15 KW	27 HP	D	4,919	2.43	3.26	0.36	0.58	1.08	0.90	1.39	14	
3150		120/240V	30 KW	63 HP	D	7,300	4.73	6.31	0.53	0.86	2.51	1.34	3.24	19	
3155		120/240V	45 KW	87 HP	D	9,652	6.44	8.58	0.70	1.13	3.47	1.77	4.48	25	

EP 1110-1-B
 (Vol. 2)
 15 Jun 81

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT					
			CONDITION	STAND-BY	AVERAGE	SEVERE	OWNER-SHIP	FUEL	OWNER-SHIP						
GENERATOR ELECT PLANTS (CONT'D)															

ONAN (CONT'D)															
3160	120/240V 60 KW	102 HP D	11,099	7.52	10.00	0.81	1.31	4.07	2.04	5.25	26				
3165	120/240V 75 KW	162 HP D	13,209	10.95	14.48	0.96	1.56	6.46	2.42	8.33	30				
3170	120/240V 90 KW	162 HP D	13,842	11.10	14.68	1.01	1.64	6.46	2.54	8.33	30				
3175	120/240V 125 KW	210 HP D	15,990	13.95	18.41	1.16	1.89	8.38	2.93	10.80	50				
3180	120/240V 150 KW	276 HP D	18,939	17.86	23.55	1.38	2.23	11.01	3.47	14.20	65				
GRADERS MOTOR															

AUSTIN WESTERN															
3190	PACER 301 POWER SHIFT	4X4 146 HP D	82,188	22.43	32.32	5.57	8.97	5.37	14.42	7.05	245				
3195	SUPER 301 POWER SHIFT	6X6 146 HP D	89,211	23.97	34.77	6.01	9.64	5.37	15.54	7.05	273				
3200	PACER 501 POWER SHIFT	4X4 187 HP D	87,340	25.30	36.26	5.91	9.54	6.87	15.34	9.03	280				
3205	SUPER 501 POWER SHIFT	6X6 187 HP D	94,060	26.79	38.63	6.35	10.19	6.87	16.41	9.03	315				
CATERPILLAR															
3215	MOD 120-6 POWER SHIFT ARTIC	125 HP D	67,697	18.52	26.54	4.60	7.45	4.59	11.95	6.04	258				
3220	MOD 130-6 POWER SHIFT ARTIC	135 HP D	77,490	20.78	29.80	5.26	8.54	4.96	13.70	6.52	301				
3225	MOD 12-6 POWER SHIFT ARTIC	135 HP D	84,127	22.11	31.79	5.71	9.23	4.96	14.82	6.52	311				
3230	MOD 140-6 POWER SHIFT ARTIC	150 HP D	85,066	23.11	33.21	5.76	9.28	5.51	14.92	7.24	317				
3235	MOD 14-6 POWER SHIFT ARTIC	180 HP D	116,843	30.64	44.30	7.89	12.68	6.61	20.42	8.69	433				
3240	MOD 16-6 POWER SHIFT ARTIC	250 HP D	169,761	44.13	63.97	11.44	18.34	9.19	29.56	12.07	581				

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS			CWT					
			CONDITION	STAND-BY	AVERAGE	SEVERE	OWNER-SHIP	FUEL						
					AVERAGE	SEVERE	OWNER-SHIP	FUEL						
GRADERS MOTOR (CONT'D)														

FIAT-ALLIS														
3250	MOD-65 DIRECT DRIVE	59 HP D	37,472	9.89	14.31	2.53	4.06	2.17	6.54	2.85	125			
3255	MOD-100C CONSTANT MESH	135 HP D	71,842	19.87	28.48	4.87	7.86	4.96	12.63	6.52	310			
3260	MOD-150C POWER SHIFT	135 HP D	76,864	20.78	29.84	5.21	8.42	4.96	13.53	6.52	316			
3265	MOD-200C POWER SHIFT	160 HP D	82,877	23.15	33.18	5.61	9.05	5.88	14.55	7.73	322			
GALION														
3275	MOD 503-L DIRECT DRIVE	74 HP G	28,607	12.08	16.68	1.94	3.14	5.82	5.04	7.54	102			
3280	MOD T-500C POWER SHIFT	150 HP D	64,638	19.60	28.16	4.33	6.89	5.51	11.14	7.24	257			
3285	MOD T-600C POWER SHIFT	200 HP D	79,883	24.75	35.39	5.38	8.60	7.35	13.87	9.66	300			
WABCO														
3295	MOD 444 POWER SHIFT	134 HP D	69,422	19.26	27.56	4.72	7.64	4.92	12.26	6.47	302			
3300	MOD 555-B CONSTANT MESH	160 HP D	71,522	20.98	29.93	4.85	7.83	5.88	12.57	7.73	328			
3305	MOD 777-B POWER SHIFT	201 HP D	84,257	25.60	36.63	5.68	9.09	7.39	14.65	9.71	355			
HOISTS														

BENDIX-SKAGIT														
3315	BU-18W DOUBLE DRUM W/5/8" CABLE	100 HP D	45,246	15.76		3.23	5.77	3.99		85				
3320	G-70 DOUBLE DRUM W/7/8" CABLE	100 HP D	58,862	19.02		4.21	7.52	3.99		126				
3325	RB-80 DOUBLE DRUM W/1-1/8" CABLE	130 HP D	105,632	31.67		7.54	13.48	5.19		240				

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.					
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL				
HOISTS (CONT'D)													

GARDNER DENVER													
3335	HML SINGLE DRUM W/1/2" CABLE	350CFM A	5.330	1.37		0.38	0.68	0.00		10			
HYDRAULIC EXCAVATOR-CRAWLER MOUNTED													

T/B = TELESCOPING BOOM													
B/H = BACKHOE													
AMERICAN													
3345	MOD 25A	1.38 CY B/H 182 HP D	133.413	33.61	48.00	8.81	14.64	6.69	23.08	8.79			
3350	MOD 35A	2.00 CY B/H 250 HP D	191.969	47.84	68.38	12.67	21.06	9.19	33.20	12.07			
3355	MOD 45A	3.50 CY B/H 420 HP D	327.000	74.82	105.93	20.48	32.09	15.43	51.17	20.29			
BUCKYRUS ERIE													
3365	MOD 300-H	1.00 CY B/H 176 HP D	130.524	34.80	50.50	9.04	15.78	6.47	24.81	8.50			
3370	MOD 325-H	1.75 CY B/H 205 HP D	178.630	43.32	62.05	11.78	19.59	7.53	30.89	9.90			
3375	MOD 350-H	2.50 CY B/H 248 HP D	226.081	54.33	77.90	14.92	24.80	9.11	39.10	11.98			
CATEPILLAR													
3385	MOD 225	1.00 CY B/H 125 HP D	113.930	29.14	42.45	7.89	13.78	4.59	21.65	6.04			
3390	MOD 235	1.50 CY B/H 195 HP D	187.892	44.68	64.11	12.40	20.61	7.17	32.50	9.42			
3395	MOD 245	2.50 CY B/H 325 HP D	291.231	70.22	100.66	19.21	31.94	11.94	50.37	15.70			

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS			CWT				
			CONDITION		STAND-BY	AVERAGE COND.	SEVERE COND.						
			AVERAGE	SEVERE		OWNER-SHIP	FUEL						
HYDRAULIC EXCAVATOR-CRLR MNTD CONT'D													
***** T/B = TELESCOPING BOOM B/H = BACKHOE													
DROTT													
3405	MOD 40-D	1.00 CY B/H 157 HP D	85,338	24.58	35.40	5.91	10.32	5.77	16.22	7.58	400		
3410	MOD 50-D	1.25 CY B/H 190 HP D	108,800	29.21	41.52	7.18	11.93	6.98	18.82	9.18	510		
GRADALL													
3420	MOD G-660	.50 CY T/B 115 HP D	116,641	29.27	42.71	8.08	14.10	4.23	22.17	5.55	459		
3425	MOD G-880	.75 CY T/B 160 HP D	139,470	35.98	52.36	9.66	16.87	5.88	26.51	7.73	549		
3430	MOD G-1000	1.25 CY T/B 272 HP D	186,747	47.79	68.17	12.32	20.48	10.00	32.30	13.14	787		
HOP TO													
3440	MOD 211	1.13 CY B/H 160 HP D	115,859	29.27	41.80	7.65	12.71	5.88	20.04	7.73	521		
3445	MOD 311	1.88 CY B/H 235 HP D	161,223	41.27	58.85	10.64	17.69	8.64	27.88	11.35	743		
3450	MOD 900B	3.25 CY B/H 308 HP D	190,895	46.40	65.42	11.95	18.73	11.32	29.87	14.88	1009		
3455	MOD 1900	5.00 CY B/H 616 HP D	392,071	94.59	133.42	24.55	38.48	22.64	61.35	29.75	1998		
INSLEY													
3465	MOD H1500B	1.50 CY B/H 240 HP D	169,064	42.99	61.36	11.15	18.54	8.82	29.24	11.59	801		
3470	MOD H3500B	3.00 CY B/H 355 HP D	233,753	55.87	78.85	14.64	22.94	13.05	36.58	17.15	1149		
KOEHRING													
3480	MOD 866D	1.75 CY B/H 325 HP D	252,172	62.70	89.65	16.65	27.67	11.94	43.62	15.70	1197		
3485	MOD 1066D	2.50 CY B/H 380 HP D	311,965	76.60	109.63	20.59	34.22	13.96	53.96	18.35	1524		

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES				ADJUSTABLE ELEMENTS				CMT
			CONDITION	STAND-BY	AVERAGE COND.	SEVERE COND.	OWNER-SHIP	FUEL	OWNER-SHIP	FUEL	
	HYDRAULIC EXCAVATOR-CRLR MNTD CONT'D ***** T/B = TELESCOPING BOOM B/H = BACKHOE										
	KOEHRING (CONT'D)										
3490	MOD 1266D .50 CY B/H 760 HP D	641,404	143.99	204.14	40.16	62.94	27.93	100.36	36.71	2600	
	P & H										
3500	MOD H-750 .75 CY B/H 105 HP D	89,389	23.16	33.69	6.19	10.81	3.86	16.99	5.07	390	
3505	MOD H-1250 1.00 CY B/H 190 HP D	124,744	34.20	49.51	8.64	15.08	6.98	23.71	9.18	620	
	SHIELD BANTAM										
3515	MOD C166 .50 CY B/H 118 HP D	71,645	20.03	28.95	4.96	8.66	4.34	13.62	5.70	321	
	UNIT										
3525	MOD H202C .75 CY B/H 152 HP D	95,030	26.38	38.12	6.58	11.49	5.59	18.06	7.34	440	
3530	MOD H342 1.25 CY B/H 228 HP D	161,894	41.10	58.65	10.68	17.76	8.38	28.00	11.01	740	
3535	MOD H471 1.75 CY B/H 304 HP D	203,984	52.50	74.85	13.46	22.38	11.17	35.28	14.68	990	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT	
			CONDITION		STAND-BY	AVERAGE COND.	SEVERE COND.				
			AVERAGE	SEVERE							
HYDRAULIC EXCAVATOR-TRUCK MOUNTED ***** (HP & FUEL LISTED EQUIP/CARRIER) T/D = TELESCOPING BOOM B/H = BACKHOE											
3545	MOD G-660 .50 CY T/B 115/180 HP D/G	136,611	28.50	40.79	8.65	13.71	6.91	21.83	8.94	419	
3550	MOD G-880 .75 CY T/B 160/210 HP D/D	151,699	31.89	45.33	9.59	15.16	7.83	24.18	9.92	508	
3555	MOD G-1000 1.25 CY T/B 272/228 HP D/D	199,378	42.81	60.23	12.10	18.22	12.43	29.44	15.83	698	
LAND CLEARING EQUIPMENT ***** (ADD TO TRACTOR)											
3565	FLECO LAND CLEARING RAKE FOR D-7	19,367	4.42	6.61	1.39	2.48	0.00	3.90	0.00	107	
3570	FLECO LAND CLEARING RAKE FOR D-8	24,728	5.63	8.44	1.77	3.16	0.00	4.99	0.00	145	
3575	FLECO LAND CLEARING RAKE FOR D-9	31,219	7.09	10.64	2.23	3.99	0.00	6.30	0.00	200	
3580	FLECO CLAMP RAKE FOR CAT 977 (ADD TO 977 LOADER)	10,079	2.32	3.48	0.72	1.29	0.00	2.04	0.00	23	
LIGHTING SETS-TRAILER MOUNTED *****											
ALLMAND METALLIC VAPOR											
3590	30' TOWER 4/1000W LTS 5 KW 11 HP D	9,665	2.92		0.70	1.15	0.65			26	
OVER LOWE METALLIC VAPOR											
3600	38' TOWER 4/1000W LTS 6 KW 12 HP D	8,806	2.80		0.64	1.05	0.71			22	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.			
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL		
	LOADERS-BELT *****										
	KOLMAN										
3610	101XHD 24'X50' 355 T/HR 56 HP D	24,775	9.18	13.32	1.77	2.84	2.23	4.65	2.88	113	
	OPTIONAL EQUIPMENT SELECT AS NEEDED										
3620	PLATE FEEDER DOZER TRAP MODEL 45	3,493	0.81	1.22	0.26	0.42	0.00	0.68	0.00	37	
3625	BELT FEEDER DOZER TRAP MODEL 65	5,108	1.18	1.78	0.37	0.61	0.00	0.99	0.00	36	
3630	WING WALLS STATIONARY	925	0.21	0.32	0.07	0.11	0.00	0.18	0.00	9	
3635	TUNNEL EXTENSION W/WING WALLS	4,812	1.11	1.68	0.35	0.57	0.00	0.94	0.00	61	
3640	SINGLE DECK SCREEN SB-70 7'X42	3,758	0.86	1.31	0.27	0.44	0.00	0.73	0.00	19	
3645	DOUBLE DECK SCREEN DC-70-42 7'X42	4,609	1.06	1.61	0.33	0.55	0.00	0.90	0.00	26	
3650	TRIPLE DECK SCREEN TC-70-42 7'X42	5,822	1.34	2.04	0.42	0.69	0.00	1.14	0.00	34	
3655	XHD CONVEYOR JACKLEG	726	0.17	0.26	0.05	0.09	0.00	0.15	0.00	9	
3660	101XHD 30'X50' 615 T/HR 56 HP D	25,706	9.56	13.91	1.83	2.93	2.23	4.80	2.88	122	
	OPTIONAL EQUIPMENT SELECT AS NEEDED										
3670	PLATE FEEDER DOZER TRAP MODEL 45	4,352	1.00	1.52	0.32	0.52	0.00	0.85	0.00	42	
3675	BELT FEEDER DOZER TRAP MODEL 65	5,350	1.23	1.87	0.38	0.63	0.00	1.04	0.00	40	
3680	WING WALLS STATIONARY	925	0.21	0.32	0.07	0.11	0.00	0.18	0.00	9	
3685	TUNNEL EXTENSION W/WING WALLS	4,812	1.11	1.68	0.35	0.57	0.00	0.94	0.00	61	
3690	SINGLE DECK SCREEN SB-80 8'X48	4,215	0.97	1.47	0.31	0.50	0.00	0.82	0.00	23	
3695	DOUBLE DECK SCREEN DC-80-48 8'X48	5,340	1.22	1.87	0.38	0.63	0.00	1.04	0.00	35	
3700	TRIPLE DECK SCREEN TC-80-48 8'X48	6,563	1.51	2.28	0.47	0.78	0.00	1.27	0.00	43	
3705	XHD CONVEYOR JACKLEG	726	0.17	0.26	0.05	0.09	0.00	0.15	0.00	9	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.						
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL					
LOADERS-BELT (CONT'D)														

KOLMAN (CONT'D)														
3710	101XHD 36"X50' 910 T/HR	68 HP D	31.588	11.66	17.00	2.24	3.59	2.71	5.91	3.50	173			
OPTIONAL EQUIPMENT SELECT AS NEEDED														
3720	PLATE FEEDER DOZER TRAP MODEL 45		4.665	1.07	1.62	0.33	0.55	0.00	0.90	0.00	45			
3725	BELT FEEDER DOZER TRAP MODEL 65		5.666	1.30	1.98	0.41	0.67	0.00	1.10	0.00	42			
3730	WING WALLS STATIONARY		925	0.21	0.32	0.07	0.11	0.00	0.18	0.00	9			
3735	TUNNEL EXTENSION W/WING WALLS		4.812	1.11	1.68	0.35	0.57	0.00	0.94	0.00	61			
3740	SINGLE DECK SCREEN SB-90 9'X54		4.754	1.10	1.65	0.35	0.57	0.00	0.92	0.00	28			
3745	DOUBLE DECK SCREEN DC-90-54 9'X54		5.972	1.37	2.08	0.43	0.71	0.00	1.16	0.00	43			
3750	TRIPLE DECK SCREEN TC-90-54 9'X54		7.954	1.84	2.77	0.58	0.95	0.00	1.54	0.00	54			
3755	XHD CONVEYOR JACKLEG		726	0.17	0.26	0.05	0.09	0.00	0.15	0.00	9			
3760	101XHD 42"X50' 1260 T/HR	84 HP D	36.846	13.84	20.12	2.62	4.19	3.35	6.89	4.32	204			
OPTIONAL EQUIPMENT SELECT AS NEEDED														
3770	PLATE FEEDER DOZER TRAP MODEL 45		4.974	1.14	1.74	0.36	0.59	0.00	0.97	0.00	48			
3775	BELT FEEDER DOZER TRAP MODEL 65		6.518	1.51	2.28	0.47	0.78	0.00	1.27	0.00	45			
3780	WING WALLS STATIONARY		925	0.21	0.32	0.07	0.11	0.00	0.18	0.00	9			
3785	TUNNEL EXTENSION W/WING WALLS		4.812	1.11	1.68	0.35	0.57	0.00	0.94	0.00	61			
3790	SINGLE DECK SCREEN SB-100		5.935	1.37	2.07	0.43	0.71	0.00	1.15	0.00	37			
3795	DOUBLE DECK SCREEN DC-100-60 10'X		7.373	1.70	2.58	0.54	0.88	0.00	1.44	0.00	55			
3800	TRIPLE DECK SCREEN TC-100-60 10'X		9.234	2.13	3.22	0.67	1.10	0.00	1.79	0.00	68			
3805	XHD CONVEYOR JACKLEG		726	0.17	0.26	0.05	0.09	0.00	0.15	0.00	9			

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT			
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.				
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL			
LOADERS-BELT (CONT'D)												
\$888888888888888888												
KOLMAN (CONT'D)												
3810	101XHD 48'X50' 1700 T/HR	125 HP D	67,287	23.14	33.67	4.80	7.74	4.99	12.67	6.43	287	
OPTIONAL EQUIPMENT SELECT AS NEEDED												
3820	PLATE FEEDER DOZER TRAP MODEL 45		7,891	1.82	2.76	0.57	0.94	0.00	1.54	0.00	51	
3825	WING WALLS STATIONARY		925	0.21	0.32	0.07	0.11	0.00	0.18	0.00	9	
3830	TUNNEL EXTENSION W/WING WALLS		5,377	1.25	1.88	0.40	0.65	0.00	1.05	0.00	66	
3835	SINGLE DECK SCREEN SB-120 12'X		7,412	1.70	2.59	0.54	0.88	0.00	1.44	0.00	53	
3840	DOUBLE DECK SCREEN DC-120-72 12'X		9,087	2.10	3.16	0.66	1.09	0.00	1.76	0.00	77	
3845	TRIPLE DECK SCREEN TC-120-60 12'X		10,365	2.39	3.61	0.75	1.24	0.00	2.01	0.00	80	
3850	XHD CONVEYOR JACKLES		726	0.17	0.26	0.05	0.09	0.00	0.15	0.00	9	
3855	303 48'X50' 2000 CY/HR	125 HP D	110,981	33.33	49.04	7.95	12.91	4.99	21.08	6.43	627	
3860	303 48'X60' 2000 CY/HR	185 HP D	123,514	39.37	57.52	8.86	14.40	7.38	23.49	9.52	662	
3865	303 60'X50' 3600 CY/HR	185 HP D	127,626	40.43	59.12	9.16	14.88	7.38	24.27	9.52	682	
3870	303 60'X60' 3600 CY/HR	290 HP D	147,099	50.57	73.33	10.55	17.16	11.57	27.99	14.92	737	
OPTIONAL EQUIPMENT SELECT AS NEEDED												
3880	SINGLE DECK SCREEN SB-120 12'X		8,266	1.91	2.89	0.60	0.99	0.00	1.61	0.00	53	
3885	DOUBLE DECK SCREEN DC-120-72 12'X		10,126	2.33	3.53	0.73	1.20	0.00	1.96	0.00	77	
3890	TRIPLE DECK SCREEN TC-120-60 12'X		11,553	2.67	4.03	0.84	1.38	0.00	2.24	0.00	80	
3895	SINGLE DECK VIBRATING GRIZZLE 72'W		13,687	3.16	4.77	1.00	1.64	0.00	2.65	0.00	80	
3900	404 48'X50' 2000 CY/HR	185 HP D	140,544	43.66	64.06	10.08	16.38	7.38	26.72	9.52	607	
3905	404 48'X60' 2000 CY/HR	185 HP D	147,745	45.67	67.16	10.59	17.19	7.38	28.05	9.52	638	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.						
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL					
LOADERS-BELT (CONT'D)														
XXXXXXXXXXXXXXXXXXXX														
KOLMAN (CONT'D)														
3910	404 60'X50' 3600 CY/HR	290 HP D	164,980	55.10	80.24	11.84	19.24	11.57	31.38	14.92	658			
3915	404 60'X60' 3600 CY/HR	290 HP D	180,620	59.15	86.41	12.96	21.05	11.57	34.32	14.92	709			
OPTIONAL EQUIPMENT SELECT AS NEEDED														
3925	SINGLE DECK SCREEN SB-120 12'X		8,266	1.91	2.89	0.60	0.99	0.00	1.61	0.00	53			
3930	DOUBLE DECK SCREEN DC-120-72 12'X		10,126	2.33	3.53	0.73	1.20	0.00	1.96	0.00	77			
3935	TRIPLE DECK SCREEN TC-120-60 12'X		11,553	2.67	4.03	0.84	1.38	0.00	2.24	0.00	80			
3940	SINGLE DECK VIBRATING GRIZZLE 72'W		13,687	3.16	4.77	1.00	1.64	0.00	2.65	0.00	80			
LOADERS - F.E. TRACK TYPE														
XXXXXXXXXXXXXXXXXXXX														
CASE														
3950	350 3/4 CY	39 HP D	27,512	9.41	13.51	1.98	3.41	1.68	5.44	2.21	125			
3955	450 1 CY	53 HP D	37,466	12.80	18.40	2.69	4.64	2.28	7.42	3.01	160			
3960	850B 1-1/2 CY	72 HP D	49,782	17.11	24.56	3.58	6.17	3.10	9.85	4.08	220			
3965	1150B 2 CY	105 HP D	64,779	22.92	32.83	4.65	8.02	4.52	12.81	5.95	290			
CATERPILLAR														
3975	931 1 CY	62 HP D	36,280	13.02	18.66	2.61	4.49	2.67	7.18	3.52	151			
3980	941B 1-1/2 CY	80 HP D	51,418	18.00	25.81	3.70	6.37	3.44	10.17	4.54	257			
3985	951C 1-3/4 CY	95 HP D	55,673	19.99	28.60	4.01	6.90	4.09	11.01	5.39	270			
3990	955L 2-1/4 CY	130 HP D	76,378	27.40	39.21	5.49	9.46	5.60	15.11	7.37	355			
3995	977L 3-1/4 CY	190 HP D	114,099	40.68	58.23	8.20	14.13	8.18	22.56	10.77	507			

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.						
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL					
LOADERS - F.E. TRACK TYPE (CONT'D)														

CATERPILLAR (CONT'D)														
4000	983	5 CY	275 HP D	173.877	61.13	87.62	12.50	21.54	11.84	34.39	15.59	783		
FIAT-ALLIS														
4010	FL9	1-5/8 CY	87 HP D	47.552	17.42	24.88	3.42	5.89	3.75	9.41	4.93	272		
4015	FL10C	1-7/8 CY	122 HP D	61.588	23.12	32.96	4.43	7.63	5.25	12.18	6.92	312		
4020	FL14C	2-1/2 CY	150 HP D	76.844	28.71	40.94	5.52	9.52	6.46	15.20	8.50	436		
INTERNATIONAL														
4030	100-E	1 CY	65 HP D	36.292	13.20	18.89	2.61	4.49	2.80	7.18	3.69	160		
4035	125-E	1-1/4 CY	78 HP D	43.290	15.79	22.57	3.11	5.36	3.36	8.57	4.42	198		
4040	175-C	2 CY	134 HP D	66.692	25.14	35.85	4.80	8.26	5.77	13.20	7.60	317		
4045	250-C	2-3/4 CY	190 HP D	98.745	36.73	52.40	7.10	12.23	8.18	19.53	10.77	443		
JOHN DEERE														
4055	JD350-C	3/4 CY	42 HP D	26.577	9.34	13.39	1.91	3.29	1.81	5.26	2.38	119		
4060	JD450-C	1-1/4 CY	65 HP D	35.493	13.01	18.58	2.56	4.40	2.80	7.02	3.69	167		

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.					
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL				
LOADERS - F.E. WHEEL TYPE													
XXXXXXXXXXXXXXXXXXXXXX													
BORGART													
4070	MOD 630	1/2 CY SKID-STEER	30 HP D	9.025	5.32	7.40	0.64	1.09	2.55	1.77	3.33	34	
CASE													
4080	W-14	1-1/2 CY ARTIC	83 HP D	46.050	14.89	21.85	3.28	5.55	3.31	8.92	4.27	148	
4085	W-18	2 CY ARTIC	103 HP D	56.549	18.41	27.06	4.03	6.80	4.11	10.94	5.30	199	
4090	W-24 C	2-1/2 CY ARTIC	132 HP D	78.422	25.58	38.33	5.54	9.28	5.27	14.98	6.79	236	
4095	W-36	3-1/2 CY ARTIC	185 HP D	93.860	32.33	48.35	6.62	11.06	7.38	17.87	9.52	332	
CATERPILLAR													
4105	920	1-3/4 CY ARTIC	80 HP D	49.470	15.45	22.71	3.53	5.97	3.19	9.60	4.12	183	
4110	930	2-1/4 CY ARTIC	100 HP D	57.135	18.37	27.02	4.07	6.87	3.99	11.05	5.14	205	
4115	950	3 CY ARTIC	130 HP D	78.246	25.12	37.40	5.54	9.32	5.19	15.03	6.69	284	
4120	966-C	4 CY ARTIC	170 HP D	102.962	33.41	50.13	7.28	12.18	6.78	19.66	8.75	374	
4125	980-C	5-1/4 CY ARTIC	270 HP D	148.389	47.59	71.02	9.83	16.17	10.77	25.79	13.89	577	
4130	988-B	7 CY ARTIC	375 HP D	223.697	70.58	106.13	14.79	24.28	14.96	38.77	19.29	888	
4135	992-C	12-1/2 CY ARTIC	690 HP D	452.891	142.27	217.42	29.80	48.60	27.53	77.81	35.50	1908	
CLARK													
4145	35C	1-1/4 CY	74 HP D	42.598	13.46	19.66	3.04	5.16	2.95	8.29	3.81	171	
4150	55-B	2 CY ARTIC	114 HP D	60.318	19.78	28.95	4.29	7.27	4.55	11.70	5.87	247	
4155	75-B	2-1/2 CY ARTIC	142 HP D	81.429	26.70	39.79	5.76	9.67	5.67	15.59	7.31	303	
4160	125B	3-1/2 CY ARTIC	212 HP D	110.272	38.30	57.93	7.74	12.85	8.46	20.81	10.91	419	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT		
			CONDITION	AVERAGE	SEVERE	STAND-BY	AVERAGE COND.	SEVERE COND.				
OWNER-SHIP	FUEL	OWNER-SHIP	FUEL									
	LOADERS - F.E. WHEEL TYPE (CONT'D)											

	CLARK (CONT'D)											
4165	175-B	4-1/2 CY ARTIC	273 HP D	138,901	45.87	68.48	9.19	15.09	10.89	24.08	14.05	527
4170	275-B	6-1/2 CY ARTIC	344 HP D	195,548	61.84	92.13	12.96	21.36	13.73	34.05	17.70	739
4175	475-B	12 CY ARTIC	632 HP D	378,800	120.89	183.20	24.97	40.83	25.22	65.30	32.52	1544
	FIAT-ALLIS											
4185	345-B	1-3/4 CY ARTIC	80 HP D	47,429	15.02	22.07	3.38	5.72	3.19	9.19	4.12	174
4190	545-B	2 CY ARTIC	102 HP D	58,082	18.69	27.47	4.13	6.99	4.07	11.24	5.25	217
4195	605-B	2-1/2 CY ARTIC	108 HP D	61,261	19.68	28.89	4.36	7.38	4.31	11.86	5.56	238
4200	645-B	3 CY ARTIC	151 HP D	80,300	26.73	39.55	5.70	9.58	6.02	15.44	7.77	286
4205	745-C	4 CY ARTIC	202 HP D	107,329	37.11	56.27	7.53	12.48	8.06	20.22	10.39	418
4210	945-B	6 CY ARTIC	335 HP D	191,760	62.20	94.32	12.63	20.62	13.37	33.00	17.24	708
	INTERNATIONAL											
4220	515	1-3/4 CY	95 HP D	43,390	14.94	21.71	3.10	5.24	3.79	8.42	4.89	161
4225	H-60E	2-1/4 CY ARTIC	104 HP D	49,652	16.88	24.61	3.54	5.98	4.15	9.62	5.35	205
4230	H-90E	4-1/2 CY ARTIC	239 HP D	110,356	36.87	54.17	7.33	12.11	9.54	19.29	12.30	402
4235	H-100-C	5 CY ARTIC	290 HP D	123,186	43.41	64.57	8.13	13.33	11.57	21.31	14.92	487
4240	560	6-1/2 CY ARTIC	380 HP D	184,247	61.47	91.31	12.19	20.06	15.16	32.01	19.55	796
4245	H-400-C	11 CY ARTIC	580 HP D	329,571	105.72	158.94	21.78	35.72	23.14	57.04	29.84	1254

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT									
			CONDITION		STAND-BY	AVERAGE COND. OWNER-SHIP	SEVERE COND. OWNER-SHIP												
			AVERAGE	SEVERE															
LOADERS - F.E. WHEEL TYPE (CONT'D) *****																			
TEREX (GM)																			
4255	72-31B	3 CY ARTIC	160 HP D	77.061	26.55	39.18	5.46	9.18	6.38	14.80	8.23	277							
4260	72-51B	4 CY ARTIC	231 HP D	110.021	37.47	56.11	7.26	11.88	9.22	18.99	11.88	392							
4265	72-61	5-1/2 CY ARTIC	307 HP D	143.944	49.44	74.19	9.49	15.51	12.25	24.80	15.80	562							
4270	72-71B	7-1/2 CY ARTIC	388 HP D	199.796	64.94	96.28	13.25	21.84	15.48	34.81	19.96	846							
4275	72-81	9 CY ARTIC	434 HP D	303.197	90.22	134.98	20.12	33.21	17.32	52.91	22.33	1149							
YALE																			
4285	1500-C	1-3/4 CY ARTIC	98 HP D	44.265	15.26	22.18	3.15	5.34	3.91	8.59	5.04	166							
4290	1700-C	2 CY ARTIC	136 HP G	52.475	27.09	38.29	3.73	6.29	11.58	10.14	15.09	193							
4295	1900-C	2-1/4 CY ARTIC	136 HP D	55.243	19.98	29.03	3.92	6.63	5.43	10.68	7.00	203							
4300	2000-C	3 CY ARTIC	165 HP D	73.715	26.13	38.49	5.22	8.77	6.58	14.13	8.49	278							
4305	2500-C	3-3/4 CY ARTIC	182 HP D	94.700	33.12	50.34	6.63	10.97	7.26	17.79	9.36	369							
4310	3000-C	4-1/4 CY ARTIC	255 HP D	99.356	36.23	53.81	6.55	10.72	10.17	17.16	13.12	409							
4315	5500-C	5-1/2 CY ARTIC	320 HP D	140.968	48.33	71.27	9.35	15.40	12.77	24.54	16.46	590							
4320	7500-C	6-1/2 CY ARTIC	400 HP D	190.111	64.72	96.85	12.55	20.54	15.96	32.83	20.58	778							

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS			CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.					
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL				
LOADER-BACKHOE IND. TYPE TRACTOR *****													
CASE													
4330	580C LDR/BHOE	7/8 CY FE BUCKET	55 HP D	30,413	9.38	13.61	2.17	3.70	2.19	5.95	2.83	114	
			24° B/H DIPPER										
4335	680E LDR/BHOE	1-1/4 CY FE BUCKET	80 HP D	44,576	13.80	20.05	3.19	5.42	3.19	8.69	4.12	152	
			30° B/H DIPPER										
JOHN DEERE													
4345	410 LDR/BHOE	1 CY FE BUCKET	66 HP D	31,286	10.29	14.97	2.23	3.77	2.63	6.07	3.40	137	
			24° B/H DIPPER										
4350	510B LDR/BHOE	1-1/2 CY FE BUCKET	83 HP D	47,426	14.62	21.28	3.39	5.75	3.31	9.22	4.27	205	
			30° B/H DIPPER										
LOADER-BACKHOE CRLR TYPE TRACTOR *****													
CASE													
4360	350 LDR/BHOE	3/4 CY FE BUCKET	39 HP D	37,599	12.01	17.35	2.70	4.66	1.68	7.44	2.21	141	
			24° B/H DIPPER										
4365	450 LDR/BHOE	1 CY FE BUCKET	53 HP D	47,530	15.39	22.23	3.41	5.88	2.28	9.41	3.01	167	
			24° B/H DIP										
CATERPILLAR													
4375	931 LDR/BHOE	1 CY FE BUCKET	62 HP D	44,638	15.18	21.84	3.21	5.53	2.67	8.84	3.52	187	
			30° B/H DIPPER										

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.		
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL	
LOADER-BACKHOE ATTACHMENT'S *****										
	HYDRAULICALLY OPERATED IMPACTOR MOUNTED ON BACKHOE BOOM TO FIT CASE AND JOHN DEERE BACKHOES (ADD TO BASIC LOADER-BACKHOE)									
4385	IMPACTOR WITH TAMPER TOOL	9,532	3.59		0.83	1.72	0.00		12	
4390	IMPACTOR WITH CHISEL TOOL	8,991	3.39		0.78	1.62	0.00		11	
PILE EXTRACTORS *****										
	MKT CORPORATION									
4400	E2 700 FT-LBS 400CFM A	10,853	4.17		0.94	1.96	0.00		26	
4405	E4 1000 FT-LBS 550CFM A	16,672	6.30		1.45	3.01	0.00		45	
VULCAN										
4415	400A 500 FT-LBS 450CFM A	13,660	5.20		1.19	2.47	0.00		29	
4420	800A 1000 FT-LBS 900CFM A	18,404	6.93		1.60	3.32	0.00		55	
4425	1200A 1640 FT-LBS 1350CFM A	21,483	8.06		1.86	3.88	0.00		92	
PILE HAMMERS-DIESEL ***** (FUEL NOT INCLUDED)										
	MKT CORPORATION									
4435	DE-20B/30B (6-FT) 12,000 FT-LBS	27,654	10.18		2.41	5.00	0.00		74	
4440	DE-20B/30B (6-FT) 16,800 FT-LBS	28,762	10.58		2.50	5.20	0.00		82	
4445	DE-50B/70B (6-FT) 30,000 FT-LBS	52,097	19.12		4.53	9.41	0.00		138	
450	DE-50B/70B (6-FT) 42,000 FT-LBS	55,317	20.30		4.80	9.99	0.00		158	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.						
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL					
PILE HAMMERS-SINGLE ACTING														

VULCAN														
4460	1	15000 FT-LBS	750CFM A	23.283	8.72		2.02	4.20	0.00	101				
4465	106	19000 FT-LBS	750CFM A	29.521	11.01		2.56	5.33	0.00	121				
4470	06	19500 FT-LBS	900CFM A	26.651	9.95		2.31	4.81	0.00	121				
4475	08	26000 FT-LBS	1100CFM A	29.879	11.14		2.60	5.40	0.00	178				
4480	010	32500 FT-LBS	1350CFM A	32.726	12.18		2.84	5.91	0.00	198				
4485	014	42000 FT-LBS	1750CFM A	47.111	17.45		4.09	8.51	0.00	283				
4490	016	48750 FT-LBS	1750CFM A	56.038	20.71		4.86	10.12	0.00	326				
4495	020	60000 FT-LBS	2150CFM A	59.791	22.09		5.19	10.80	0.00	425				
4500	030	90000 FT-LBS	2350CFM A	87.270	32.15		7.58	15.76	0.00	550				
PILE HAMMERS-DOUBLE ACTING														

MKT CORPORATION														
4510	9-B-3	8750 FT-LBS	900CFM A	20.038	7.54		1.74	3.62	0.00	72				
4515	10-B-3	13100 FT-LBS	1200CFM A	25.788	9.63		2.24	4.65	0.00	111				
4520	11-B-3	19150 FT-LBS	1200CFM A	33.474	12.46		2.91	6.05	0.00	138				
4525	5 (SELF STOP)	1000 FT-LBS	375CFM A	7.692	3.02		0.67	1.39	0.00	16				
4530	6 (SELF STOP)	2500 FT-LBS	600CFM A	9.222	3.57		0.80	1.66	0.00	30				
4535	7 (SELF STOP)	4150 FT-LBS	750CFM A	12.424	4.74		1.08	2.24	0.00	49				

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.						
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL					
PILE HAMMERS-DOUBLE ACTING (CONT'D)														

VULCAN														
4545	50C	15100 FT-LBS	1250CFM A	27.827	10.39		2.42	5.03	0.00	127				
4550	65C	19200 FT-LBS	1450CFM A	31.895	11.88		2.77	5.76	0.00	158				
4555	80C	24450 FT-LBS	1750CFM A	32.651	12.15		2.83	5.89	0.00	191				
4560	100C	32900 FT-LBS	2050CFM A	33.374	12.41		2.89	6.02	0.00	232				
4565	140C	36000 FT-LBS	2150CFM A	44.012	16.31		3.83	7.95	0.00	287				
4570	200C	50200 FT-LBS	2550CFM A	67.040	24.74		5.83	12.11	0.00	422				
4575	400C	113500 FT-LBS	5800CFM A	182.905	67.17		15.89	33.04	0.00	850				
PILE HAMMERS-VIBRATORY														

MKT CORPORATION														
4585	V5	WITH POWER PACK	59 HP D	46.975	20.20		4.08	8.48	2.35	131				
4590	V16	WITH POWER PACK	156 HP D	93.690	42.26		8.14	16.92	6.22	225				
4595	V18	WITH POWER PACK	248 HP D	136.049	62.47		11.81	24.57	9.90	304				
PIPELAYER														

CATERPILLAR														
4605	561D	15 FT BOOM, 40,000 LB CAP 105 HP D		80.793	15.37	22.79	5.53	9.02	2.32	14.42	2.98	280		
4610	571G	18 FT BOOM, 60,000 LB CAP 200 HP D		137.552	26.77	39.58	9.40	15.35	4.41	24.54	5.67	500		
4615	572G	18 FT BOOM, 90,000 LB CAP 200 HP D		157.421	29.79	44.22	10.76	17.56	4.41	28.09	5.67	605		
4620	583K	20 FT BOOM, 140,000 LB CAP 300 HP D		203.743	39.76	58.77	13.93	22.73	6.61	36.35	8.50	900		

EP 1110-1-8
 (Vol. 2)
 15 Jun 81

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT
			CONDITION	STAND-BY	AVERAGE	SEVERE	AVERAGE COND.	SEVERE COND.		
							OWNER-SHIP	FUEL	OWNER-SHIP	
	PIPELAYER (CONT'D) *****									
	CATERPILLAR (CONT'D)									
4625	594G 24 FT BOOM, 200,000 LB CAP 410 HP D	290,240	56.13	83.06	19.83	32.38	9.04	51.77	11.62	1230
	PUMPS-GROUT *****									
	G.M. PHILPOTT GROUT UNITS WITH GARDNER-DENVER PUMPS									
4635	SSF2-10 W/ (2 EA) FG-AG 6" X 3" X 6" PUMPS UNIT INCLUDES (2)-10 C.F. TANKS, AUTO. WATER METER, FITTINGS, HOSES & SKID MOUNTING CAPACITY: 21 GPM @ 252 PSI TO 60 GPM @ 90 PSI	600CFM A	19.844	5.84			1.54	2.93	0.00	64
4640	SSF2-20 W/ (2 EA) FD-FS 10" X 3" X 10" PUMPS UNIT INCLUDES (2)-20 C.F. TANKS, AUTO. WATER METER, FITTINGS, HOSES & SKID MOUNTING CAPACITY: 32 GPM AT 700 PSI TO 98 GPM @ 252 PSI	900CFM A	31.036	9.10			2.40	4.58	0.00	107
	PUMPS-WATER-FOR CORE DRILLS *****									
	LONGYEAR									
4650	520 RQ 5.7-20 GPM UP TO 600PSI	10 HP G	4,122	2.49			0.30	0.53	1.17	7
4655	535 RQ 9.9-35 GPM UP TO 800PSI	15 HP G	5,266	3.52			0.38	0.68	1.76	10

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS			CWT
			CONDITION	STAND-BY	AVERAGE COND.	SEVERE COND.			
			AVERAGE	SEVERE	OWNER-SHIP	FUEL	OWNER-SHIP	FUEL	
PUMPS-WATER-CENTRIF.-DEWATERING									

HOMELITE, SKID MOUNTED									
4665	MOD 110S 1-1/2"-5000 GPH @ 30' H 2 HP G	336	0.39		0.03	0.05	0.23		1
4670	MOD 111S 2" - 9000 GPH @ 22' H 3 HP G	375	0.55		0.03	0.05	0.35		1
4675	MOD 120SP 3" - 18000 GPH @ 20' H 6 HP G	566	1.06		0.04	0.07	0.70		2
MARLOW, WHEEL MOUNTED									
4685	MOD 4D2 465 GPM @ 20' HEAD 59 HP G	6,150	10.54		0.44	0.78	6.93		14
4690	MOD 4D2 470 GPM @ 20' HEAD 47 HP D	8,001	5.42		0.57	1.02	2.62		15
4695	MOD 6E4A 1095 GPM @ 20' HEAD 117 HP G	7,338	19.80		0.53	0.94	13.73		18
4700	MOD 6E4A 1090 GPM @ 20' HEAD 80 HP D	11,695	8.80		0.84	1.50	4.45		24
4705	MOD 8FA3 2200 GPM @ 20' HEAD 108 HP D	14,332	11.54		1.02	1.83	6.01		23
4710	MOD 1061 2840 GPM @ 20' HEAD 108 HP D	15,954	11.91		1.14	2.04	6.01		30
PUMPS-WATER-CENTRIF.-TRASH									

HOMELITE, SKID MOUNTED									
4720	MOD 121TP 2" - 11500 GPH @ 20' H 4 HP G	533	0.74		0.04	0.07	0.47		2
4725	MOD 122TP 3" - 21600 GPH @ 20' H 4 HP G	729	0.78		0.05	0.09	0.47		3
4730	MOD 123TP 4" - 36500 GPH @ 20' H 10 HP G	1,334	1.85		0.10	0.17	1.17		4

EP 1110-1-8
(Vol. 2)
15 Jun 81

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT	
			CONDITION	SEVERE	STAND-BY	AVERAGE COND.		SEVERE COND.			
						OWNER-SHIP	FUEL	OWNER-SHIP	FUEL		
	PUMPS-WATER-DIAPHRAGM *****										
	HOMELITE, SKID MOUNTED										
4740	MOD 111DP 2" - 1900 GPH @ 10' HD 4 HP G	627	0.76		0.04	0.08	0.47			2	
4745	MOD 111DP 3" - 4140 GPH @ 10' HD 4 HP G	1,415	0.94		0.10	0.18	0.47			3	
	PUMPS-WATER-SUBMERSIBLE *****										
	HOMELITE										
4755	MOD SP-2 2" - 7400 GPH @ 10' HD 2 HP E	693	0.26		0.05	0.09	0.10			1	
4760	MOD SP-3 3" - 19000 GPH @ 15' HD 5 HP E	1,242	0.58		0.09	0.16	0.25			2	
	RIPPER & HYDR. BANK SLOPER ***** (DOES NOT INCLUDE COST OF POINT WEAR)										
	ATECO										
4770	VRAR-1 D9H RADIAL LIFT	29,599	8.05	12.48	2.29	4.38	0.00	7.01	0.00	136	
4775	D-9H SHANKS EA	2,249	0.60	0.94	0.17	0.33	0.00	0.53	0.00	15	
4780	LPAS-D8K PARALLEL LIFT	16,783	4.58	7.11	1.30	2.48	0.00	3.98	0.00	87	
4785	D-8K SHANKS EA	3,135	0.85	1.31	0.25	0.47	0.00	0.74	0.00	19	
4790	LPAS-D7G PARALLEL LIFT	13,492	3.69	5.71	1.04	1.99	0.00	3.19	0.00	45	
4795	D-7G SHANKS EA	2,238	0.60	0.94	0.17	0.33	0.00	0.53	0.00	10	
4800	PS D6D RADIAL LIFT	6,534	1.82	2.80	0.51	0.97	0.00	1.55	0.00	24	
4805	D-6C SHANKS EA	214	0.06	0.10	0.02	0.03	0.00	0.06	0.00	1	
4810	V-LPRF-TD25C PARALLEL LIFT STD SVC	14,970	4.09	6.34	1.15	2.21	0.00	3.55	0.00	P	
4815	TD-25C SHANKS EA	1,351	0.37	0.57	0.10	0.20	0.00	0.32	0.00	8	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS			CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.					
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP					
RIPPER & HYDR. BANK SLOPER (CONT'D) ***** (DOES NOT INCLUDE COST OF POINT WEAR)													
ATECO (CONT'D)													
4820	V-LPRF-TD20E PARALLEL LIFT STD SVC	10,986	3.01	4.66	0.85	1.62	0.00	2.60	0.00	51			
4825	TD-20E SHANKS EA	990	0.26	0.41	0.07	0.14	0.00	0.23	0.00	4			
4830	PS-TD15C RADIAL LIFT	6,198	1.72	2.66	0.48	0.91	0.00	1.47	0.00	22			
4835	TD-15C SHANKS EA	214	0.06	0.10	0.02	0.03	0.00	0.06	0.00	1			
4840	V-LPRF 82-50 PARALLEL LIFT STD SVC	16,908	4.62	7.15	1.31	2.50	0.00	4.00	0.00	96			
4845	82-50 SHANKS EA	1,351	0.37	0.57	0.10	0.20	0.00	0.32	0.00	8			
4850	LPRS-82-50 PARALLEL LIFT EXT SVC	16,447	4.49	6.95	1.27	2.43	0.00	3.89	0.00	88			
4855	82-50 SHANKS EA	3,135	0.85	1.31	0.25	0.47	0.00	0.74	0.00	19			
4860	V-LPRF-82-30 PARALLEL LIFT	14,970	4.09	6.34	1.15	2.21	0.00	3.55	0.00	89			
4865	82-30 SHANKS EA	1,351	0.37	0.57	0.10	0.20	0.00	0.32	0.00	8			
4870	D9,D8;82-30,82-50;TD25 HYDR BANK SLOP	6,442	1.51	2.25	0.46	0.83	0.00	1.31	0.00	28			
CATERPILLAR													
4880	D-10 MULTI-SHANK BEAM	33,702	9.15	14.20	2.60	4.98	0.00	7.98	0.00	150			
4885	D-10 SHANKS EA	2,473	0.66	1.04	0.19	0.36	0.00	0.59	0.00	16			
4890	D-10 SINGLE-SHANK BEAM	36,304	9.80	15.24	2.81	5.37	0.00	8.59	0.00	165			
4895	D-9 MULTI-SHANK BEAM W/HYD-CONTROL	26,429	7.19	11.15	2.04	3.91	0.00	6.26	0.00	132			
4900	D-9 SHANKS EA	1,302	0.35	0.55	0.10	0.19	0.00	0.31	0.00	8			
4905	D-9 SINGLE-SHANK BEAM HYD-CNTL&SHANK	24,596	6.69	10.38	1.90	3.64	0.00	5.82	0.00	124			
4910	D-8 MULTI-SHANK BEAM HYD-CONTROL	18,641	5.09	7.88	1.44	2.76	0.00	4.41	0.00	103			

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CNT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.						
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL					
RIPPER & HYDR. BANK SLOPER (CONT'D) ***** (DOES NOT INCLUDE COST OF POINT WEAR)														
CATERPILLAR (CONT'D)														
4915	D-8 SHANKS EA	1,250	0.34	0.53	0.10	0.19	0.00	0.30	0.00	7				
4920	D-8 SINGLE-SHANK BEAM HYD-CNTL&SHANK	18,111	4.94	7.65	1.40	2.68	0.00	4.28	0.00	100				
4925	D-7 MULTI-SHANK BEAM HYD-CONTROL	10,820	2.97	4.60	0.84	1.60	0.00	2.57	0.00	53				
4930	D-7 SHANKS EA	651	0.17	0.28	0.05	0.09	0.00	0.16	0.00	4				
4935	D-6 MULTI-SHANK BEAM HYD-CONTROL	6,789	1.88	2.90	0.52	1.00	0.00	1.61	0.00	27				
4940	D-6 SHANKS EA	335	0.09	0.14	0.03	0.05	0.00	0.08	0.00	~				
4945	D-4 MULTI-SHANK BEAM HYD-CONTROL	4,168	1.17	1.80	0.32	0.61	0.00	0.99	0.00	14				
4950	D-4 SHANKS EA	176	0.05	0.07	0.02	0.03	0.00	0.04	0.00	1				
4955	D-3 FIVE-SHANK BEAM HYD-CONTROL	1,862	0.56	0.83	0.15	0.28	0.00	0.44	0.00	6				
4960	D-3 SHANKS EA	98	0.03	0.05	0.01	0.02	0.00	0.03	0.00	1				
FIAT-ALLIS														
4970	41-R W/HYD-CNTL AND 2 SHANKS	37,975	10.31	16.00	2.94	5.62	0.00	8.99	0.00	204				
4975	31-R W/HYD-CNTL AND 2 SHANKS	30,560	8.30	12.89	2.36	4.52	0.00	7.24	0.00	188				
4980	21-R W/HYD-CNTL AND 2 SHANKS	19,698	5.37	8.32	1.52	2.91	0.00	4.66	0.00	108				
4985	16-R W/HYD-CNTL AND 2 SHANKS	12,365	3.38	5.25	0.95	1.82	0.00	2.93	0.00	73				

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT								
			CONDITION	STAND-BY	AVERAGE OWNER-SHIP	COND.		SEVERE OWNER-SHIP									
						AVERAGE	SEVERE										
ROLLERS-RUBBER-TIRED-SELF PROPELLED *****																	
INGRAM																	
4995	9-2800-P	12 TON	107 HP G	19,845	16.08	1.40	2.48	9.11	77								
5000	9-2800-PA	12 TON	76 HP D	24,438	9.63	1.73	3.07	3.03	89								
5005	11-2700	15 TON	107 HP G	23,672	17.01	1.67	2.96	9.11	89								
5010	11-2700	15 TON	76 HP D	26,050	10.04	1.85	3.27	3.03	91								
5015	13-2300	15 TON	107 HP G	24,139	17.14	1.71	3.01	9.11	94								
5020	13-2300	15 TON	76 HP D	27,199	10.33	1.92	3.40	3.03	96								
5025	9-6000	27 TON	117 HP D	58,051	19.93	4.08	7.18	4.67	208								
5030	7-10000	35 TON	148 HP D	63,018	22.87	4.40	7.67	5.91	241								
ROLLER-RUBBER TIRED-TOWED *****																	
5040	FERGUSON RT-100S	50 TON		37,531	9.15	2.55	4.27	0.00	200								
5045	FERGUSON RT-120S	60 TON		43,723	10.61	2.99	5.06	0.00	233								
5050	SOUTHWEST C 75	75 TON		51,418	12.53	3.50	5.88	0.00	347								
5055	SOUTHWEST C 50	50 TON		48,843	11.89	3.32	5.60	0.00	309								

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT			
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.				
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL			
ROLLER-SHEEPS FOOT-DOUBLE DRUM												

FERGUSON-TOWED												
5065	MOD 112	40"X48"	7,703	1.92	0.55	0.98	0.00		65			
5070	MOD 112W-48	48"X48"	9,794	2.42	0.70	1.25	0.00		105			
5075	MOD 120	60"X60"	15,087	3.68	1.08	1.93	0.00		157			
5080	MOD 120 MODIFIED	60"X60"	29,149	7.01	2.08	3.73	0.00		230			
5085	MOD 120-RE	60"X60"	35,557	8.54	2.54	4.56	0.00		327			
5090	MOD 22	60"X72"	20,926	5.06	1.50	2.68	0.00		215			
5095	MOD 22 MODIFIED	60"X72"	33,852	8.13	2.42	4.34	0.00		27			
5100	MOD 144-RE	60"X72"	41,483	9.94	2.96	5.31	0.00		385			
CATERPILLER-SELF PROPELLED												
5110	815	40.5"X38"	170 HP D	87,809	29.23	6.27	11.24	6.78	360			
5115	825C	51"X41.5"	300 HP D	157,718	52.23	11.26	20.19	11.97	631			
5120	825C	W/S BLADE	300 HP D	166,141	54.23	11.86	21.27	11.97	683			
HYSSTER-SELF PROPELLED												
5130	C455-B	TANDEM	60"X72" ARTIC	330 HP D	159,249	54.09	11.37	20.39	13.17	523		

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CMT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.			
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL		
	ROLLER-SMOOTH WHEEL-SELF PROPELLED \$										
	INGRAM										
5140	8 TON 3 WHEEL 3" OVERLAP	107 HP G	29.314	18.25		2.09	3.75	9.11		124	
5145	8 TON 3 WHEEL 3" OVERLAP	76 HP D	32.375	11.43		2.31	4.14	3.03		126	
5150	12 TON 3 WHEEL 3" OVERLAP	107 HP G	35.531	19.73		2.54	4.55	9.11		203	
5155	12 TON 3 WHEEL 3" OVERLAP	86 HP D	38.593	13.40		2.76	4.94	3.43		205	
5160	14 TON 3 WHEEL 3" OVERLAP	107 HP G	37.625	20.22		2.69	4.82	9.11		241	
5165	14 TON 3 WHEEL 3" OVERLAP	86 HP D	40.686	13.90		2.91	5.21	3.43		243	
5170	4-6 TON 2 WHEEL TANDEM	53 HP G	17.980	9.85		1.28	2.30	4.51		82	
5175	6-9 TON 2 WHEEL TANDEM	107 HP G	24.200	17.04		1.73	3.10	9.11		133	
5180	6-9 TON 2 WHEEL TANDEM	76 HP D	27.261	10.22		1.95	3.49	3.03		135	
5185	8-12 TON 2 WHEEL TANDEM	107 HP G	29.276	18.24		2.09	3.75	9.11		171	
5190	8-12 TON 2 WHEEL TANDEM	76 HP D	32.337	11.43		2.31	4.14	3.03		173	
5195	10-14 TON 2 WHEEL TANDEM	107 HP G	31.588	18.80		2.26	4.05	9.11		258	
5200	10-14 TON 2 WHEEL TANDEM	76 HP D	34.654	11.98		2.48	4.44	3.03		262	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT					
			CONDITION	STAND-BY	AVERAGE COND.		SEVERE COND.							
					AVERAGE	SEVERE	OWNER-SHIP	FUEL						
ROLLER-VIBRATORY ***** TF=ROLLER W/TAMPING FEET														
TOWED														
5210	FERGUSON 652 TF 60"X60" 9 TON 49 HP D	27,551	12.73		2.13	3.92	2.73		125					
5215	SOUTHWEST 756 TF 66"X78" 20 TON 75 HP D	55,063	23.85		4.26	7.84	4.17		240					
5220	FERGUSON 230 66"X78" 20 TON 66 HP D	40,981	18.45		3.17	5.83	3.67		234					
5225	FERGUSON 230 TF 66 HP D	44,641	19.69		3.45	6.35	3.67		266					
5230	HYSTER C200B 48"X60" 12.5 TON 36 HP D	22,025	9.95		1.70	3.13	2.00		87					
5235	HYSTER C210A TF 58"X60" 14 TON 39 HP D	25,849	11.46		2.00	3.68	2.17		100					
SELF PROPELLED SINGLE DRUM														
5245	VIBRO PLUS CA-25 60"X84" 23 TON 125 HP D	49,978	25.65		3.84	7.00	6.96		198					
5250	VIBRO PLUS CA-25S 61"X84" 28 TON 125 HP D	53,140	26.71		4.07	7.44	6.96		203					
5255	VIBRO PLUS CA-25PD 60"X48" 30 TON 125 HP D	61,405	29.52		4.71	8.62	6.96		240					
5260	RAYGO RASCAL 400A 59"X84" ARTIC 88 HP D	54,948	24.77		4.22	7.72	4.90		197					
5265	RAYGO RASCAL 600A 60"X100"	119 HP D	67,876	31.31	5.21	9.52	6.62		288					
5270	I-RAND SP-60 60"X100"	210 HP D	109,428	51.81	8.36	15.18	11.69		450					
5275	I-RAND SPF-54 TF 54"X85"	120 HP D	63,209	29.76	4.86	8.91	6.68		264					
5280	FERGUSON SP 75D	120 HP D	54,137	26.70	4.16	7.60	6.68		179					
5285	FERGUSON SP 75DT TF	120 HP D	61,769	29.30	4.74	8.67	6.68		217					
5290	FERGUSON SP 230D	148 HP D	64,072	32.01	4.92	9.01	8.24		302					

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CNT									
			CONDITION		STAND-BY	AVERAGE COND. OWNER-SHIP	SEVERE COND. OWNER-SHIP												
			AVERAGE	SEVERE															
SCRAPERS-SELF PROPELLED ***** (CAPACITY AS RECOMMENDED BY MFGR HP & FUEL LISTED TRACTOR/SCRAPER PP = PUSH PULL ATTACHMENT)																			
CATERPILLAR																			
5300	613-B 13 T 11 CY P.S.	150 HP D	85.828	30.80	43.82	5.99	10.43	6.14	16.61	8.03	311								
5305	621-B 24 T 14-20 CY P.S.	330 HP D	171.240	56.89	85.11	11.91	20.65	12.13	32.94	15.94	640								
5310	623-B 25 T 22 CY P.S.	330 HP D	190.785	64.90	92.87	13.31	23.16	13.51	36.88	17.67	702								
5315	627-B 24 T 14-20 CY P.S. 225/225 HP D/D	200.644	74.63	105.82	14.01	24.42	17.48	38.87	22.68	715									
5320	627-B PP 24 T 14-20 CY P.S. 225/225 HP D/D	213.319	77.33	109.82	14.91	26.04	17.48	41.43	22.68	757									
5325	631-D 37.5T 21-31 CY P.S.	450 HP D	262.314	84.37	126.51	18.25	31.69	16.54	50.53	21.73	876								
5330	633-D 37.5T 34 CY P.S.	450 HP D	299.517	97.91	140.54	20.91	36.46	18.43	58.03	24.10	996								
5335	637-D 37.5T 21-31 CY P.S. 450/255 HP D/D	323.253	118.04	167.48	22.60	39.49	27.39	62.81	35.53	983									
5340	637-D PP 37.5T 21-31 CY P.S. 450/255 HP D/D	337.467	121.06	171.97	23.62	41.31	27.39	65.68	35.53	1018									
5345	641-B 47 T 28-38 CY P.S.	550 HP D	326.670	105.13	158.12	22.69	39.32	20.21	62.74	26.56	1155								
5350	651-B 52 T 32-44 CY P.S.	550 HP D	340.423	108.07	162.46	23.68	41.09	20.21	65.51	26.56	1179								
5355	657-B 52 T 32-44 CY P.S. 550/400 HP D/D	420.653	161.65	229.13	29.21	50.58	36.91	80.73	47.88	1408									
CLARK																			
5365	110-11B 13 T 11 CY P.S.	174 HP D	91.418	34.04	48.36	6.36	11.02	7.13	17.58	9.32	345								
5370	110-15 18 T 15 CY P.S.	232 HP D	121.821	42.82	61.16	8.48	14.73	9.50	23.48	12.42	456								
5375	110-TB 19 T 16 CY P.S. 140/140 HP D/D	161.589	57.25	81.57	11.30	19.72	11.47	31.37	14.99	521									
5380	210-HB 26.5T 23 CY P.S.	324 HP D	193.801	65.26	93.45	13.52	23.55	13.27	37.49	17.35	710								

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.			
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL		
	SCRAPERS-SELF PROPELLED (CONT'D) ***** (CAPACITY AS RECOMMENDED BY MFGR HP & FUEL LISTED TRACTOR/SCRAPER PP = PUSH PULL ATTACHMENT)										
	FIAT-ALLIS										
5390	161 18.7 T 15 CY P.S. 229 HP D	126,019	46.54	66.19	8.75	15.15	9.38	24.18	12.26	448	
5395	260B 25 T 15-21 CY P.S. 325 HP D	172,646	56.96	85.26	12.01	20.84	11.94	33.23	15.70	586	
5400	261B 26.5T 23 CY P.S. 325 HP D	199,547	66.56	95.37	13.93	24.28	13.31	38.65	17.40	639	
5405	262B 25 T 15-21 CY P.S. 325/171 HP D/D	203,967	74.23	108.04	14.24	24.84	18.23	39.54	23.96	681	
5410	263-B 26.5 T 23 CY P.S. 325/171 HP D/D	233,330	89.03	126.31	16.25	28.25	20.31	45.02	26.56	744	
	INTERNATIONAL										
5420	412 13 T 11 CY P.S. 150 HP D	81,911	30.29	43.08	5.69	9.84	6.14	15.72	8.03	308	
5425	431B 24 T 14-21 CY P.S. 326 HP D	158,941	54.09	81.00	11.03	19.08	11.98	30.47	15.75	594	
5430	433B 24 T 14-21 CY P.S. 126/185 HP D/D	186,494	64.86	92.60	12.99	22.60	12.08	36.02	15.67	690	
5435	442B 25 T 22 CY P.S. 326 HP D	180,922	62.53	89.43	12.60	21.89	13.35	34.89	17.46	680	
5440	444B 25 T 22 CY P.S. 326/185 HP D/D	213,869	83.98	118.81	14.91	25.96	20.93	41.35	27.36	805	
	JOHN DEERE										
5450	JD762 13.7 T 11 CY P.S. 175 HP D	92,471	34.11	48.45	6.45	11.20	7.17	17.85	9.37	345	
5455	JD860-B 18.7 T 15 CY P.S. 215 HP D	119,971	41.26	59.02	8.36	14.55	8.80	23.18	11.51	451	
	TEREX (GM)										
5465	S-23E 26.5T 23 CY P.S. 310 HP D	177,929	61.96	88.71	12.34	21.33	12.69	34.07	16.60	655	
5470	S-24B 40 T 24-34 CY P.S. 475 HP D	276,884	89.29	134.07	19.25	33.39	17.46	53.25	22.94	931	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT								
			CONDITION		STAND-BY	OWNER-SHIP	FUEL	OWNER-SHIP									
			AVERAGE	SEVERE													
SCRAPERS-SELF PROPELLED (CONT'D)																	
***** (CAPACITY AS RECOMMENDED BY MFGR HP & FUEL LISTED TRACTOR/SCRAPER PP = PUSH PULL ATTACHMENT)																	
TEREX (GM) (CONT'D)																	
5475	TS-14B 23.5T 14-20 CY P.S. 144/144 HP D/D	171,834	60.08	85.74	11.97	20.80	11.19	33.15	14.52	528							
5480	TS-18 30 T 18-24 CY P.S. 295/225 HP D/D	232,796	87.67	124.32	16.21	28.18	20.20	44.91	26.21	720							
5485	TS-24 40 T 24-32 CY P.S. 394/225 HP D/D	314,532	114.12	162.30	21.92	38.12	24.05	60.73	31.20	932							
5490	TS-24B 52 T 24-34 CY P.S. 475/242 HP D/D	340,572	123.59	175.51	23.80	41.55	27.86	66.10	36.14	1050							
WABCO																	
5500	101G 13 T 11 CY P.S. 161 HP D	85,840	32.32	45.96	5.95	10.25	6.59	16.38	8.62	317							
5505	222H 25 T 22 CY P.S. 332 HP D	184,495	64.52	92.30	12.81	22.18	13.60	35.40	17.78	648							
5510	229H 25 T 15-21 CY P.S. 332 HP D	161,516	55.62	83.70	11.17	19.23	12.20	30.76	16.04	594							
5515	252FT 32 T 27 CY P.S. 332/332 HP D/D	302,140	114.75	162.66	21.10	36.80	27.19	58.56	35.56	1017							
5520	333F 38 T 32 CY P.S. 467 HP D	267,453	91.52	130.97	18.63	32.39	19.12	51.62	25.01	1020							
5525	339F 41 T 25-34 CY P.S. 467 HP D	258,236	84.10	125.88	17.98	31.22	17.16	49.76	22.56	937							
5530	353FT 43 T 36 CY P.S. 493/473 HP D/D	424,783	167.58	237.35	29.52	51.14	39.56	81.59	51.73	1355							
SCRAPER-TRACTOR DRAWN																	

5540	ROME 18T 12-17CY HYDR/CONTROL	47,334	10.14	14.98	3.08	4.95	0.00	7.98	0.00	235							
5545	ROME 27T 18-26CY HYDR/CONTROL	66,997	14.56	21.52	4.33	6.92	0.00	11.18	0.00	365							
5550	SOUTHWEST DS18 DRAG SCRAPER 8.8 CY	27,456	5.87	8.67	1.79	2.88	0.00	4.64	0.00	137							

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CMT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.						
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL					
TRACTOR - CRAWLERS														
\$\$\$\$\$\$\$\$\$\$\$\$\$\$\$\$\$														
CATERPILLAR														
5560	D3 P.S.	62 HP D	25,303	9.32	13.41	1.83	3.02	2.67	4.91	3.52	119			
5565	3P POWER ANGLE & POWER TILT		5,518	1.25	1.88	0.40	0.71	0.00	1.12	0.00	24			
5570	D4-E D.D.	75 HP D	39,482	13.33	19.30	2.86	4.73	3.23	7.66	4.25	176			
5575	4A ANGLE BLADE HYDRAULIC		7,361	1.71	2.55	0.53	0.94	0.00	1.49	0.00	30			
5580	4S STRAIGHT BLADE HYDRAULIC		5,748	1.34	2.00	0.41	0.73	0.00	1.16	0.00	25			
5585	D5-B P.S.	105 HP D	59,960	19.74	28.64	4.35	7.18	4.52	11.63	5.95	269			
5590	5A ANGLE BLADE HYDRAULIC		8,862	2.06	3.06	0.64	1.14	0.00	1.79	0.00	41			
5595	5S STRAIGHT BLADE HYDRAULIC		6,976	1.63	2.42	0.50	0.90	0.00	1.41	0.00	34			
5600	D6-D P.S.	140 HP D	77,870	25.83	37.47	5.64	9.31	6.03	15.10	7.94	264			
5605	6S STRAIGHT BLADE HYDRAULIC		9,306	2.15	3.21	0.67	1.19	0.00	1.88	0.00	47			
5610	6A ANGLE BLADE HYDRAULIC		10,380	2.39	3.58	0.75	1.33	0.00	2.10	0.00	51			
5615	D7-G P.S.	200 HP D	107,046	35.94	52.07	7.75	12.80	8.61	20.76	11.34	373			
5620	7S STRAIGHT BLADE HYDRAULIC		14,535	3.32	4.99	1.03	1.85	0.00	2.94	0.00	77			
5625	7U HYD. UNIVERSAL BLADE		15,904	3.64	5.45	1.14	2.04	0.00	3.21	0.00	84			
5630	7A ANGLE BLADE HYDRAULIC		12,693	2.92	4.36	0.91	1.63	0.00	2.57	0.00	68			
5635	D8-K P.S.	300 HP D	149,399	48.02	67.98	10.21	16.67	12.91	26.65	17.01	606			
5640	8S STRAIGHT BLADE HYDRAULIC		21,203	4.83	7.24	1.51	2.71	0.00	4.28	0.00	121			
5645	8U HYD. UNIVERSAL BLADE		23,352	5.32	7.97	1.67	2.99	0.00	4.71	0.00	133			
5650	8A ANGLE BLADE HYDRAULIC		17,984	4.11	6.15	1.29	2.30	0.00	3.63	0.00	116			
5655	PUSH PLATE USE W/BS		538	0.12	0.18	0.04	0.07	0.00	0.11	0.00	4			

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT									
			CONDITION		STAND-BY	OWNER-SHIP	FUEL	OWNER-SHIP	FUEL										
			AVERAGE	SEVERE															
TRACTOR - CRAWLER (CONT'D)																			
CATERPILLAR (CONT'D)																			
5660	D9-H P.S.	410 HP D	219,781	68.95	97.80	15.02	24.52	17.65	39.21	23.25	809								
5665	9S STRAIGHT BLADE HYDRAULIC		27,371	6.22	9.33	1.96	3.50	0.00	5.52	0.00	173								
5670	9A ANGLE BLADE HYDRAULIC		23,349	5.32	7.97	1.67	2.99	0.00	4.71	0.00	152								
5675	9U HYD. UNIVERSAL BLADE		29,912	6.79	10.20	2.13	3.82	0.00	6.04	0.00	190								
5680	9C CUSHION BLADE		21,063	4.81	7.19	1.51	2.70	0.00	4.25	0.00	127								
5685	REAR CUSHION PUSH BLOCK		5,275	1.30	1.89	0.38	0.68	0.00	1.07	0.00	29								
5690	FRONT PUSH PLATE		620	0.15	0.23	0.04	0.08	0.00	0.13	0.00	5								
5695	DUAL D9-H P.S.	820 HP D	465,146	143.38	203.58	31.79	51.90	35.30	82.97	46.49	1851								
5700	D10 P.S.	700 HP D	408,301	120.66	168.34	26.45	42.93	30.13	67.97	39.69	1478								
5705	10S STRAIGHT BLADE HYDRAULIC		43,822	9.93	14.91	3.13	5.60	0.00	8.84	0.00	286								
5710	10U HYD. UNIVERSAL BLADE		48,209	10.92	16.39	3.44	6.16	0.00	9.72	0.00	283								
5715	FRONT PUSH PLATE		948	0.26	0.38	0.07	0.12	0.00	0.20	0.00	7								
5720	REAR PUSH BLOCK		13,827	3.17	4.74	0.99	1.77	0.00	2.79	0.00	46								
FIAT-ALLIS																			
5730	8 P.S.	87 HP D	39,688	14.06	20.26	2.88	4.75	3.75	7.69	4.93	189								
5735	8-HA ANGLE BLADE HYDRAULIC		6,482	1.51	2.25	0.46	0.83	0.00	1.31	0.00	30								
5740	8-HSU SEMI-U BLADE HYDRAULIC		6,780	1.58	2.35	0.49	0.87	0.00	1.37	0.00	30								
5745	10-B P.S.	110 HP D	58,989	19.80	28.68	4.27	7.06	4.74	11.43	6.24	256								
5750	10-HA ANGLE BLADE HYDRAULIC		7,211	1.67	2.50	0.52	0.92	0.00	1.46	0.00	36								
5755	10-HSU SEMI-U BLADE HYDRAULIC		7,608	1.76	2.64	0.54	0.97	0.00	1.54	0.00	36								

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		STAND-BY	ADJUSTABLE ELEMENTS		CWT				
			CONDITION			AVERAGE	SEVERE					
			OWNER-SHIP	FUEL		OWNER-SHIP	FUEL					
TRACTOR - CRAWLER (CONT'D)												
\$												
FIAT-ALLIS (CONT'D)												
5760	14-C P.S.	150 HP D	82,761	27.53	39.91	5.99	9.90	6.46	16.05	8.50	306	
5765	14-HA ANGLE BLADE HYDRAULIC		11,047	2.54	3.80	0.79	1.41	0.00	2.23	0.00	51	
5770	14-HSU STRAIGHT BLADE HYDRAULIC		11,543	2.66	3.97	0.83	1.48	0.00	2.33	0.00	51	
5775	16-B P.S.	195 HP D	109,620	36.24	52.59	7.94	13.11	8.39	21.25	11.06	453	
5780	16-HA ANGLE BLADE HYDRAULIC		11,738	2.70	4.03	0.84	1.50	0.00	2.37	0.00	66	
5785	16-HS STRAIGHT BLADE HYDRAULIC		12,334	2.84	4.23	0.88	1.58	0.00	2.49	0.00	66	
5790	16-HSU FULL-U BLADE HYDRAULIC		13,581	3.11	4.66	0.97	1.73	0.00	2.74	0.00	81	
5795	21-C P.S.	300 HP D	161,318	50.56	71.72	11.03	18.00	12.91	28.78	17.01	636	
5800	21HSU HYD. SEMI-UNIVERSAL BLADE		21,193	4.83	7.24	1.51	2.71	0.00	4.28	0.00	127	
5805	21-HU FULL-U BLADE HYDRAULIC		20,823	4.74	7.11	1.48	2.66	0.00	4.20	0.00	114	
5810	31 P.S.	425 HP D	246,396	75.44	107.18	16.84	27.49	18.30	43.95	24.10	908	
5815	31-HSU SEMI-U BLADE HYDRAULIC		30,325	6.88	10.34	2.16	3.87	0.00	6.12	0.00	190	
5820	31-HU FULL-U BLADE HYDRAULIC		31,374	7.13	10.68	2.24	4.01	0.00	6.32	0.00	210	
5825	31-HC CUSHION BLADE		22,545	5.14	7.69	1.62	2.89	0.00	4.54	0.00	120	
5830	41-B P.S.	524 HP D	313,619	91.96	128.37	20.32	32.97	22.56	52.22	29.71	1128	
5835	41-HSU SEMI-U BLADE HYDRAULIC		35,432	8.04	12.07	2.53	4.53	0.00	7.15	0.00	222	
5840	41-HU FULL-U BLADE HYDRAULIC		40,344	9.15	13.73	2.88	5.16	0.00	8.14	0.00	254	
5845	41-HC CUSHION BLADE		25,888	5.89	8.83	1.85	3.31	0.00	5.22	0.00	120	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CUT					
			CONDITION	STAND-BY	AVERAGE COND.		SEVERE COND.							
					AVERAGE	SEVERE	OWNER-SHIP	FUEL						
TRACTOR - CRAWLER (CONT'D)														

INTERNATIONAL														
5855	TD-7-E P. S. W/HYD BLADE	65 HP D	35,616	11.88	17.21	2.58	4.26	2.80	6.90	3.69	139			
5860	TD-8-E P.S. W/HYD BLADE	78 HP D	43,408	14.39	20.89	3.14	5.19	3.36	8.42	4.42	172			
5865	TD-15-C P.S.	140 HP D	71,548	24.39	35.27	5.18	8.56	6.03	13.87	7.94	269			
5870	HYD. SEMI-UNIVERSAL BLADE		9,641	2.23	3.32	0.69	1.24	0.00	1.95	0.00	46			
5875	ANGLE BLADE HYDRAULIC		10,728	2.47	3.69	0.76	1.37	0.00	2.17	0.00	50			
5880	TD-20-E P.S.	210 HP D	103,976	35.80	51.76	7.53	12.44	9.04	20.16	11.91	475			
5885	HYD. SEMI-UNIVERSAL BLADE		13,820	3.17	4.74	0.99	1.77	0.00	2.79	0.00	61			
5890	ANGLE BLADE HYDRAULIC		14,256	3.26	4.89	1.02	1.82	0.00	2.88	0.00	71			
5895	TD-25-E P.S.	310 HP D	142,011	46.99	66.38	9.71	15.84	13.35	25.33	17.58	590			
5900	HYD. SEMI-UNIVERSAL BLADE		18,420	4.21	6.29	1.32	2.36	0.00	3.71	0.00	108			
5905	ANGLE BLADE HYDRAULIC		16,264	3.73	5.56	1.17	2.09	0.00	3.28	0.00	110			
5910	FRONT PUSHER CUSHION		7,454	1.73	2.58	0.53	0.95	0.00	1.51	0.00	29			
5915	REAR PUSHER CUSHION		3,946	1.00	1.44	0.29	0.51	0.00	0.80	0.00	23			
5920	FRONT PUSH BLOCK /S BLD		595	0.18	0.26	0.04	0.07	0.00	0.13	0.00	12			
JOHN DEERE														
5930	JD350C/6305 D.D. W/HYD BLADE	42 HP D	25,105	8.15	11.84	1.82	3.00	1.81	4.87	2.38	102			
5935	JD450C/6405 D.D. W/HYD BLADE	65 HP D	36,140	12.00	17.40	2.62	4.33	2.80	7.01	3.69	143			
5940	JD550/6405 P.S. W/HYD BLADE	72 HP D	43,161	13.99	20.35	3.12	5.16	3.10	8.37	4.08	169			

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	ADJUSTABLE ELEMENTS								
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL					
TRACTOR - CRAWLER (CONT'D)														
XXXXXXXXXXXXXXXXXXXXXX														
TEREX (GM)														
5950	82-20B	P.S. 205 HP D	107,168	36.25	52.48	7.76	12.82	8.83	20.78	11.62				
5955		STRAIGHT BLADE HYDRAULIC	10,480	2.36	3.56	0.75	1.34	0.00	2.12	0.00				
5960		ANGLE BLADE HYDRAULIC	11,361	2.57	3.85	0.82	1.46	0.00	2.29	0.00				
5965		HYD. UNIVERSAL BLADE	11,355	2.57	3.85	0.82	1.46	0.00	2.29	0.00				
5970	82-30B	P.S. 260 HP D	138,690	43.58	61.80	9.48	15.47	11.19	24.74	14.74				
5975		STRAIGHT BLADE HYDRAULIC	15,290	3.49	5.24	1.09	1.95	0.00	3.09	0.00				
5980		ANGLE BLADE HYDRAULIC	17,007	3.88	5.82	1.21	2.17	0.00	3.43	0.00				
5985		HYD. UNIVERSAL BLADE	17,004	3.88	5.82	1.21	2.17	0.00	3.43	0.00				
5990		REAR CUSHION PUSH BLOCK	4,650	1.14	1.68	0.33	0.59	0.00	0.94	0.00				
5995	82-50B	P.S. 370 HP D	201,835	62.97	89.35	13.80	22.52	15.93	36.01	20.98				
6000		STRAIGHT BLADE	19,727	4.46	6.69	1.41	2.53	0.00	3.98	0.00				
6005		HYD. UNIVERSAL BLADE	22,026	4.97	7.47	1.58	2.82	0.00	4.44	0.00				
6010		ANGLE BLADE HYDRAULIC	22,094	4.98	7.50	1.58	2.82	0.00	4.46	0.00				
6015		PUSH PLATE (WELD ON)	798	0.18	0.27	0.06	0.10	0.00	0.16	0.00				
6020		PUSH BLOCK (CUSHION REAR)	4,650	1.04	1.58	0.33	0.59	0.00	0.94	0.00				

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS			CWT						
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.							
			AVERAGE	SEVERE		OWNER-SHIP	FUEL								
TRACTOR - WHEEL TYPE DOZERS															

CATERPILLAR															
6030	814	ARTICULATED ST BLADE P.S. 170 HP D	92.068	30.08	47.82	6.40	11.02	6.78	17.62	8.75	363				
6035	824-C	ARTICULATED ST BLADE P.S. 300 HP D	164.269	54.30	87.65	11.37	19.45	11.97	31.17	15.43	603				
CLARK															
6045	280	ARTICULATED ST BLADE P.S. 274 HP D	164.985	52.68	84.78	11.45	19.66	10.93	31.46	14.10	688				
6050	380	ARTICULATED ST BLADE P.S. 473 HP D	247.153	80.73	126.74	17.23	29.80	18.87	47.58	24.34	1010				
TRACTOR - WHEEL TYPE - FARM TYPE															

JOHN DEERE															
6060	MOD 20-40	40 HP G	9.856	6.75	10.13	0.67	1.12	3.41	1.81	4.44	0				
6065	MOD 24-40	60 HP G	14.365	9.77	14.25	0.99	1.69	5.11	2.72	6.66	0				
TRENCHER-CHAIN-DITCH WITCH															

6075	MOD C99	6"X24" TRENCH	9 HP G	2.425	1.62	2.24	0.18	0.31	0.77	0.49	1.00	5			
6080	MOD 2200	8"X36" TRENCH	17 HP G	10.797	4.54	6.48	0.77	1.36	1.45	2.16	1.89	27			
6085	MOD V30	10"X36" TRENCH	30 HP G	11.840	6.26	8.76	0.84	1.49	2.55	2.37	3.33	40			
6090	MOD 65	12"X48" TRANCH	65 HP D	24.038	9.24	13.23	1.71	3.03	2.59	4.79	3.34	72			
6095	MOD 100	18"X72" TRENCH	101 HP D	56.236	19.11	27.88	3.99	7.06	4.03	11.17	5.20	95			

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CMT	
			CONDITION	AVERAGE	SEVERE	STAND-BY	OWNER-SHIP	FUEL	OWNER-SHIP		
	TRENCHER-WHEEL TYPE *****										
	BARBER-GREEN										
6105	MOD TA 56 16'X5'-10" TRENCH	84 HP D	74.237	22.12	32.07	5.31	9.47	3.35	14.93	4.32	275
6110	MOD TA 65 22'X7'-0" TRENCH	175 HP D	170.124	49.79	72.34	12.16	21.69	6.98	34.22	9.00	632
	CLEVELAND										
6120	MOD 247-HD-1 21'X7' TRENCH	84 HP D	74.237	22.12	32.07	5.31	9.47	3.35	14.93	4.32	275
6125	MOD 400W-HD-1 36'X9' TRENCH	175 HP D	170.124	49.79	72.34	12.16	21.69	6.98	34.22	9.00	632
	TRUCKS - HIGHWAY ***** (CHASSIS ONLY)										
	FORD										
6140	F100 4X2 1/2T PKUP 4900 GVW 157 HP G	4,835	6.63	9.00	0.37	0.70	4.05	1.12	5.27	37	
6145	F150 4X2 1/2T PKUP 6150 GVW 157 HP G	5,237	6.74	9.16	0.40	0.75	4.05	1.21	5.27	38	
6150	F250 4X2 3/4T PKUP 7900 GVW 157 HP G	6,014	6.99	9.57	0.45	0.85	4.05	1.37	5.27	39	
6155	F250 4X4 3/4T PKUP 8400 GVW 157 HP G	7,046	7.27	10.06	0.54	1.01	4.05	1.61	5.27	44	
6160	F600 2AX 16000 GVW 155 HP G	9,050	13.27	17.94	0.68	1.28	8.20	2.08	10.60	51	
6165	F612 2AX 21000 GVW 155 HP G	9,250	13.38	18.15	0.69	1.28	8.20	2.09	10.60	53	
6170	F702 2AX 22000 GVW 170 HP G	11,071	14.97	20.37	0.83	1.53	8.99	2.49	11.62	59	
6175	F706 2AX 25500 GVW 170 HP G	11,326	15.12	20.64	0.85	1.55	8.99	2.51	11.62	62	
6180	L804 2AX 27500 GVW 170 HP G	12,906	15.51	21.26	0.96	1.78	8.99	2.88	11.62	66	
6185	L8000 2AX 35000 GVW 175 HP D	22,940	15.23	21.85	1.74	3.25	7.04	5.24	9.26	87	
6190	LTS900 3AX 39000 GVW 200 HP D	24,836	17.41	25.20	1.85	3.40	8.05	5.51	10.58	10	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.						
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL					
TRUCKS - HIGHWAY (CONT'D)														
XXXXXXXXXXXXXXXXXXXXXX														
(CHASSIS ONLY)														
FORD (CONT'D)														
6195	LTS904	3AX	46000 GVW 200 HP D	25,518	17.58	25.48	1.90	3.50	8.05	5.68	10.58	104		
6200	LTS9000	3AX	54000 GVW 250 HP D	40,004	23.96	34.91	3.01	5.60	10.06	9.05	13.22	135		
6205	LTS9000	3AX	58000 GVW 250 HP D	41,974	24.44	35.68	3.16	5.90	10.06	9.52	13.22	140		
GMC AND CHEVROLET														
6215	C10903	4X2 1/2T PKUP	6000 GVW 140 HP G	5,398	6.20	8.47	0.41	0.78	3.61	1.25	4.70	43		
6220	C10906	4X2	WAGON 6400 GVW 165 HP G	6,613	7.35	10.05	0.50	0.95	4.26	1.54	5.53	46		
6225	K10906	4X4	WAGON 6800 GVW 165 HP G	7,633	7.63	10.50	0.59	1.11	4.26	1.78	5.53	50		
6230	C20903	4X2 3/4T PKUP	7500 GVW 165 HP G	5,943	7.25	9.91	0.45	0.84	4.26	1.35	5.53	46		
6235	C20903	4X4 3/4T PKUP	7500 GVW 165 HP G	7,129	7.56	10.45	0.54	1.01	4.26	1.63	5.53	49		
6240	C5D042	2AX	16000 GVW 160 HP G	9,204	13.79	18.71	0.68	1.26	8.46	2.04	10.94	56		
6245	C6D042	2AX	20000 GVW 160 HP G	10,272	14.06	19.14	0.77	1.42	8.46	2.30	10.94	63		
6250	C7D042	2AX	24000 GVW 188 HP G	10,567	16.09	21.77	0.80	1.47	9.94	2.37	12.85	67		
6255	J8C042	2AX	27500 GVW 220 HP G	18,578	20.46	28.06	1.40	2.61	11.64	4.22	15.04	85		
6260	J9C042	2AX	33900 GVW 242 HP D	34,888	21.84	31.36	2.65	4.98	9.74	8.01	12.80	121		
6265	C7D064	3AX	37000 GVW 200 HP G	14,871	25.05	33.92	1.11	2.04	15.74	3.30	20.38	100		
6270	J8C064	3AX	43000 GVW 220 HP G	24,476	29.73	40.82	1.83	3.39	17.31	5.49	22.42	120		
6275	J9C064	3AX	44900 GVW 242 HP D	39,072	23.30	33.98	2.94	5.47	9.74	8.84	12.80	148		
6280	N9E042	2AX	33900 GVW 242 HP D	37,372	22.47	32.36	2.84	5.35	9.74	8.61	12.80	122		
6285	D9K042	2AX	33900 GVW 289 HP D	37,795	25.00	35.71	2.87	5.41	11.63	8.71	15.29	123		

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.					
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL				
TRUCKS - HIGHWAY (CONT'D)													
XXXXXXXXXXXXXXXXXXXX													
(CHASSIS ONLY)													
GMC AND CHEVROLET (CONT'D)													
6290	N9E064	3AX	48900 GVW 289 HP D	42,558	26.52	38.34	3.22	6.02	11.63	9.70	15.29	154	
6295	D9K064	3AX	48900 GVW 289 HP D	42,960	26.56	38.40	3.25	6.09	11.63	9.82	15.29	152	
INTERNATIONAL													
6305	800	4X4 SCOUT	6200 GVW 97 HP G	6,079	4.90	6.84	0.47	0.89	2.50	1.42	3.25	30	
6310	1624	2AX	20000 GVW 147 HP G	9,471	12.89	17.52	0.71	1.32	7.77	2.14	10.05	57	
6315	1724	2AX	20500 GVW 147 HP G	9,785	12.96	17.65	0.73	1.36	7.77	2.22	10.05	65	
6320	1824	2AX	23600 GVW 189 HP G	10,397	16.12	21.77	0.78	1.45	10.00	2.34	12.92	68	
6325	1854	2AX	23600 GVW 180 HP D	15,699	10.61	15.03	1.19	2.23	4.97	3.59	6.42	74	
6330	1924	2AX	25000 GVW 190 HP G	12,184	16.64	22.57	0.92	1.71	10.05	2.76	12.99	79	
6335	1954	2AX	27000 GVW 180 HP D	20,269	11.84	17.00	1.53	2.88	4.97	4.65	6.42	100	
6340	F1954	3AX	43000 GVW 210 HP D	24,219	17.42	24.89	1.83	3.43	8.45	5.52	11.11	123	
6345	F2554	3AX	43000 GVW 210 HP D	33,756	19.96	28.94	2.56	4.80	8.45	7.73	11.11	123	
6350	F2574	3AX	50000 GVW 230 HP D	40,488	22.70	32.96	3.08	5.80	9.26	9.32	12.17	123	
6355	F5050	3AX	52000 GVW 225 HP D	41,201	22.62	32.90	3.13	5.90	9.06	9.49	11.90	138	
KENWORTH													
6365	K100 3AX	47400 GVW	72800 GCW 290 HP D	47,726	27.86	40.45	3.61	6.78	11.67	10.92	15.34	138	
6370	W900 3AX	50000 GVW	76800 GCW 290 HP D	46,627	27.58	40.02	3.52	6.62	11.67	10.66	15.34	140	
6375	C500 3AX	56000 GVW	86000 GCW 290 HP D	53,378	29.29	42.70	4.04	7.62	11.67	12.27	15.34	144	
6380	BRUTE 3AX	62000 GVW	95300 GCW 290 HP D	57,360	30.30	44.27	4.36	8.22	11.67	13.21	15.34	179	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.						
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL					
TRUCKS - HIGHWAY (CONT'D)														
***** (CHASSIS ONLY)														
PETERBILT														
6390	MOD 348 3AX 56000 GVW 250 HP D	48,026	25.91	37.85	3.63	6.82	10.06	10.98	13.22	121				
6395	MOD 352 3AX 50000 GVW 76800 GCW 350 HP D	51,501	31.87	45.92	3.90	7.35	14.09	11.83	18.51	131				
6400	MOD 359 3AX 50000 GVW 76800 GCW 350 HP D	51,510	31.87	45.93	3.90	7.35	14.09	11.84	18.51	134				
6405	MOD 381 3AX 73000 GVW 125000 GCW 350 HP D	55,075	32.78	47.34	4.19	7.89	14.09	12.69	18.51	174				
6410	MOD 383 3AX 83000 GVW 150000 GCW 350 HP D	55,132	32.90	47.35	4.19	7.90	14.09	12.69	18.51	193				
TRUCK ACCESSORIES-TRAILER B/D														

COOK BROS CHALLENGE														
6420	BDS 2511 19CY 25T 80,000 GVW MAX	22,256	5.41	8.13	1.56	2.57	0.00	4.18	0.00	120				
6425	BDS 2811 23CY 28T 80,000 GVW MAX	24,276	5.88	8.83	1.70	2.81	0.00	4.56	0.00	130				
6430	BDS-4011 30CY 40T 80,000 GVW MAX	26,825	6.57	9.86	1.87	3.06	0.00	4.98	0.00	150				
6435	E-400 20CY 40T 100,000 GVW MAX	35,345	8.47	12.73	2.48	4.11	0.00	6.66	0.00	170				
6440	E-550 37CY 55T OFF-HWY	55,727	13.43	20.20	3.89	6.42	0.00	10.43	0.00	370				
6445	E-550G 37CY 55T OFF-HWY W/GOOSE NECK	65,734	15.66	23.57	4.62	7.66	0.00	12.41	0.00	390				
6450	E-700 43CY 70T OFF-HWY	75,634	18.62	27.98	5.23	8.51	0.00	13.89	0.00	370				
6455	E-700G 43CY 70T OFF-HWY W/GOOSE NECK	81,660	19.95	30.02	5.67	9.25	0.00	15.09	0.00	390				
6460	DOLLY FOR GOOSE NECK TRAILERS	15,667	4.05	6.05	1.07	1.71	0.00	2.81	0.00	80				

EP 1110-1-8
 (Vol. 2)
 15 Jun 81

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT
			CONDITION		STAND-BY	AVERAGE COND.	SEVERE COND.			
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL	
	TRUCK ACCESSORIES-TRAILER E/D *****									
	COOK BROS CHALLENGE									
6470	SDS-26-R 20CY 28T 80,000 GVW MAX	20,248	4.98	7.47	1.41	2.31	0.00	3.76	0.00	114
6475	SDS-28-R 21CY 28T 80,000 GVW MAX	20,764	5.11	7.65	1.45	2.38	0.00	3.87	0.00	120
	FRUEHAUF									
6485	DDC-M2-27 20CY 25T 80,000 GVW MAX	19,817	4.86	7.30	1.38	2.26	0.00	3.69	0.00	110
	TRUCK ACCESSORIES - DUMP-REAR *****									
	WILLIAMSEN W/HOIST									
6495	5CY 24M TO 26M GVW	4,116	1.27	1.88	0.32	0.61	0.00	0.97	0.00	25
6500	AIR GATE 8CY 27M TO 30M GVW	6,405	1.93	2.91	0.49	0.94	0.00	1.52	0.00	45
6505	AIR GATE 10CY 36000 & UP GVW	6,518	1.97	2.95	0.50	0.96	0.00	1.54	0.00	46
6510	AIR GATE 12CY 36000 & UP GVW	6,610	2.05	3.05	0.52	0.98	0.00	1.57	0.00	47
	TRUCK ACCESSORIES - FLATBEDS *****									
	KNAPHEIDE									
6520	CT 8' X 12'	1,124	0.38		0.09	0.17	0.00			13
6525	CT 8' X 13.5'	1,290	0.42		0.10	0.19	0.00			16
6530	CT 8' X 15'	1,377	0.44		0.10	0.20	0.00			17
6535	CT 8' X 16'	1,469	0.47		0.12	0.22	0.00			19

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS			CWT				
			CONDITION		STAND-BY	AVERAGE	SEVERE	OWNERSHIP					
			AVERAGE	SEVERE		OWNERSHIP	FUEL	OWNERSHIP					
TRUCK ACCESSORIES-HOIST-ELECT \$88888888888888888888888888888888													
AUTO CRANE													
6545	BACKSAVER SENIOR CAP 1500#	2,402	0.73		0.19	0.36	0.00		3				
6550	WORKHORSE CAP 2500#	2,988	0.88		0.23	0.44	0.00		6				
6555	MIGHTY WORKHORSE CAP 4000#	6,428	1.81		0.50	0.95	0.00		9				
6560	MUSTANG CAP 4000#	9,847	2.74		0.76	1.45	0.00		20				
TRUCK ACCESSORIES-CRANE-HYDR \$88888888888888888888888888888888													
NATIONAL CRANE													
6570	SERIES 4 7.5T@5'RAD 27500 GVW	25,123	6.89		1.94	3.71	0.00		80				
6575	SERIES 6 10T@5'RAD 44000 GVW	31,138	8.51		2.40	4.59	0.00		94				
6580	SERIES 8 12T@5'RAD 60000 GVW	45,210	12.33		3.49	6.67	0.00		140				
PITMAN													
6590	HL-140CD 2AX 7T@ 4'RAD 24000 GVW	13,907	3.84		1.08	2.05	0.00		64				
6595	HL-170CD 2AX 8T@ 4'RAD 24000 GVW	18,297	5.03		1.41	2.70	0.00		85				
6600	HL-1268-1 2AX 12T@5'RAD 33000 GVW	38,909	10.62		3.00	5.74	0.00		120				

EP 1110-1-8
 (Vol. 2)
 15 Jun 81

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.			
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL		
	TRUCK ACCESSORIES-TRAILERS FB *****										
	FRUEHAUF										
6610	PF-F2-40 40 FT 35 T 2 AX	9.196	2.49		0.62	0.90	0.00			96	
	TRANSPORT										
6620	PF-BX 36 FT 35 T 2 AX	12.530	3.21		0.86	1.31	0.00			98	
6625	PF-BX 40 FT 35 T 2 AX	12.624	3.24		0.87	1.33	0.00			104	
	TRUCK ACCESSORIES-TRAILERS LOWBOY FB *****										
	LOAD KING										
6635	302-DR 30T 2AX 41000-49000 GVW	19.378	4.59		1.37	2.18	0.00			96	
6640	402-DR 40T 2AX 50000-60000 GVW	25.656	6.04		1.82	2.90	0.00			108	
6645	352-DF 35T 2AX 41000-49000 GVW	24.174	5.63		1.72	2.75	0.00			112	
6650	402-DF 40T 2AX 50000-60000 GVW	26.651	6.24		1.89	3.01	0.00			117	
6655	503-DF 50T 3AX 50000-60000 GVW	32.640	7.77		2.30	3.65	0.00			157	
6660	603-DF 60T 3AX 61000-80000 GVW	38.770	9.19		2.74	4.34	0.00			180	
6665	DOLLY FOR THREE-AXLE TRAILERS	13.846	3.46		0.97	1.49	0.00			60	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS			CNT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.		
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP		
	TRUCK ACCESSORIES-TRAILERS-TILT *****									
	Hyster									
6675	HP15T 15T 2AX 35000-40000 GVW	10,969	2.76		0.76	1.17	0.00		68	
6680	HP2DT 20T 2AX 35000-40000 GVW	13,041	3.25		0.91	1.40	0.00		71	
6685	GHP25T 25T 2AX 35000-40000 GVW	14,856	3.65		1.04	1.62	0.00		80	
	TRUCK ACCESSORIES-TRANSIT MIXER *****									
	COOK BROS CHALLENGE (MIXER ONLY - ADD CHASSIS)									
6700	708-MD 7 CY 40000 - 50000 GVW	19,749	5.45		1.52	2.91	0.00		63	
6705	808-MD 8 CY 50000 - 70000 GVW	20,056	5.54		1.55	2.96	0.00		66	
6710	858-MD 8.5 CY 55000 - 75000 GVW	20,265	5.60		1.57	2.99	0.00		68	
6715	908-MD 9 CY 61000 - 80000 GVW	20,556	5.68		1.59	3.04	0.00		73	
	TRUCK ACCESSORIES-WATER TANK *****									
	ROSCO									
6720	MFW 2000 GAL 23500 - 28000 GVW 7 HP G TRUCK MOUNTED (ADD CHASSIS)	8,068	2.98		0.62	1.19	0.60		35	
6725	MFW 2500 GAL 25000 - 34950 GVW 7 HP G TRUCK MOUNTED (ADD CHASSIS)	8,482	3.10		0.66	1.26	0.60		42	
6730	MFW 3000 GAL 29000 - 40000 GVW 7 HP G TRUCK MOUNTED (ADD CHASSIS)	8,982	3.22		0.69	1.32	0.60		46	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNI. NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND- BY	AVERAGE COND.		SEVERE COND.						
			AVERAGE	SEVERE		OWNER- SHIP	FUEL	OWNER- SHIP	FUEL					
TRUCKS - OFF HIGHWAY														

CATERPILLAR														
6740	769-B	35T 22-29 CY	P.S. 450 HP D	205,260	58.60	85.70	13.63	22.49	11.34	35.85	14.65	681		
6745	773	50T 30-40 CY	P.S. 600 HP D	288,874	81.62	119.57	19.19	31.62	15.12	50.38	19.53	903		
6750	777	85T 47-67 CY	P.S. 870 HP D	395,626	118.14	173.96	26.04	42.39	21.92	67.92	28.32	1225		
6755	768C PRIME MOVER TRACTOR		P.S. 450 HP D	180,809	57.41	84.60	11.82	19.05	11.34	30.66	14.65	506		
6760	772B PRIME MOVER TRACTOR		P.S. 600 HP D	271,885	81.46	119.96	17.89	29.09	15.12	46.63	19.53	705		
DJB (ARTICULATED FRAME)														
6770	D275	27.5T 15-24 CY	P.S. 235 HP D	163,315	42.73	63.27	10.83	17.82	5.92	28.43	7.65	410		
6775	D330	33T 17-28 CY	P.S. 255 HP D	173,413	45.29	66.94	11.52	18.99	6.43	30.26	8.30	430		
6780	D350	35T 20-31 CY	P.S. 255 HP D	185,547	48.92	72.67	12.27	20.11	6.43	32.12	8.30	460		
6785	D550	55T 32-55 CY	P.S. 450 HP D	318,618	83.44	123.66	21.11	34.71	11.34	55.38	14.65	820		
EUCLID														
6795	R25-215FD	25T 14-19 CY	P.S. 228 HP D	125,812	34.52	50.77	8.35	13.75	5.75	21.93	7.42	378		
6800	R35-302TD	35T 23-29 CY	P.S. 394 HP D	187,273	54.15	79.57	12.39	20.29	9.93	32.42	12.82	583		
6805	R50-301LD	50T 31-41 CY	P.S. 606 HP D	263,709	76.94	112.51	17.49	28.77	15.27	45.89	19.73	790		
INTERNATIONAL														
6815	330	36T 24-31 CY	P.S. 394 HP D	179,997	53.64	79.22	11.91	19.51	9.93	31.17	12.82	630		
6820	350B	50T 31-42 CY	P.S. 580 HP D	261,844	76.70	112.85	17.38	28.63	14.62	45.64	18.88	740		

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.						
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL					
TRUCKS - OFF HIGHWAY (CONT'D)														

MACK														
6835	M-15-X 15T 11-15 CY	180 HP D	93,366	26.28	38.67	6.18	10.15	4.54	16.21	5.86	340			
6840	M-20-X 20T 13-17 CY	250 HP D	95,302	27.92	40.43	6.36	10.57	6.30	16.79	8.14	350			
6845	M-25-X 25T 16-20 CY	P.S. 250 HP D	121,017	34.36	50.39	8.03	13.21	6.30	21.07	8.14	460			
6850	M-35-AX 35T 23-29 CY	P.S. 434 HP D	171,797	51.71	75.46	11.38	18.69	10.94	29.84	14.13	630			
6855	M-45-SX 3AX45T 28-36 CY	P.S. 535 HP D	234,295	69.65	102.33	15.50	25.41	13.48	40.58	17.41	810			
6860	M-50-AX 50T 32-39 CY	P.S. 635 HP D	250,230	75.38	109.98	16.57	27.22	16.00	43.46	20.67	790			
6865	M-65-BX 65T 42-51 CY	P.S. 700 HP D	316,906	91.66	134.21	21.00	34.54	17.64	55.11	22.78	955			
6870	M-75ASX 3AX75T 44-56 CY	P.S. 800 HP D	365,295	106.52	156.49	24.20	39.76	20.16	63.46	26.04	1160			
TEREX														
6880	33-03B 22T 15-18 CY	P.S. 215 HP D	101,911	29.97	44.15	6.71	10.94	5.42	17.53	7.00	380			
6885	33-05B 30T 19-23 CY	P.S. 321 HP D	162,353	45.83	67.36	10.76	17.67	8.09	28.21	10.45	525			
6890	33-07 40T 25-32 CY	P.S. 493 HP D	216,434	63.82	93.56	14.32	23.46	12.42	37.48	16.05	756			
6895	33-09 55T 34-44 CY	P.S. 624 HP D	289,356	83.95	123.19	19.14	31.39	15.72	50.14	20.31	992			
6900	33-11C 85T 51-65 CY	P.S. 840 HP D	391,038	113.05	165.85	25.88	42.48	21.17	67.83	27.34	1227			
WABCO														
6910	HAULPAK 35C 35T 23-29 CY	P.S. 456 HP D	183,835	55.82	81.72	12.14	19.85	11.49	31.75	14.84	571			
6915	HAULPAK 50 50T 31-40 CY	P.S. 635 HP D	264,410	79.33	116.17	17.47	28.60	16.00	45.72	20.67	792			
6920	75B 75T 45-47 CY	P.S. 700 HP D	304,455	91.99	135.28	20.04	32.61	17.64	52.26	22.78	955			
6925	85C 85T 40-60 CY	P.S. 860 HP D	368,817	111.86	164.42	24.28	39.51	21.67	63.30	27.99	1181			

EP 1110-1-8
 (Vol. 2)
 15 Jun 81

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CMT									
			CONDITION		STAND BY	AVERAGE OWNER-SHIP	FUEL	SEVERE OWNER-SHIP	FUEL										
			AVERAGE	SEVERE															
TRUCKS - WATER																			

TRACTOR DRAWN - KLEIN																			
6940	KT-50	5000 GAL. CAT 613B P.S. 150 HP D	91,969	26.35	37.98	6.08	9.94	5.98	15.89	7.72	310								
6945	KT-60	6000 GAL. CAT 621B P.S. 330 HP D	163,766	51.79	74.69	10.75	17.44	13.17	27.99	16.98	593								
6950	KT-80	8000 GAL. CAT 631D P.S. 450 HP D	225,330	69.16	99.34	14.91	24.46	17.95	39.07	23.15	788								
6955	KT-100	10000 GAL. CAT 631D P.S. 450 HP D	231,787	71.09	102.29	15.27	24.91	17.95	39.88	23.15	798								
6960	KT-100	10000 GAL. CAT 641B P.S. 550 HP D	271,362	85.74	123.81	17.89	29.20	21.94	46.74	28.30	951								
6965	KT-120	12000 GAL. CAT 651B P.S. 550 HP D	275,577	87.24	126.08	18.11	29.41	21.94	47.17	28.30	1097								
6970	KT-140	14000 GAL. CAT 660B P.S. 550 HP D	271,387	88.25	127.72	17.69	28.36	21.94	45.72	28.30	106								
TRACTOR DRAWN - SOUTHWEST																			
6980	STT-60	6000 GAL. CAT 621B P.S. 330 HP D	171,292	52.95	76.39	11.28	18.37	13.17	29.42	16.98	623								
6985	STT-80	8000 GAL. CAT 631D P.S. 450 HP D	232,587	70.62	101.52	15.39	25.23	17.95	40.29	23.15	848								
6990	STT-100	10000 GAL. CAT 631D P.S. 450 HP D	236,222	71.42	102.71	15.62	25.59	17.95	40.89	23.15	918								
6995	STT-120	12000 GAL. CAT 651B P.S. 550 HP D	284,361	90.03	130.36	18.59	29.96	21.94	48.21	28.30	1053								
7000	STT-140	14000 GAL. CAT 660B P.S. 550 HP D	278,930	89.93	130.27	18.16	29.08	21.94	46.92	28.30	1137								
WAGONS - BOTTOM - DUMP																			

CATERPILLAR-ATHey																			
7010	621B/PW621B	33T 22-26CY P.S. 330 HP D	176,415	54.53	78.78	11.56	18.71	13.17	30.05	16.98	579								
7015	631D/PW631D	41T 27-32CY P.S. 450 HP D	244,207	73.32	105.59	16.11	26.32	17.95	42.11	23.15	769								
7020	768B/PW768B	72T 42-48CY P.S. 415 HP D	275,455	79.42	115.07	18.02	29.04	16.56	46.72	21.35									
7025	660B/PW772	100T 60-67CY P.S. 550 HP D	353,372	103.69	150.65	23.14	37.38	21.94	60.09	28.30	1218								

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT	
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.			
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL		
	WAGONS - BOTTOM - DUMP (CONT'D) *****										
	CATERPILLAR-ATHEY (CONT'D)										
7030	660B/PW660B 100T 60-67CY P.S. 550 HP D	353,293	103.11	149.74	23.19	37.58	21.94	60.32	28.30	1164	
	EUCLID										
7040	863-203LDT147W 63T 42-56CY P.S. 442 HP D	270,410	79.45	115.07	17.77	28.88	17.64	46.32	22.74	896	
	WAGONS - REAR - DUMP *****										
	CATERPILLAR-ATHEY										
7050	621B/PR621B 30T 20-24CY P.S. 330 HP D	177,553	56.27	81.87	11.65	18.89	13.17	30.32	16.98	572	
7055	631D/PR631D 40T 27-32CY P.S. 450 HP D	249,428	77.26	112.32	16.44	26.82	17.95	42.93	23.15	833	
	WATER BLASTER *****										
	MULLINS WATER BLASTERS										
7070	5000DH 1 - NOZZLE	95 HP D	22,666	17.08		1.97	4.09	5.59		47	
7075	5200DH 2 - NOZZLE	140 HP D	30,509	24.36		2.65	5.51	8.23		52	
7080	5300 3 - NOZZLE	275 HP D	55,855	46.24		4.85	10.08	16.17		128	
7085	5400 4 - NOZZLE	318 HP D	60,156	51.94		5.22	10.86	18.70		145	

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES			ADJUSTABLE ELEMENTS				CWT				
			CONDITION		STAND-BY	AVERAGE COND.		SEVERE COND.						
			AVERAGE	SEVERE		OWNER-SHIP	FUEL	OWNER-SHIP	FUEL					
WATER TANKS														

SKID MOUNTED														
7095	WST-8 8000 GAL. SOUTHWEST	9,838	2.68		0.76	1.45	0.00			128				
7100	WST-10 10000 GAL. SOUTHWEST	11,466	3.13		0.89	1.70	0.00			150				
7105	WST-12 12000 GAL. SOUTHWEST	13,685	3.72		1.06	2.02	0.00			183				
PORTABLE (WITH WHEELS)														
7115	EWT-8 8000 GAL. SOUTHWEST	21,351	5.80		1.65	3.15	0.00			150				
7120	EWT-10 10000 GAL. SOUTHWEST	23,998	6.52		1.85	3.54	0.00			170				
7125	EWT-12 12000 GAL. SOUTHWEST	26,706	7.25		2.07	3.94	0.00			210				
WELDERS														

ELECTRIC DRIVE - AC 3 PHASE 60 HZ														
7135	250 AMP SKID MTD	10 HP E	946	0.61		0.07	0.12	0.33		7				
7140	300 AMP SKID MTD	20 HP E	1,306	1.12		0.11	0.18	0.66		7				
7145	400 AMP SKID MTD	25 HP E	1,578	1.38		0.12	0.21	0.82		8				
7150	600 AMP SKID MTD	36 HP E	2,331	2.00		0.18	0.31	1.19		15				
GASOLINE ENGINE DRIVE														
7160	200 AMP W/1 AXLE TRLR	37 HP G	2,068	5.52		0.18	0.34	3.87		11				
7165	250 AMP W/1 AXLE TRLR	65 HP G	3,451	9.62		0.29	0.56	6.79		17				
7170	300 AMP W/1 AXLE TRLR	65 HP G	3,503	9.65		0.30	0.58	6.79		17				
7175	400 AMP W/1 AXLE TRLR	69 HP G	4,051	10.35		0.35	0.66	7.21						

TABLE 3-1 HOURLY EQUIPMENT OWNERSHIP AND OPERATING EXPENSE (CONTINUED)

UNIT NO.	EQUIPMENT	VALUE	TOTAL HOURLY RATES		ADJUSTABLE ELEMENTS				CNT					
			CONDITION	STAND-BY	AVERAGE COND.		SEVERE COND.							
					AVERAGE	SEVERE	OWNER-SHIP	FUEL						
WELDERS (CONT'D)														

GASOLINE ENGINE DRIVE (CONT'D)														
7180	650 AMP W/2 AXLE TRLR	85 HP G	6,240	13.19		0.53	1.02	8.88						
DIESEL ENGINE DRIVE														
7190	350 AMP W/2 AXLE TRLR	55 HP D	5,350	5.23		0.46	0.88	2.71						
7195	400 AMP W/2 AXLE TRLR	55 HP D	6,992	5.80		0.59	1.14	2.71						
RECTIFIER AC-DC COMB.														
7205	250 AMP W/SHOP RUNNING GEAR	19 HP E	807	0.98		0.07	0.11	0.63						
7210	300 AMP W/SHOP RUNNING GEAR	24 HP E	966	1.23		0.08	0.14	0.79						
7215	500 AMP W/SHOP RUNNING GEAR	30 HP E	1,381	1.57		0.11	0.19	0.99						
7220	650 AMP W/SHOP RUNNING GEAR	42 HP E	1,666	2.14		0.13	0.23	1.39						




TABLE 3-2. EQUIPMENT AGE ADJUSTMENT FACTORS FOR OWNERSHIP COSTS

The "Age Adjustment Factors for Ownership Costs" in TABLE 3-2 are used when the age of an item of equipment is other than the age of the equipment listed in TABLE 3-1. The factors given in TABLE 3-2 are multiplied by the hourly ownership costs shown in TABLE 3-1 and result in an ownership rate adjusted for the actual age of the equipment being considered. When the "life" of the equipment has exceeded the economic service life given in APPENDIX D, the age will be determined as given in paragraph 3-2.f.

Examples: Assume that a two-year old 50-ton truck crane listed in TABLE 3-1 has a total hourly rate of \$40.00 per hour and an ownership rate of \$19.00 per hour.

A. If an equivalent crane owned by a contractor had been purchased new in 1976, the total hourly rate can be determined as follows:

Total Hourly Rate	= \$40.00/Hr.
Ownership Rate	(-) \$19.00/Hr.
Ownership Adjusted for Age: (Ownership Rate)	
x (Age Adj. Factor) = (\$19.00) x (.79)	= (+) \$15.01/Hr.
Adjusted Total Hourly Rate	= \$36.01/Hr.

B. If an equivalent crane owned by a Contractor had been purchased new in 1968, the total hourly rate can be determined as follows:

Total Hourly Rate	= \$40.00/Hr.
Ownership Rate	(-) \$19.00/Hr.
Ownership adjusted for Age: (Ownership Rate)	
x (Oldest Age Adj. Factor) = (\$19.00) x (.40)	= (+) \$ 7.60/Hr.
Adjusted Total Hourly Rate	= \$28.60/Hr.

C. If an equivalent crane, manufactured in 1968, had been purchased used in 1976 by the Contractor, the crane is over-age and the rate computation would be identical to Example B.

D. If an equivalent crane, manufactured in 1976, had been purchased used in 1980 by the Contractor, the used crane is not over-age and the rate computation would be identical to Example A.

TABLE 3-2. EQUIPMENT AGE ADJUSTMENT FACTORS FOR OWNERSHIP COSTS (CONTINUED)

KEY NO.	TYPE OF EQUIPMENT	YEAR PURCHASED NEW											
		1981	1980	1979	1978	1977	1976	1975	1974	1973	1972	1971	
15	AGGREGATE SPREADERS	1.21	1.10	1.00	0.91	0.84	0.77	0.73					
30	AIR COMPRESSORS	1.20	1.10	1.00	0.87	0.83	0.74	0.73					
45	AIR TOOLS & EQUIP, TAMPERS ETC	1.21	1.10	1.00									
60	ASPHALT DISTRIBUTORS	1.22	1.11	1.00	0.90	0.83	0.76	0.72					
65	ASPHALT AND CONCRETE PAVERS	1.21	1.10	1.00	0.91	0.84	0.77	0.73					
	BACKHOE (SEE KEY NO. 570-601)												
75	BROOMS	1.28	1.15	1.00	0.90	0.81	0.75	0.69					
80	BRUSH CHIPPERS	1.28	1.15	1.00	0.90	0.81	0.75	0.69					
90	BUCKETS, CLAMSHELL & DRAGLINE	1.37	1.21	1.00	0.89	0.81	0.74	0.62					
95	BUCKETS, CONCRETE	1.37	1.21	1.00	0.89	0.81	0.74	0.62					
105	CONCRETE OR GROUT PUMP	1.29	1.15	1.00	0.89	0.81	0.74						
120	CONCRETE GUNITE EQUIPMENT & FLUID GROUTERS	1.28	1.15	1.00	0.90	0.81	0.75	0.69					
125	CONCRETE MIXERS & BUGGIES	1.28	1.15	1.00	0.90	0.81	0.75	0.69					
135	CONCRETE VIBRATORS	1.21	1.10	1.00									
140	COMPACTORS, MANUALLY OPERATED CRANE, CRAWLER TYPE	1.21	1.10	1.00	0.87	0.83							
150	0 THRU 25 TON	1.23	1.12	1.00	0.91	0.84	0.78	0.71	0.57	0.47			
165	OVER 25 TON THRU 50 TON	1.23	1.12	1.00	0.91	0.84	0.78	0.71	0.58	0.48	0.46	0.44	
170	OVER 50 TON THRU 150 TON	1.22	1.12	1.00	0.91	0.84	0.79	0.72	0.59	0.49	0.48	0.46	0.43
180	OVER 150 TON	1.22	1.11	1.00	0.91	0.85	0.79	0.72	0.59	0.50	0.48	0.46	0.41
	DRAGLINE & CLAMSHELL, CRAWLER MOUNTED												
185	0 THRU 1 CY	1.23	1.12	1.00	0.91	0.84	0.78	0.71	0.56	0.47			
190	OVER 1 CY THRU 2-1/2 CY	1.23	1.12	1.00	0.91	0.84	0.78	0.71	0.58	0.48	0.46	0.44	
195	OVER 2-1/2 CY THRU 5 CY	1.22	1.12	1.00	0.91	0.84	0.79	0.72	0.59	0.49	0.48	0.46	0.43
196	OVER 5 CY	1.22	1.11	1.00	0.91	0.85	0.79	0.72	0.59	0.50	0.48	0.46	0.41
200	CRANES, HYDRAULIC, SELF- PROPELLED	1.23	1.12	1.00	0.91	0.84	0.78	0.71	0.57	0.48	0.46	0.44	
	CRANES & HYD. EXC., TRK MTD												
210	UNDER 26 T. (THRU 1 CY)	1.23	1.12	1.00	0.91	0.84	0.78	0.71	0.58	0.48	0.46	0.44	
225	26 THRU 65 T (1 TH 2-1/2 CY)	1.22	1.12	1.00	0.91	0.84	0.79	0.72	0.58	0.49	0.48	0.45	0.43
230	66 THRU 125 T	1.22	1.11	1.00	0.91	0.85	0.79	0.72	0.59	0.50	0.48	0.46	0.41
240	OVER 125 T	1.22	1.11	1.00	0.91	0.85	0.79	0.73	0.60	0.51	0.49	0.47	0.42
255	DRILL, AUGER	1.29	1.16	1.00	0.92	0.83	0.80	0.75					
270	DRILL, BLAST HOLE	1.29	1.16	1.00	0.92	0.83	0.80	0.75					
300	DRILL, CORE	1.29	1.16	1.00	0.92	0.83	0.80	0.75					
315	DRILL, ROTARY TO 11" DIA. HOLE	1.27	1.15	1.00	0.93	0.84	0.81	0.76	0.66	0.60	0.56	0.55	
330	DRILL, ROTARY OVER 11" DIA.	1.26	1.14	1.00	0.93	0.85	0.81	0.77	0.68	0.61	0.58	0.57	0.54
345	DRILL, ROTARY OVER 11" DIA., ELECTRIC	1.26	1.14	1.00	0.93	0.85	0.81	0.77	0.68	0.61	0.58	0.57	0.51
375	FORK LIFTS	1.28	1.15	1.00	0.90	0.81	0.75	0.69					
390	GRADERS	1.26	1.13	1.00	0.92	0.82	0.75	0.69	0.54	0.44			
420	GENERATORS	1.39	1.24	1.00	0.95	0.87	0.83	0.72					
435	HOIST	1.28	1.15	1.00	0.90	0.81	0.75	0.69					
	HYD. EXCAVATOR (SEE KEY NO. 570-601)												

TABLE 3-2. EQUIPMENT AGE ADJUSTMENT FACTORS FOR OWNERSHIP COSTS (CONTINUED)

KEY NO.	TYPE OF EQUIPMENT	YEAR PURCHASED NEW											
		1981	1980	1979	1978	1977	1976	1975	1974	1973	1972	1971	
440	LIGHT PLANTS	1.30	1.16	1.00	0.89	0.80	0.73	0.66					
450	LOADER, BELT	1.30	1.16	1.00	0.89	0.80	0.73	0.66					
460	LOADER, FRONT END & LOADER F/E WITH BACKHOE, CRAWLER TYPE LOADER, WHEEL TYPE	1.27	1.14	1.00	0.91	0.83	0.75	0.70					
465	0 THRU 225 HP	1.30	1.15	1.00	0.90	0.80	0.73	0.68					
470	OVER 225 HP	1.28	1.14	1.00	0.90	0.81	0.74	0.70	0.56	0.47			
475	LOADER, FRONT END WITH BACKHOE, WHEEL TYPE	1.29	1.15	1.00	0.90	0.80	0.73	0.69					
480	PILE EXTRACTOR, PILE HAMMER & HYDRAULIC IMPACTOR	1.30	1.15	1.00	0.89	0.80							
485	PIPELAYERS PUMP, GROUT (SEE KEY NO. 105)	1.27	1.13	1.00	0.89	0.79	0.71	0.66	0.51	0.41			
495	PUMP, WATER, ENGINE DRIVE	1.28	1.15	1.00	0.90	0.81	0.75	0.69					
500	PUMP, WATER, ELECTRIC DRIVE	1.28	1.15	1.00	0.90	0.81	0.75	0.69					
510	RIPPERS	1.27	1.13	1.00	0.89	0.79	0.71						
525	ROLLERS, EXCEPT VIB. ROLLERS	1.25	1.12	1.00	0.89	0.78	0.71	0.67					
530	ROLLERS, VIBRATORY	1.27	1.12	1.00	0.88	0.77	0.70						
440	SCRAPERS, STANDARD	1.25	1.13	1.00	0.92	0.82	0.76	0.69					
542	SCRAPERS, TANDEM POWERED SCRAPERS, ELEVATING	1.25	1.13	1.00	0.92	0.82	0.76	0.69					
545	0 THRU 200 HP	1.25	1.13	1.00	0.92	0.82	0.76	0.69					
550	OVER 200 HP	1.25	1.13	1.00	0.92	0.82	0.76	0.69					
555	SCRAPERS, TRACTOR DRAWN SHOVELS, BACKHOES, & HYDRAULIC EXCAVATORS CRAWLER MOUNTED	1.25	1.13	1.00	0.92	0.82	0.76	0.70	0.55	0.45			
570	0 THRU 1 CY	1.24	1.12	1.00	0.91	0.83	0.78	0.70	0.56				
585	OVER 1 CY THRU 2-1/2 CY	1.23	1.12	1.00	0.91	0.84	0.78	0.71	0.57	0.47			
595	OVER 2-1/2 CY THRU 5 CY	1.23	1.12	1.00	0.91	0.84	0.79	0.72	0.58	0.49	0.47	0.45	
600	OVER 5 CY	1.22	1.12	1.00	0.91	0.84	0.79	0.72	0.59	0.49	0.48	0.46	0.43
601	OVER 2-1/2 CY ELECTRIC TRACTOR, CRAWLER TYPE	1.22	1.11	1.00	0.91	0.85	0.79	0.73	0.60	0.51	0.49	0.47	0.44
615	0 THRU 225 HP	1.28	1.14	1.00	0.88	0.78	0.69	0.63					
620	226 HP THRU 425 HP (PER UNIT FOR TANDEM TRACTORS)	1.27	1.13	1.00	0.89	0.79	0.71	0.66	0.51	0.41			
625	OVER 425 HP	1.25	1.12	1.00	0.89	0.80	0.72	0.67	0.53	0.44	0.42		
630	TRACTOR, BLADES, PUSH BLOCKS, PUSH PLATES & CLEARING BLADES	1.26	1.13	1.00	0.89	0.79	0.71	0.66					
645	TRACTOR, WHEEL TYPE	1.30	1.15	1.00	0.89	0.80	0.72	0.66					
650	TRENCHER	1.30	1.16	1.00	0.92	0.81	0.64	0.53					
655	TRAILERS, BOTTOM DUMP AND END DUMP	1.30	1.15	1.00	0.89	0.80	0.73	0.67					
660	TRAILERS, FLATBED, LO-BOY AND TILT	1.31	1.16	1.00	0.89	0.79	0.72	0.66					
	TRUCK ACCESSORIES FOR CHASSIS MOUNTING												

TABLE 3-2. EQUIPMENT AGE ADJUSTMENT FACTORS FOR OWNERSHIP COSTS (CONTINUED)

KEY NO.	TYPE OF EQUIPMENT	YEAR PURCHASED NEW											
		1981	1980	1979	1978	1977	1976	1975	1974	1973	1972	1971	
670	DUMP BODIES	1.29	1.15	1.00	0.89	0.81	0.74						
675	ALL OTHER ACCESSORIES	1.29	1.15	1.00	0.89	0.81	0.74						
	TRUCK, HIGHWAY												
690	0 THRU 10,000 GVW	1.24	1.12	1.00	0.90	0.82	0.75						
695	OVER 10,000 THRU 30,000 GVW	1.24	1.12	1.00	0.90	0.82	0.75						
705	OVER 30,000 GVW	1.24	1.12	1.00	0.90	0.82	0.75						
720	TRUCK, OFF-HIGHWAY	1.29	1.16	1.00	0.90	0.83	0.78	0.73	0.56	0.45			
765	WAGON, BOTTOM DUMP & WATER	1.29	1.16	1.00	0.90	0.83	0.78	0.73	0.56	0.45			
780	WAGON, REAR DUMP	1.29	1.16	1.00	0.90	0.83	0.78	0.73	0.56	0.45			
785	WATER BLASTER	1.30	1.15	1.00	0.89	0.80							
795	WATER TANKS	1.29	1.15	1.00	0.89	0.81	0.74						
810	WELDERS	1.33	1.17	1.00	0.88	0.78							
811	WELDERS ELECTRIC POWER	1.31	1.16	1.00	0.89	0.79	0.72						

TABLE 3-3. EQUIPMENT AGE ADJUSTMENT FACTORS FOR STANDBY COSTS

The "Age Adjustment Factors for Standby Costs" in TABLE 3-3 are used when the age of a piece of equipment is other than the age of the equipment listed in TABLE 3-1. The factors given in TABLE 3-3 are multiplied by the hourly standby costs shown in TABLE 3-1 and result in a standby rate adjusted for the actual age of the equipment being considered. When the "life" of the equipment has exceeded the economic service life given in APPENDIX D, the age will be determined as given in paragraph 3-2.f.

Example: Assume that a two-year old 50-ton truck crane listed in TABLE 3-1 has an hourly standby rate of \$11.00 per hour. If an equivalent crane owned by a Contractor had been purchased new in 1976, the hourly standby rate can be determined as follows:

Hourly Standby Rate	= \$11.00/Hr.
Standby Adjusted for Age (Standby Rate) x (Age Adj. Factor)	
= (\$11.00) x (.82)	= \$ 9.02/Hr.

TABLE 3-3. EQUIPMENT AGE ADJUSTMENT FACTORS FOR STANDBY COSTS (CONTINUED)

KEY NO.	TYPE OF EQUIPMENT	YEAR PURCHASED NEW											
		1981	1980	1979	1978	1977	1976	1975	1974	1973	1972	1971	1970
15	AGGREGATE SPREADERS	1.18	1.09	1.00	0.92	0.86	0.80	0.77					
30	AIR COMPRESSORS	1.17	1.08	1.00	0.89	0.86	0.79	0.77					
45	AIR TOOLS & EQUIP., TAMPERS ETC	1.19	1.09	1.00									
60	ASPHALT DISTRIBUTORS	1.18	1.09	1.00	0.92	0.87	0.81	0.77					
65	ASPHALT AND CONCRETE PAVERS BACKHOE (SEE KEY NO. 570-601)	1.18	1.09	1.00	0.92	0.86	0.80	0.77					
75	BROOMS	1.24	1.13	1.00	0.91	0.84	0.78	0.73					
80	BRUSH CHIPPERS	1.24	1.13	1.00	0.91	0.84	0.78	0.73					
90	BUCKETS, CLAMSHELL & DRAGLINE	1.32	1.18	1.00	0.91	0.84	0.78	0.67					
95	BUCKETS, CONCRETE	1.32	1.18	1.00	0.91	0.84	0.78	0.67					
105	CONCRETE OR GROUT PUMP	1.25	1.13	1.00	0.91	0.83	0.78						
120	CONCRETE GUNITE EQUIPMENT & FLUID GROUTERS	1.24	1.13	1.00	0.91	0.84	0.78	0.73					
125	CONCRETE MIXERS & BUGGIES	1.24	1.13	1.00	0.91	0.84	0.78	0.73					
135	CONCRETE VIBRATORS	1.19	1.09	1.00									
140	COMPACTORS, MANUALLY OPERATED CRANE, CRAWLER TYPE	1.18	1.09	1.00	0.89	0.85							
150	0 THRU 25 TON	1.20	1.10	1.00	0.92	0.86	0.81	0.75	0.63	0.55			
165	OVER 25 TON THRU 50 TON	1.20	1.10	1.00	0.92	0.86	0.81	0.75	0.63	0.55	0.54	0.52	
170	OVER 50 TON THRU 150 TON	1.19	1.10	1.00	0.92	0.86	0.82	0.76	0.64	0.56	0.54	0.53	0.50
180	OVER 150 TON DRAGLINE & CLAMSHELL, CRAWLER MOUNTED	1.19	1.10	1.00	0.92	0.87	0.82	0.76	0.64	0.56	0.55	0.53	0.51
185	0 THRU 1 CY	1.20	1.10	1.00	0.92	0.86	0.81	0.75	0.62	0.54			
190	OVER 1 CY THRU 2-1/2 CY	1.20	1.10	1.00	0.92	0.86	0.81	0.75	0.63	0.55	0.54	0.52	
195	OVER 2-1/2 CY THRU 5 CY	1.19	1.10	1.00	0.92	0.86	0.82	0.76	0.64	0.56	0.54	0.53	0.50
196	OVER 5 CY	1.19	1.10	1.00	0.92	0.87	0.82	0.76	0.64	0.56	0.55	0.53	0.51
200	CRANES, HYDRAULIC, SELF- PROPELLED	1.19	1.10	1.00	0.92	0.86	0.82	0.76	0.64	0.56	0.55	0.53	
	CRANES & HYD. EXC., TRK MTD												
210	UNDER 26 T. (THRU 1 CY)	1.20	1.10	1.00	0.92	0.86	0.81	0.75	0.63	0.55	0.54	0.52	
225	26 THRU 65 T (1 TH 2-1/2 CY)	1.19	1.10	1.00	0.92	0.86	0.82	0.76	0.64	0.56	0.54	0.53	0.50
230	66 THRU 125 T	1.19	1.10	1.00	0.92	0.87	0.82	0.76	0.64	0.57	0.55	0.53	0.51
240	OVER 125 T	1.19	1.10	1.00	0.92	0.87	0.82	0.76	0.65	0.57	0.55	0.54	0.51
255	DRILL, AUGER	1.25	1.13	1.00	0.93	0.86	0.83	0.79					
270	DRILL, BLAST HOLE	1.25	1.13	1.00	0.93	0.86	0.83	0.79					
300	DRILL, CORE	1.25	1.13	1.00	0.93	0.86	0.83	0.79					
315	DRILL, ROTARY TO 11" DIA. HOLE	1.23	1.13	1.00	0.94	0.86	0.83	0.80	0.71	0.65	0.62	0.61	
330	DRILL, ROTARY OVER 11" DIA.	1.23	1.12	1.00	0.94	0.87	0.84	0.80	0.72	0.66	0.63	0.62	0.60
345	DRILL, ROTARY OVER 11" DIA., ELECTRIC	1.23	1.12	1.00	0.94	0.87	0.84	0.80	0.72	0.66	0.63	0.62	0.57
375	FORK LIFTS	1.24	1.13	1.00	0.91	0.84	0.78	0.73					
390	GRADERS	1.21	1.11	1.00	0.93	0.85	0.80	0.74	0.62	0.54			
420	GENERATORS	1.31	1.19	1.00	0.96	0.90	0.87	0.78					
435	HOIST HYD. EXCAVATOR (SEE KEY NO. 570-601)	1.24	1.13	1.00	0.91	0.84	0.78	0.73					

TABLE 3-3. EQUIPMENT AGE ADJUSTMENT FACTORS FOR STANDBY COSTS (CONTINUED)

KEY NO.	TYPE OF EQUIPMENT	YEAR PURCHASED, M/Y											
		1981	1980	1979	1978	1977	1976	1975	1974	1973	1972	1971	
440	LIGHT PLANTS	1.24	1.12	1.00	0.91	0.84	0.79	0.73					
450	LOADER, BELT	1.24	1.12	1.00	0.91	0.84	0.79	0.73					
460	LOADER, FRONT END & LOADER F/E WITH BACKHOE, CRAWLER TYPE	1.22	1.12	1.00	0.92	0.86	0.79	0.75					
	LOADER, WHEEL TYPE												
465	0 THRU 225 HP	1.24	1.12	1.00	0.91	0.83	0.78	0.74					
470	OVER 225 HP	1.24	1.12	1.00	0.92	0.84	0.78	0.74	0.63	0.55			
475	LOADER, FRONT END WITH BACKHOE, WHEEL TYPE	1.24	1.12	1.00	0.91	0.83	0.78	0.74					
480	PILE EXTRACTOR, PILE HAMMER & HYDRAULIC IMPACTOR	1.26	1.13	1.00	0.91	0.83							
485	PIPELAYERS PUMP, GROUT (SEE KEY NO. 105)	1.22	1.11	1.00	0.91	0.83	0.76	0.71	0.60	0.51			
495	PUMP, WATER, ENGINE DRIVE	1.24	1.13	1.00	0.91	0.84	0.78	0.73					
500	PUMP, WATER, ELECTRIC DRIVE	1.24	1.13	1.00	0.91	0.84	0.78	0.73					
510	RIPPERS	1.23	1.11	1.00	0.90	0.82	0.75						
525	ROLLERS, EXCEPT VIB. ROLLERS	1.22	1.10	1.00	0.91	0.81	0.75	0.71					
530	ROLLERS, VIBRATORY	1.22	1.10	1.00	0.90	0.81	0.75						
540	SCRAPERS, STANDARD	1.22	1.11	1.00	0.93	0.85	0.79	0.74					
542	SCRAPERS, TANDEM POWERED SCRAPERS, ELEVATING	1.22	1.11	1.00	0.93	0.85	0.79	0.74					
545	0 THRU 200 HP	1.22	1.11	1.00	0.93	0.85	0.79	0.74					
550	OVER 200 HP	1.22	1.11	1.00	0.93	0.85	0.79	0.74					
555	SCRAPERS, TRACTOR DRAWN SHOVELS, BACKHOES, & HYDRAULIC EXCAVATORS CRAWLER MOUNTED	1.21	1.11	1.00	0.93	0.85	0.80	0.74	0.62	0.53			
570	0 THRU 1 CY	1.20	1.11	1.00	0.92	0.86	0.81	0.74	0.62				
585	OVER 1 CY THRU 2-1/2 CY	1.20	1.10	1.00	0.92	0.86	0.81	0.75	0.63	0.55			
595	OVER 2-1/2 CY THRU 5 CY	1.20	1.10	1.00	0.92	0.86	0.82	0.75	0.64	0.56	0.54	0.52	
600	OVER 5 CY	1.19	1.10	1.00	0.92	0.86	0.82	0.76	0.64	0.56	0.54	0.53	0.50
601	OVER 2-1/2 CY ELECTRIC TRACTOR, CRAWLER TYPE	1.19	1.10	1.00	0.92	0.87	0.82	0.76	0.65	0.57	0.55	0.54	0.51
615	0 THRU 225 HP	1.22	1.11	1.00	0.91	0.82	0.76	0.71					
620	226 HP THRU 425 HP (PER UNIT FOR TANDEM TRACTORS)	1.22	1.11	1.00	0.91	0.83	0.76	0.71	0.60	0.51			
625	OVER 425 HP	1.22	1.11	1.00	0.91	0.83	0.76	0.72	0.60	0.52	0.50		
630	TRACTOR, BLADES, PUSH BLOCKS, PUSH PLATES & CLEARING BLADES	1.23	1.11	1.00	0.91	0.82	0.75	0.70					
645	TRACTOR, WHEEL TYPE	1.26	1.13	1.00	0.90	0.83	0.77	0.71					
650	TRENCHER	1.26	1.13	1.00	0.93	0.83	0.69	0.60					
655	TRAILERS, BOTTOM DUMP AND END DUMP	1.24	1.12	1.00	0.91	0.84	0.78	0.73					
660	TRAILERS, FLATBED, LO-BOY AND TILT TRUCK ACCESSORIES FOR CHASSIS MOUNTING	1.24	1.12	1.00	0.91	0.84	0.79	0.73					

EP 1110-1-B
(Vol. 2)
15 Jun 81

TABLE 3-3. EQUIPMENT AGE ADJUSTMENT FACTORS FOR STANDBY COSTS (CONTINUED)

KEY NO.	TYPE OF EQUIPMENT	YEAR PURCHASED NEW											
		1981	1980	1979	1978	1977	1976	1975	1974	1973	1972	1971	1970
670	DUMP BODIES	1.25	1.13	1.00	0.91	0.83	0.78						
675	ALL OTHER ACCESSORIES	1.25	1.13	1.00	0.91	0.83	0.78						
	TRUCK, HIGHWAY												
690	0 THRU 10,000 GVW	1.20	1.10	1.00	0.92	0.84	0.78						
695	OVER 10,000 THRU 30,000 GVW	1.20	1.10	1.00	0.92	0.84	0.78						
705	OVER 30,000 GVW	1.20	1.10	1.00	0.92	0.84	0.78						
720	TRUCK, OFF-HIGHWAY	1.25	1.14	1.00	0.92	0.86	0.81	0.77	0.63	0.53			
765	WAGON, BOTTOM DUMP & WATER	1.25	1.14	1.00	0.92	0.86	0.81	0.77	0.63	0.53			
780	WAGON, REAR DUMP	1.25	1.14	1.00	0.92	0.86	0.81	0.77	0.63	0.53			
785	WATER BLASTER	1.26	1.13	1.00	0.91	0.83							
795	WATER TANKS	1.25	1.13	1.00	0.91	0.83	0.78						
810	WELDERS	1.26	1.14	1.00	0.90	0.82							
811	WELDERS ELECTRIC POWER	1.25	1.13	1.00	0.91	0.83	0.78						

TABLE 3-4. SHIFT ADJUSTMENT FACTORS FOR OWNERSHIP COSTS

The "Shift Adjustment Factors" in TABLE 3-4 are used when the working hours per week are greater than 40 hours per week. The factors given in TABLE 3-4 are multiplied by the adjusted hourly ownership cost (if adjusted for age) and result in an ownership rate adjusted for working hours other than 40 hours per week.

Example: Assume that the truck crane in Example A of TABLE 3-2 is to be worked 10 hours per day, 6 days per week. The total hourly rate for this piece of equipment can be determined as follows:

Total Hourly Rate (adjusted for age)	= \$36.01/Hr.
Ownership Rate (adjusted for age)	(-) \$15.01/Hr.
Ownership Adjusted for Work Hours (Ownership Rate) x (Work Hr Adj. Factor)	
= (\$15.01) x (.82)	= (+) \$12.31/Hr.
Adjusted Total Hourly Rate	= <u>\$33.31/Hr.</u>

EP 1110-1-B
(Vol. 2)
15 Jun 81

TABLE 3-4 SHIFT ADJUSTMENT FACTORS FOR OWNERSHIP COSTS (CONTINUED)

Service Life From APP. D	Equipment Usage - Hours per Week												
	40	45	48	54	60	66	72	80	90	100	110	120	140
4,000	1.00	0.97	0.96	0.94	0.92	0.91	0.89	0.88	0.87	0.86	0.85	0.84	0.83
6,000	1.00	0.97	0.95	0.92	0.90	0.88	0.86	0.85	0.83	0.82	0.80	0.79	0.78
8,000	1.00	0.96	0.94	0.91	0.88	0.86	0.84	0.82	0.80	0.78	0.77	0.76	0.74
9,000	1.00	0.96	0.94	0.90	0.87	0.85	0.83	0.81	0.78	0.77	0.75	0.74	0.72
10,000	1.00	0.95	0.93	0.89	0.86	0.84	0.82	0.79	0.77	0.75	0.74	0.72	0.71
11,000	1.00	0.95	0.93	0.89	0.86	0.83	0.81	0.78	0.76	0.74	0.72	0.71	0.69
12,000	1.00	0.95	0.92	0.88	0.85	0.82	0.80	0.77	0.75	0.73	0.71	0.70	0.68
13,000	1.00	0.95	0.92	0.88	0.84	0.81	0.79	0.76	0.74	0.72	0.70	0.68	0.66
14,000	1.00	0.95	0.92	0.87	0.84	0.81	0.78	0.76	0.73	0.71	0.69	0.67	0.65
15,000	1.00	0.94	0.92	0.87	0.83	0.80	0.78	0.75	0.72	0.70	0.68	0.66	0.64
16,000	1.00	0.94	0.91	0.86	0.83	0.79	0.77	0.74	0.71	0.69	0.67	0.65	0.63
18,000	1.00	0.94	0.91	0.86	0.82	0.78	0.76	0.73	0.69	0.67	0.65	0.63	0.61
20,000	1.00	0.94	0.90	0.85	0.81	0.77	0.74	0.71	0.68	0.66	0.63	0.62	0.59
22,000	1.00	0.93	0.90	0.85	0.80	0.77	0.74	0.70	0.67	0.64	0.62	0.60	0.57
50,000	1.00	0.91	0.87	0.80	0.74	0.70	0.66	0.62	0.57	0.54	0.51	0.49	0.45

APPENDIX A

REFERENCES

1. Bureau of Labor Statistics, U.S. Department of Labor, "Producer Prices and Price Indexes." Published by the U.S. Government Printing Office, Washington, D.C. 20402.
2. Office of Construction Industry Services, Labor Management Services Administration, U.S. Department of Labor, "Handbook of Wages and Benefits for Construction Unions," January 1980, 200 Constitution Avenue, N.W., Washington, D.C. 20216.
3. Caterpillar Tractor Company, "Caterpillar Performance Handbook," Tenth Edition, 100 N.E. Adams Street, Peoria, Illinois 61629.
4. Caterpillar Tractor Company, "Fundamentals of Earthmoving," July 1975, 100 N.E. Adams Street, Peoria, Illinois 61629.
5. Equipment Guide Book Company, "Green Guide," Volume I and II, P.O. Box 10113, Palo Alto, California 94303.
6. Equipment Guide Book Company, "Green Guide for Off-Highway Trucks and Trailers," P.O. Box 10113, Palo Alto, California 94303.
7. Havers, J.A. and Stubbs, F.W., Jr., "Handbook of Heavy Construction," Second Edition. Published by McGraw-Hill Book Company, New York, New York.
8. Nichols, H.L., Jr., "Moving the Earth," Third Edition. Published by North Castle Books, Greenwich, Connecticut 06830.
9. Pay Line Division, International Harvester, "Earthmoving Principles," November 1975, 600 Woodfield, Schaumburg, Illinois 60196.
10. Power Crane and Shovel Association, Bureau of Construction Industry Manufacturers Association, "Operating Cost Guide," 1976, 111 E. Wisconsin Avenue, Milwaukee, Wisconsin 53202.

EP 1110-1-8
(Vol. 2)
15 Jun 81

APPENDIX A

REFERENCES (Cont'd)

11. Terex Division, General Motors Corporation, "Production and Cost Estimating of Material Movement with Earthmoving Equipment," 1975 Revision, Hudson, Ohio 44236.
12. Construction Equipment Manufacturer's Price Lists.
13. Defense Acquisition Regulation (DAR).

APPENDIX B

AREA FACTORS

The area factors given in this Appendix were used to compute the hourly equipment rates shown in TABLE 3-1.

State Sales Tax Rate:	4.0 %
Working Hours Per Year:	1,500 Hrs/Yr
Labor Adjustment Factor (LAF):	0.990
Electricity Cost Per Kilowatt-Hour:	0.055 /Kw-Hr
Gasoline Cost Per Gallon:	\$ 1.290 /Gal.
Diesel Cost Per Gallon (Off-Road Use):	\$ 1.050 /GAL.
Diesel Cost Per Gallon (On-Road Use):	\$ 1.150 /Gal.
Freight Rates:	
0 thru 24,000 lbs.	\$ 2.870 /Cwt.
over 24,000 thru 50,000 lbs.	\$ 2.550 /Cwt.
over 50,000 thru 60,000 lbs.	\$ 1.580 /Cwt.
over 60,000 thru 80,000 lbs.	\$ 1.480 /Cwt.
over 80,000 thru 9999,900 lbs.	\$ 1.400 /Cwt.

APPENDIX C

GUIDE FOR SELECTING OPERATING CONDITIONS

EQUIPMENT TYPE	AVERAGE	SEVERE
Cranes, Crawler Truck	Lift less than rated capacity, intermittent duty.	Continuous lift near rated capacity, excessive swing, abrasive materials, sloped surfaces.
Depreciation Period	13,000 - 22,000 Hrs.	11,000 - 20,000 Hrs.
Shovels	Gravels, silts, well broken rock, lift less than rated capacity.	Extremely abrasive tough materials, lifting near rated capacity, impact breakout.
Depreciation Period	11,000 - 22,000 Hrs.	9,000 - 20,000 Hrs.
Draglines	Gravels, silts, pull and lift less than rated capacity.	Highly abrasive materials, impact breakout, continuous load near rated capacity.
Depreciation Period	12,000 - 20,000 Hrs.	10,000 - 18,000 Hrs.
Backhoes	Clay, earth digging, no breakout impact, easy continuous or intermittent duty.	Rock work, pull near rated capacity, uneven surface, impact breakout, abrasive materials.
Depreciation Period	11,000 - 22,000 Hrs.	9,000 - 20,000 Hrs.

GUIDE FOR SELECTING OPERATING CONDITIONS (Continued)

EQUIPMENT TYPE	AVERAGE	SEVERE
Tractors, Crawler Type	Production dozing in clays, sands, gravels and talus rock. Push-loading scrapers, borrow pit ripping, most landclearing and skidding applications. Medium impact conditions.	Heavy rock ripping. Tandem ripping. Pushloading and dozing in hard rock. Continuous high impact conditions.
Depreciation Period	10,000 - 14,000 Hrs.	8,000 - 12,000 Hrs.
Tractors, Wheel-Type	Production dozing, pushloading in clays, sands, silts, loose gravels. Shovel cleanup.	Production dozing in rock. Push-loading in rocky, bouldery borrow pits. High impact conditions.
Depreciation Period	10,000 Hrs.	8,000 Hrs.
Scrapers, Self-Propelled	Varying loading and haul road conditions. Long and short hauls. Adverse and favorable grades. Some impact. Typical road-building use on a variety of jobs.	High impact condition, such as loading ripped rock. Overloading. Continuous high total resistance conditions. Rough haul roads.
Depreciation Period	10,000 Hrs.	8,000 Hrs.
Trucks, Off Highway	Varying loading and haul road conditions. Typical road-building use on a variety of jobs.	Consistently poor haul road conditions. Extreme overloading. Over-sized loading equipment.
Depreciation Period	12,000 Hrs.	10,000 Hrs.

GUIDE FOR SELECTING OPERATING CONDITIONS (Continued)

EQUIPMENT TYPE	AVERAGE	SEVERE
Trucks, Highway	Varying loading and road conditions. Typical construction use on a variety of jobs.	Consistently poor road conditions. Extreme overloading.
Depreciation Period	8,000 Hrs.	6,000 Hrs.
Loaders, Front End Wheel Type	Continuous truck loading from stockpile. Low to medium density materials in properly sized bucket. Hopper charging in low to medium rolling resistance. Loading from bank in good digging.	Loading shot rock (large loaders). Handling high density materials with counterweighted machine. Steady loading from very tight banks. Continuous work on rough or very soft surfaces.
Depreciation Period	10,000 - 12,000 Hrs.	8,000 - 10,000 Hrs.
Loaders, Front End Crawler Type	Bank excavation, intermittent ripping, basement digging of natural bed clays, sands, silts, gravels. Some traveling. Steady full throttle operations.	Loading shot rock, cobbles. High density materials in standard bucket. Continuous work on rock surfaces. Large amount of ripping of tight, rocky materials. High impact conditions.
Depreciation Period	10,000 Hrs.	8,000 Hrs.

EP 1110-1-8

(Vol. 2)

15 Jun 81

GUIDE FOR SELECTING OPERATING CONDITIONS (Continued)

<u>EQUIPMENT TYPE</u>	<u>AVERAGE</u>	<u>SEVERE</u>
Motor Graders	Haul road maintenance. Road construction, ditching. Loose fill spreading. Land- forming, landleveling. Summer road mainten- ance with medium to heavy winter snow removal. Elevating grader use.	Maintenance of hard packed roads with embedded rock. Heavy fill spread- ing. Ripping- scarifying of asphalt or con- crete. Continuous high load factor. High impact.
Depreciation Period	12,000 Hrs.	10,000 Hrs.

APPENDIX D

EQUIPMENT HOURLY EXPENSE CALCULATION FACTORS

TABLE LEGEND

C - OPERATING CONDITIONS
A - AVERAGE CONDITIONS
S - SEVERE CONDITIONS
LFE - EQUIP LIFE 1000 HRS
SLV - EQUIP SALVAGE
HP - HORSEPOWER FACTOR (%)
FOG-E - ELECTRIC FOG (%)
FOG-G - GAS FOG (%)

TABLE LEGEND

FOG-D - DIESEL FOG (%)
E - ELECT. CONSUMPTION (KW/HP/HR)
G - GAS CONSUMPTION (GAL/HP/HR)
D - DIESEL CONSUMPTION (GAL/HP/HR)
F-TIRE - FRONT TIRE FACTOR (%)
D-TIRE - DRIVE TIRE FACTOR (%)
T-TIRE - TRAIL TIRE FACTOR (%)
RPR - REPAIR FACTOR (%)

EQUIPMENT HOURLY EXPENSE CALCULATION FACTORS (CONTINUED)

KEY NO.	TYPE OF EQUIPMENT	C	LFE	SLV	EQUIPMENT POWER				CARRIER POWER				FOD			TIRES			
					HP	E	G	D	HP	E	G	D	E	G	D	F	D	T	
15	AGGREGATE SPREADERS	A	10	20	50 .000	.051	.030		0 .000	.000	.000		0	24	24	77	73	99	80
30	AIR COMPRESSORS	A	10	25	65 .000	.066	.038		0 .000	.000	.000		0	32	28	0	0	0	90
45	AIR TOOLS & EQUIP, TAMERS ETC	A	4	20	0 .000	.000	.000		0 .000	.000	.000		0	0	0	0	0	0	100
60	ASPHALT DISTRIBUTORS	A	10	30	65 .000	.066	.038		0 .000	.000	.000		0	32	28	60	44	79	85
65	ASPHALT AND CONCRETE PAVERS	A	10	20	65 .000	.066	.038		0 .000	.000	.000		0	32	28	65	40	70	90
BACKHOE (SEE KEY NO. 570-601)																			
75	BROOMS	A	10	20	65 .000	.066	.000		0 .000	.000	.000		0	24	0	77	73	99	90
80	BRUSH CHIPPERS	A	10	20	65 .000	.066	.038		0 .000	.000	.000		0	32	28	0	0	0	90
90	BUCKETS, CLAMSHELL & DRAGLINE	A	10	20	0 .000	.000	.000		0 .000	.000	.000		0	0	0	0	0	0	80
90		S	8	20	0 .000	.000	.000		0 .000	.000	.000		0	0	0	0	0	0	90
95	BUCKETS, CONCRETE	A	10	20	0 .000	.000	.000		0 .000	.000	.000		0	0	0	0	0	0	80
105	CONCRETE OR GROUT PUMP	A	8	20	95 .000	.097	.056		0 .000	.000	.000		0	32	28	0	0	0	90
120	CONCRETE GUNITE EQUIPMENT & FLUID GROUTERS	A	10	20	0 .000	.000	.000		0 .000	.000	.000		0	0	0	0	0	0	80
125	CONCRETE MIXERS & BUGGIES	A	10	20	70 .700	.071	.041		0 .000	.000	.000		50	32	28	0	0	0	80
135	CONCRETE VIBRATORS	A	4	20	0 .000	.000	.000		0 .000	.000	.000		0	0	0	0	0	0	250
140	COMPACTORS, MANUALLY OPERATED	A	6	20	90 .000	.091	.053		0 .000	.000	.000		0	24	24	0	0	0	100
CRANE, CRAWLER TYPE																			
150	0 THRU 25 TON	A	13	20	40 .000	.041	.024		0 .000	.000	.000		0	18	18	0	0	0	50
150		S	11	20	0 .000	.053	.031		0 .000	.000	.000		0	18	18	0	0	0	55
165	OVER 25 TON THRU 50 TON	A	15	20	40 .000	.041	.024		0 .000	.000	.000		0	18	18	0	0	0	60
165		S	13	20	0 .000	.053	.031		0 .000	.000	.000		0	18	18	0	0	0	65
170	OVER 50 TON THRU 150 TON	A	18	20	40 .000	.041	.024		0 .000	.000	.000		0	18	18	0	0	0	70
170		S	16	20	0 .000	.053	.031		0 .000	.000	.000		0	18	18	0	0	0	75
180	OVER 150 TON	A	20	20	40 .000	.041	.024		0 .000	.000	.000		0	18	18	0	0	0	80
180		S	18	20	0 .000	.053	.031		0 .000	.000	.000		0	18	18	0	0	0	85

EQUIPMENT HOURLY EXPENSE CALCULATION FACTORS (CONTINUED)

KEY NO.	TYPE OF EQUIPMENT	C	LFE	SLV	EQUIPMENT POWER				CARRIER POWER				FOG			TIRES			RPR
					HP	E	G	D	HP	E	G	D	E	G	D	F	G	D	
DRAGLINE & CLAMSHELL, CRAWLER MOUNTED																			
185	0 THRU 1 CY	A	12	20	50 .000	.051	.030		0 .000	.000	.000		0	18	18	0	0	0	70
185		S	10	20	0 .000	.066	.039		0 .000	.000	.000		0	18	18	0	0	0	80
190	OVER 1 CY THRU 2-1/2 CY	A	15	20	50 .000	.051	.030		0 .000	.000	.000		0	18	18	0	0	0	80
190		S	13	20	0 .000	.066	.039		0 .000	.000	.000		0	18	18	0	0	0	90
195	OVER 2-1/2 CY THRU 5 CY	A	18	20	50 .000	.051	.030		0 .000	.000	.000		0	18	18	0	0	0	90
195		S	16	20	0 .000	.066	.039		0 .000	.000	.000		0	18	18	0	0	0	100
196	OVER 5 CY	A	20	20	50 .000	.051	.030		0 .000	.000	.000		0	18	18	0	0	0	100
196		S	18	20	0 .000	.066	.039		0 .000	.000	.000		0	18	18	0	0	0	110
200	CRANES, HYDRAULIC, SELF-PROPELLED	A	16	25	65 .000	.066	.038		0 .000	.000	.000		0	32	28	95	90	0	70
CRANES & HYD. EXC., TRK MTD																			
210	UNDER 26 T. (THRU 1 CY)	A	15	20	65 .000	.066	.038		10 .000	.010	.006		0	30	26	95	90	0	50
210		S	13	20	0 .000	.086	.049		0 .000	.013	.007		0	30	26	86	73	0	55
225	26 THRU 65 T (1 TH 2-1/2 CY)	A	18	20	65 .000	.066	.038		10 .000	.010	.006		0	30	26	95	90	0	60
225		S	16	20	0 .000	.086	.049		0 .000	.013	.007		0	30	26	86	73	0	65
230	66 THRU 125 T	A	20	20	65 .000	.066	.038		10 .000	.010	.006		0	30	26	95	90	0	70
230		S	18	20	0 .000	.086	.049		0 .000	.013	.007		0	30	26	86	73	0	75
240	OVER 125 T	A	22	20	65 .000	.066	.038		10 .000	.010	.006		0	30	26	95	80	0	80
240		S	20	20	0 .000	.086	.049		0 .000	.013	.007		0	30	26	86	73	0	85
255	DRILL, AUGER	A	10	20	50 .000	.051	.030		0 .000	.000	.000		0	32	28	67	57	0	90
270	DRILL, BLAST HOLE	A	10	20	0 .000	.000	.000		0 .000	.000	.000		0	0	0	0	0	0	90
300	DRILL, CORE	A	10	20	80 .000	.081	.047		0 .000	.000	.000		0	16	24	0	0	0	90
315	DRILL, ROTARY TO 11" DIA. HOLE	A	15	20	80 .000	.081	.047		10 .000	.010	.006		0	24	24	67	57	0	90
330	DRILL, ROTARY OVER 11" DIA.	A	20	20	80 .000	.081	.047		0 .000	.000	.000		0	24	24	67	57	0	90
345	DRILL, ROTARY OVER 11" DIA., ELECTRIC	A	20	20	70 .700	.000	.000		0 .000	.000	.000		50	0	0	0	0	0	45

EQUIPMENT HOURLY EXPENSE CALCULATION FACTORS (CONTINUED)

KEY NO.	TYPE OF EQUIPMENT	C	LFE	SLV	EQUIPMENT POWER				CARRIER POWER				FDS			TIRES			RPR
					HP	E	G	D	HP	E	G	D	E	G	D	F	D	T	
375	FORK LIFTS	A	10	20	65 .000	.066	.038		0 .000	.000	.000		0	24	24	86	77	0	90
390	GRADERS	A	12	25	60 .000	.061	.035		0 .000	.000	.000		0	16	29	86	68	0	70
390		S	10	25	0 .000	.079	.046		0 .000	.000	.000		0	16	29	60	39	0	75
420	GENERATORS	A	10	30	65 .000	.066	.038		0 .000	.000	.000		0	24	24	0	0	0	80
420		S	9	30	0 .000	.086	.049		0 .000	.000	.000		0	24	24	0	0	0	90
435	HOIST	A	10	20	65 .000	.066	.038		0 .000	.000	.000		0	24	24	0	0	0	90
	HYD. EXCAVATOR (SEE KEY NO. 570-601)																		
440	LIGHT PLANTS	A	10	30	95 .000	.097	.056		0 .000	.000	.000		0	24	24	0	0	0	80
450	LOADER, BELT	A	10	30	65 .000	.066	.038		0 .000	.000	.000		0	32	28	26	0	99	90
450		S	8	30	0 .000	.086	.049		0 .000	.000	.000		0	32	28	16	0	99	100
460	LOADER, FRONT END & LOADER F/E	A	10	25	70 .000	.071	.041		0 .000	.000	.000		0	32	38	0	0	0	110
460	WITH BACKHOE, CRAWLER TYPE	S	8	25	0 .000	.092	.054		0 .000	.000	.000		0	32	38	0	0	0	120
	LOADER, WHEEL TYPE																		
465	0 THRU 225 HP	A	10	25	65 .000	.066	.038		0 .000	.000	.000		0	32	40	60	40	0	70
465		S	8	25	0 .000	.086	.049		0 .000	.000	.000		0	32	40	41	19	0	75
470	OVER 225 HP	A	12	20	65 .000	.066	.038		0 .000	.000	.000		0	32	30	60	40	0	80
470		S	10	20	0 .000	.086	.049		0 .000	.000	.000		0	32	30	41	19	0	85
475	LOADER, FRONT END WITH BACKHOE, WHEEL TYPE	A	10	25	65 .000	.066	.038		0 .000	.000	.000		0	32	28	60	40	0	70
475		S	8	25	0 .000	.086	.049		0 .000	.000	.000		0	32	28	41	19	0	75
480	PILE EXTRACTOR, PILE HAMMER & HYDRAULIC IMPACTOR	A	6	20	65 .000	.066	.038		0 .000	.000	.000		0	32	28	0	0	0	90
485	PIPELAYERS	A	12	25	35 .000	.000	.021		0 .000	.000	.000		0	0	32	0	0	0	40
485		S	10	25	0 .000	.000	.027		0 .000	.000	.000		0	0	32	0	0	0	45
	PUMP, GROUT (SEE KEY NO. 105)																		
495	PUMP, WATER, ENGINE DRIVE	A	10	20	90 .000	.091	.053		0 .000	.000	.000		0	32	38	0	0	0	80
500	PUMP, WATER, ELECTRIC DRIVE	A	10	20	90 .900	.000	.000		0 .000	.000	.000		45	0	0	0	0	0	40
510	RIPPERS	A	8	20	0 .000	.000	.000		0 .000	.000	.000		0	0	0	0	0	0	80
510		S	6	20	0 .000	.000	.000		0 .000	.000	.000		0	0	0	0	0	0	90

EQUIPMENT HOURLY EXPENSE CALCULATION FACTORS (CONTINUED)

KEY NO.	TYPE OF EQUIPMENT	C	LFE	SLV	EQUIPMENT POWER				CARRIER POWER				FOD			TIRES			
					HP	E	G	D	HP	E	G	D	E	G	D	F	D	T	
525	ROLLERS, EXCEPT VIB. ROLLERS	A	10	20	65 .000	.066	.038		65 .000	.066	.038		0	24	24	76	64	99	90
530	ROLLERS, VIBRATORY	A	B	25	90 .000	.091	.053		90 .000	.091	.053		0	24	24	76	64	99	130
540	SCRAPERS, STANDARD	A	10	20	60 .000	.000	.035		60 .000	.000	.035		0	0	27	58	31	65	70
540		S	8	20	0 .000	.000	.046		0 .000	.000	.046		0	0	27	40	19	27	75
542	SCRAPERS, TANDEM POWERED	A	10	20	62 .000	.000	.037		62 .000	.000	.037		0	0	25	58	25	60	70
542		S	8	20	0 .000	.000	.048		0 .000	.000	.048		0	0	25	40	18	40	75
	SCRAPERS, ELEVATING																		
545	0 THRU 200 HP	A	10	20	66 .000	.000	.039		66 .000	.000	.039		0	0	34	0	25	60	85
545		S	8	20	0 .000	.000	.051		0 .000	.000	.051		0	0	34	0	18	40	90
550	OVER 200 HP	A	10	20	66 .000	.000	.039		66 .000	.000	.039		0	0	24	0	25	60	75
550		S	8	20	0 .000	.000	.051		0 .000	.000	.051		0	0	24	0	18	40	80
555	SCRAPERS, TRACTOR DRAWN	A	12	20	0 .000	.000	.000		0 .000	.000	.000		0	0	0	58	0	65	70
555		S	10	20	0 .000	.000	.000		0 .000	.000	.000		0	0	0	40	0	45	75
	SHOVELS, BACKHOES, & HYDRAULIC EXCAVATORS CRAWLER MOUNTED																		
570	0 THRU 1 CY	A	11	20	60 .000	.061	.035		0 .000	.000	.000		0	18	18	0	0	0	80
570		S	9	20	0 .000	.079	.046		0 .000	.000	.000		0	18	18	0	0	0	90
585	OVER 1 CY THRU 2-1/2 CY	A	13	20	60 .000	.061	.035		0 .000	.000	.000		0	18	18	0	0	0	90
585		S	11	20	0 .000	.079	.046		0 .000	.000	.000		0	18	18	0	0	0	100
595	OVER 2-1/2 CY THRU 5 CY	A	16	20	60 .000	.061	.035		0 .000	.000	.000		0	18	18	0	0	0	100
595		S	14	20	0 .000	.079	.046		0 .000	.000	.000		0	18	18	0	0	0	110
600	OVER 5 CY	A	18	20	60 .000	.061	.035		0 .000	.000	.000		0	18	18	0	0	0	110
600		S	16	20	0 .000	.079	.046		0 .000	.000	.000		0	18	18	0	0	0	120
601	OVER 2-1/2 CY ELECTRIC	A	22	20	50 .500	.000	.000		0 .000	.000	.000		25	0	0	0	0	0	80
601		S	20	20	0 .650	.000	.000		0 .000	.000	.000		25	0	0	0	0	0	90
	TRACTOR, CRAWLER TYPE																		
615	0 THRU 225 HP	A	10	30	70 .000	.000	.041		0 .000	.000	.000		0	0	32	0	0	0	90
615		S	8	30	0 .000	.000	.054		0 .000	.000	.000		0	0	32	0	0	0	100
620	226 HP THRU 425 HP (PER UNIT FOR TANDEM TRACTORS)	A	12	25	70 .000	.000	.041		0 .000	.000	.000		0	0	25	0	0	0	100
620		S	10	25	0 .000	.000	.054		0 .000	.000	.000		0	0	25	0	0	0	110

EQUIPMENT HOURLY EXPENSE CALCULATION FACTORS (CONTINUED)

KEY NO.	TYPE OF EQUIPMENT	C	LFE	SLV	EQUIPMENT POWER				CARRIER POWER				FOG			TIRES			RPR
					HP	E	G	D	HP	E	G	D	E	G	D	F	D	T	
625	OVER 425 HP	A	14	20	70 .000 .000 .041	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	0	22	0	0	0	115
625		S	12	20	0 .000 .000 .054	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	0	22	0	0	0	125
630	TRACTOR, BLADES, PUSH BLOCKS,	A	10	20	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	0	0	0	0	0	80
630	PUSH PLATES & CLEARING BLADES	S	8	20	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	0	0	0	0	0	90
645	TRACTOR, WHEEL TYPE	A	10	20	65 .000 .066 .038	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	24	28	60	44	0	60
645		S	8	20	0 .000 .086 .049	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	24	28	46	17	0	65
650	TRENCHER	A	10	20	65 .000 .066 .038	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	32	28	60	40	0	90
650		S	8	20	0 .000 .086 .049	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	32	28	41	19	0	100
655	TRAILERS, BOTTOM DUMP AND	A	10	25	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	0	0	0	0	61	80
655	END DUMP	S	8	25	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	0	0	0	0	44	90
660	TRAILERS, FLATBED, LO-BOY AND TILT	A	10	30	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	0	0	0	0	61	80
	TRUCK ACCESSORIES FOR CHASSIS MOUNTING																		
670	DUMP BODIES	A	8	20	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	0	0	0	0	0	80
670		S	6	20	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	0	0	0	0	0	90
675	ALL OTHER ACCESSORIES	A	8	20	65 .000 .066 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	32	0	0	0	0	80
	TRUCK, HIGHWAY																		
690	0 THRU 10,000 GVW	A	8	20	20 .000 .020 .012	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	32	28	47	40	0	70
690		S	6	20	0 .000 .026 .015	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	32	28	33	20	0	80
695	OVER 10,000 THRU 30,000 GVW	A	8	20	40 .000 .041 .024	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	32	28	47	40	0	70
695		S	6	20	0 .000 .053 .031	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	32	28	33	20	0	80
705	OVER 30,000 GVW	A	8	20	60 .000 .061 .035	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	32	28	47	40	61	70
705		S	6	20	0 .000 .079 .046	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	32	28	33	20	44	80
720	TRUCK, OFF-HIGHWAY	A	12	20	40 .000 .000 .024	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	0	33	58	36	65	70
720		S	10	20	0 .000 .000 .031	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	0	33	40	22	45	80
765	WAGON, BOTTOM DUMP & WATER	A	12	20	65 .000 .066 .038	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	24	28	58	36	65	60
765		S	10	20	0 .000 .086 .049	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	24	28	40	22	45	65
780	WAGON, REAR DUMP	A	12	20	65 .000 .066 .038	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	24	28	58	36	65	70
780		S	10	20	0 .000 .086 .049	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	24	28	40	22	45	80
785	WATER BLASTER	A	6	20	95 .000 .097 .056	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0 .000 .000 .000	0	24	28	0	0	0	110

EQUIPMENT HOURLY EXPENSE CALCULATION FACTORS (CONTINUED)

KEY NO.	TYPE OF EQUIPMENT	C	LFE	SLV	EQUIPMENT POWER				CARRIER POWER				FOG			TIRES			RPR
					HP	E	G	D	HP	E	G	D	E	G	D	F	D	T	
795	WATER TANKS	A	8	20	0 ,000 ,000 ,000				0 ,000 ,000 ,000				0	0	0	0	0	0	80
810	WELDERS	A	6	30	80 ,000 ,081 ,047				0 ,000 ,000 ,000				0	24	24	0	0	0	90
811	WELDERS ELECTRIC POWER	A	8	30	60 ,600 ,000 ,000				0 ,000 ,000 ,000				30	0	0	0	0	0	40

APPENDIX E

SALVAGE AND REPAIR INDEXES FOR CONSTRUCTION EQUIPMENT

CATEGORY	YEAR PURCHASE NEW												
	1981	1980	1979	1978	1977	1976	1975	1974	1973	1972	1971	1970	1969
	AGE IN YEARS												
0	1	2	3	4	5	6	7	8	9	10	11	12	
Air Equipment	1787	1649	1521	1354	1295	1186	1165	1028	935	920	929	936	918
Asphalt & Concrete Paving Equipment	2498	2306	2111	1941	1815	1686	1610	1451	1304	1263	1235	1163	1091
Buckets	4357	3879	3280	2963	2738	2520	2175	1838	1430	1370	1316	1188	1062
Cranes, Draglines & Clamshells - Crawler & Truck Mounted	3044	2787	2512	2301	2138	2010	1843	1522	1305	1260	1212	1147	1090
Drills	2496	2267	1993	1858	1699	1638	1559	1373	1249	1184	1160	1115	1052
Generators	3153	2858	2390	2301	2128	2053	1839	1456	1316	1283	1243	1188	1089
Graders, Motor	3289	2994	2687	2492	2259	2109	1956	1604	1361	1244	1208	1152	1101
Loaders, Track	2918	2663	2376	2188	2024	1859	1755	1445	1249	1219	1184	1135	1100
Loaders, Wheel	3260	2940	2606	2375	2156	2002	1907	1584	1362	1317	1261	1197	1144
Pile Driving Equipment	3200	2892	2562	2329	2135	1989	1852	1523	1307	1257	1218	1159	1104
Rollers	3248	2926	2653	2396	2139	1983	1872	1556	1328	1279	1230	1178	1082
Scrapers	3289	2994	2687	2492	2259	2109	1956	1604	1361	1244	1208	1152	1101
Shovels, Backhoes & Hydraulic Excavators	3044	2787	2512	2301	2138	2010	1843	1522	1305	1260	1212	1147	1090
Tractors, Crawler & Attachments	3393	3061	2750	2482	2247	2053	1916	1573	1329	1281	1236	1181	1133
Tractors, Wheel	3257	2927	2578	2319	2125	1956	1813	1498	1288	1251	1211	1152	1109
Trenchers	3503	3153	2772	2580	2300	1894	1633	1527	1384	1316	1284	1207	1113
Trucks, Highway	2537	2320	2108	1934	1775	1646	1524	1369	1230	1211	1185	1114	1062
Trucks & Wagons - Off Highway	3270	2960	2588	2364	2196	2081	1965	1568	1315	1293	1245	1190	1135
All Other Equipment	3200	2892	2562	2329	2135	1989	1852	1523	1307	1257	1218	1159	1104

TO EXTEND AGE: Add difference between 11th & 12th year for each additional year.

APPENDIX F

TIRE LIFE AND TIRE WEAR FACTORS

F-1. The tire wear factors used in this pamphlet are listed in APPENDIX D. Using the methods and tables in "Production and Cost Estimating of Material Movement with Earthmoving Equipment" by Terex Division of General Motors, the "useful life" of a new tire is the product of factors from Group A through Group G multiplied by the appropriate maximum tire life from TABLE F-1. A sample computation of the tire wear factors for off-highway haul units is given in Figure F-1.

No.	Condition	Factor	
		Average	Severe
A	Maintenance	1.0	1.0
B	Speeds	0.8	0.9
C	Curves	1.0	0.85
D	Surface Condition	0.9	0.65
E	Loads	0.9	0.9
		<u>0.648</u>	<u>0.448</u>
F	Wheel Positions		
	Trailing (T-Tire)	1.0	1.0
	Front (F-Tire)	0.9	0.9
	Driver (D-Tire)		
	(Rear Dump)	0.7	0.7
	(Bottom Dump)	0.7	0.7
	(Self-Propelled Scrapers)	0.6	0.6
G	Grades		
	Driver	<u>0.80</u>	<u>0.7</u>
TOTALS			
	Trailing (T-Tire)	0.65	0.45
	Front (F-Tire)	0.58	0.40
	Driver (D-Tire)		
	(Rear Dump)	0.36	0.22
	(Bottom Dump)	0.36	0.22
	(Self-Propelled Scrapers)	0.31	0.19

Figure F-1. Rear and Bottom Wagons (Off-Highway), Scrapers

EP 1110-1-8

(Vol. 2)

15 Jun 81

TABLE F-1. Maximum Tire Life.

Bias Ply Tires:

Off-highway E4, L4, & L5	7,000 Hours
All other bias ply tires	5,000 Hours

Radial Ply Tires:

Off-highway RL4	8,300 Hours
All other radial ply tires	6,000 Hours

APPENDIX G

EQUIPMENT EXTRAS

In addition to features required for safety, the following extras have been included with the major equipment listed in this pamphlet when they are not included with the basic cost and are offered by the manufacturer:

(1) Crane, Crawler-Mounted.

- (a) Power load lowering.
- (b) Independent swing and travel.
- (c) Third drum.
- (d) Torque converter (Machines 25 ton or larger.)
- (e) One-half maximum boom length (Machines 60 ton or smaller.)
- (f) Maximum boom length (Machines larger than 60 ton.)
- (g) Counterweight.

(2) Dragline and Clamshell, Crawler-Mounted.

- (a) Power load lowering.
- (b) Independent swing and travel.
- (c) Third drum.
- (d) Torque converter (Machines 1-1/2 C.Y. or larger.)
- (e) Approximately one-half maximum boom length.
- (f) Counterweight.

(3) Backhoe and Shovel, Crawler-Mounted.

- (a) Power load lowering.
- (b) Torque converter (Machines 1-1/2 C.Y. or larger.)
- (c) Counterweight.

(4) Truck Crane Less than 25 Ton.

- (a) Power load lowering.
- (b) Third drum.
- (c) Mechanical outriggers w/screw jacks.
- (d) Power steering.
- (e) Maximum boom length.
- (f) Counterweight.

(5) Truck Crane 25 Ton and Larger.

- (a) Power load lowering.
- (b) Third drum.
- (c) Hydraulic outriggers w/screw jacks.
- (d) Torque converter when available.
- (e) Power steering.
- (f) Diesel engines.
- (g) Maximum boom length.
- (h) Counterweight.

(6) Grader.

- (a) Enclosed operators' cab.
- (b) Scarifier.
- (c) Front wheel lean.
- (d) Power circle.
- (e) Hydraulic shift and tilt moldboard.
- (f) End bits.
- (g) Alternator.

(7) Belt Loader.

- (a) Power unit.
- (b) Head pulley clutch and backstop.
- (c) Belt cleaner and belt installing equip.
- (d) King pin attachment.

(8) Loader 1-1/2 C.Y. and Larger.

- (a) Reversible fan blade.
- (b) Guard, power train.
- (c) Automatic bucket positioner.
- (d) Counterweight.
- (e) Rock buckets (Machines 4 C.Y. or larger.)
- (f) Alternator.

(9) Scraper.

- (a) Control single lever.
- (b) Reversible fan blade.
- (c) Flood light.
- (d) Alternator.
- (e) Guards, power train.

(10) Tractor, Crawler.

- (a) Hydraulic controls for ripper and blade.
- (b) Guards.
- (c) Reversible fan blade.
- (d) Alternator.
- (e) Hook, front pull.
- (f) Track Grousers (Severe service for units over 200 hp.)
- (g) Blades include counterweights where required.

(11) Tractor, Wheel Dozer.

- (a) Hydraulic controls for ripper and blade.
- (b) Guards.
- (c) Reversible fan blade.
- (d) Alternator.
- (e) Blade.
- (f) Counterweight.

(12) Trucks, Off-Highway.

- (a) No-spin differential.
- (b) Tacograph.
- (c) Engine and transmission guards.
- (d) Body liners.